



Encinitas pradu 1 bedroom

CONTACT SDG&E REGARDING ELECTRIC SERVICE TO THIS DETACHED ADU.
ANY EXISTING SERVICE UPGRADE OR NEW SERVICE FOR THE ADU
WILL REQUIRE A SEPARATE PERMIT FROM THE CITY OF ENCINITAS.




construction codes:

2022	CALIFORNIA	BUILDING CODE	TITLE 24	PART 2, V. 1&2
2022	CALIFORNIA	RESIDENTIAL CODE	TITLE 24	PART 2.5
2022	CALIFORNIA	ELECTRICAL CODE	TITLE 24	PART 3
2022	CALIFORNIA	MECHANICAL CODE	TITLE 24	PART 4
2022	CALIFORNIA	PLUMBING CODE	TITLE 24	PART 5
2022	CALIFORNIA	ENERGY CODE	TITLE 24	PART 6
2022	CALIFORNIA	FIRE CODE	TITLE 24	PART 9
2022	CALIFORNIA	GREEN CODE	TITLE 24	PART 11

PROJECT SHALL COMPLY WITH THE 2022 CALIFORNIA BUILDING CODE WHICH ADOPTS:
2021 IRC, 2021 UMC, 2021 UPC & 2020 NEC.

vicinity map:

SITE ADDRESS =



NOT TO SCALE

COMMUNITY =

slope analysis:

- IF THE SITE IS IN THE SPECIAL SITE OVERLAY WITH NATURAL STEEP SLOPES (25% IN GRADIENT OR STEEPER) ARE PRESENT ON SITE, PROVIDE A SLOPE ANALYSIS AS PER EMC 30.34.030.A&B AND SHOW ANY REQUIRED FUEL MODIFICATION BUFFERS OVERLAID ON THE SITE PLAN.

required for plan check submittal and permits

ITEM	✓	COMPLETED OR ACKNOWLEDGED
SHEET a0.0	<input type="checkbox"/>	PROJECT DATA SHEET INFORMATION FILLED OUT
SHEET a0.1	<input type="checkbox"/>	CHECKLIST SHEET INFORMATION FILLED OUT
SHEET a0.3	<input type="checkbox"/>	CAL GREEN CHECKLIST FILLED OUT
SHEET a0.4	<input type="checkbox"/>	SITE PLAN DRAFTED & NOTED PER SITE PLAN INFORMATION CHECKLIST AND SAMPLE SITE PLAN DIAGRAM
SHEET a0.5	<input type="checkbox"/>	AVERAGE LOT SLOPE DIAGRAM DRAFTED & NOTED WITH TABLE FILLED OUT
SHEET a2.0	<input type="checkbox"/>	ELECTRICAL UTILITY TABLE FILLED OUT & ADU ELECTRICAL PANEL LOAD CALCULATION REVISED IF MODIFIED
T24 SHEETS	<input type="checkbox"/>	UPDATED REPORT WITH PROJECT OWNER & LOCATION IF NEEDED
SEPARATE PERMIT	<input type="checkbox"/>	COUNTY PERMIT (IF APPLICABLE)
SEPARATE PERMIT	<input type="checkbox"/>	CONTACT SDG&E PROJECT PLANNING FOR WORK ORDER, GET CITY PERMIT FOR ELECTRICAL UPGRADE (IF APPLICABLE)
DEFERRED SUBMITTAL	<input type="checkbox"/>	PHOTOVOLTAIIC PERMIT OR EXISTING PV SYSTEM REPORT, SEE DEFERRED SUBMITTAL TABLE ON THIS SHEET
DEFERRED SUBMITTAL	<input type="checkbox"/>	FIRE SPRINKLER PERMIT (IF APPLICABLE), SEE FIRE SPRINKLER CHECKLIST ON SHEET a0.1
BY OWNER	<input type="checkbox"/>	SOIL REPORT FOR ADU OVER 500 SF WITH FOUNDATION DESIGN REVIEW APPROVAL LETTER
BY OWNER	<input type="checkbox"/>	PROPERTY GRANT DEED WITH LEGAL DESCRIPTION
BY OWNER	<input type="checkbox"/>	RESIDENTIAL BUILDING RECORD FROM COUNTY ASSESSOR
BY OWNER	<input type="checkbox"/>	AGENCY LETTER IF OWNER IS USING AGENT FOR PLAN CHECK & PERMIT PROCESSING
CITY FORM	<input type="checkbox"/>	BUILDING PERMIT CALCULATIONS - BUILDING SQUARE FOOTAGE
CITY FORM	<input type="checkbox"/>	CONSTRUCTION & DEMO WASTE MANAGEMENT PLAN
CITY FORM	<input type="checkbox"/>	STORMWATER INTAKE FORM & STANDARD SWQMP
CITY FORM	<input type="checkbox"/>	LOCAL GREEN BUILDING ORDINANCE CHECKLIST
CITY FORM	<input type="checkbox"/>	BUILDING ACKNOWLEDGMENT OWNER-BUILDER
CITY FORM	<input type="checkbox"/>	HOUSING DEVELOPMENT TRACKING FORM
CITY FORM	<input type="checkbox"/>	ADU COVENANT PROVIDED BY PROJECT PLANNER NOTARIZED AND OWNER CHECK PROVIDED FOR COUNTY RECORDER
CITY FORM	<input type="checkbox"/>	WATER DISTRICT SIGN OFF
CITY FORM	<input type="checkbox"/>	SEWER DISTRICT OR COUNTY HEALTH SEPTIC SIGN OFF
CITY FORM	<input type="checkbox"/>	SCHOOL DISTRICT(S) SIGN OFF IF ADU IS 500 SF OR GREATER

energy requirement notes:

- CONNECTION TO A PHOTOVOLTAIC SOLAR SYSTEM IS REQUIRED FOR THIS PROJECT. SOLAR SYSTEM IS A DEFERRED SUBMITTAL.
- REQUIRED SPECIAL FEATURES:
 - WHOLE HOUSE FAN
 - EXPOSED SLAB FLOOR IN CONDITIONED ZONE
 - VARIABLE CAPACITY HEAT PUMP COMPLIANCE OPTION (VERIFICATION DETAILS FROM VCHP STAFF REPORT, APPENDIX B, AND RA3)
 - NORTHWEST ENERGY EFFICIENCY ALLIANCE (NEEA) RATED HEAT PUMP WATER HEATER, SPECIFIC BRAND/MODEL, OR EQUAL, MUST BE INSTALLED
- HERS FEATURE SUMMARY
 - BUILDING LEVEL VERIFICATIONS:
 - INDOOR AIR QUALITY VENTILATION
 - KITCHEN RANGE HOOD
 - WHOLE HOUSE FAN AIRFLOW AND FAN EFFICACY
 - COOLING SYSTEM VERIFICATIONS:
 - VERIFIED EER/SEER2
 - VERIFIED SEER/SEER2
 - VERIFIED REFRIGERANT CHARGE
 - AIRFLOW IN HABITABLE ROOMS(SC3.1.4.1.7)
 - HEATING SYSTEM VERIFICATIONS:
 - VERIFIED HSPF
 - VERIFIED HEAT PUMP RATED HEATING CAPACITY
 - WALL MOUNTED THERMOSTAT IN ZONES GREATER THAN 150 SF(SC3.4.5)
 - DUCTLESS INDOOR UNITS LOCATED ENTIRELY IN CONDITIONED SPACE (SC3.1.4.1.8)
 - HVAC DISTRIBUTION SYSTEM VERIFICATIONS:
 - NONE
 - DOMESTIC HOT WATER SYSTEM VERIFICATIONS:
 - NONE

deferred submittals:

- A PHOTOVOLTAIC SYSTEM MEETING THE MINIMUM QUALIFICATION REQUIREMENTS AS SPECIFIED IN JOINT APPENDIX JA11, WITH ANNUAL ELECTRICAL OUTPUT EQUAL TO OR GREATER THAN THE DWELLING'S ANNUAL ELECTRICAL USAGE AS DETERMINED BY EQUATION 150.1-C, REQUIRED, ES SECTION 150.1(C)14.
- SUBMITTED DOCUMENTS FOR DEFERRED SUBMITTAL ITEMS SHALL BE SUBMITTED TO THE REGISTERED DESIGN PROFESSIONAL RESPONSIBLE CHARGE, WHO SHALL REVIEW THEM AND FORWARD THEM TO THE BUILDING OFFICIAL WITH A NOTATION INDICATING THAT THE DEFERRED SUBMITTAL DOCUMENTS HAVE BEEN REVIEWED AND THAT THEY HAVE BEEN FOUND TO BE IN GENERAL CONFORMANCE WITH THE DESIGN OF THE BUILDING. THE DEFERRED SUBMITTAL ITEMS SHALL NOT BE INSTALLED UNTIL THEIR DESIGN AND SUBMITTAL DOCUMENTS HAVE BEEN APPROVED BY THE BUILDING OFFICIAL.

solar system notes:

- A PHOTOVOLTAIC (PV) SOLAR SYSTEM IS REQUIRED AND A SEPARATE PERMIT WILL BE REQUIRED. THE PV SYSTEM MUST BE INSTALLED, OPERATIONAL AND HAVE FINAL APPROVAL PRIOR TO FINAL BUILDING INSPECTION AND APPROVAL FOR THE ADU.
- ADDITIONAL INFORMATION ABOUT THE PV SOLAR SYSTEM IS PROVIDED AT THE UTILITY PLAN ON SHEET a2.0 AND AT THE T-24 ENERGY REQUIREMENT SHEETS.

parking:

REQUIRED VEHICLE SPACES FOR EXISTING RESIDENCE	=	SPACES
REQUIRED VEHICLE SPACES FOR ADU	=	SPACES
REQUIRED SPACES ON SITE	=	TOTAL REQUIRED SPACES
PROVIDED ENCLOSED SPACES PROVIDED FOR EXISTING RESIDENCE	=	SPACES
PROVIDED UNENCLOSED SPACES PROVIDED FOR EXISTING RESIDENCE	=	SPACES
PROVIDED ENCLOSED SPACES PROVIDED FOR ADU	=	SPACES
PROVIDED UNENCLOSED SPACES PROVIDED FOR ADU	=	SPACES
VEHICLE SPACES PROVIDED ON SITE	=	TOTAL PROVIDED SPACES

conditions of use:

- THE PERMITTEE AND OWNER OF THE PROPERTY THAT IS THE SUBJECT OF THESE PLANS AGREES TO AND DOES BY UTILIZING THESE PLANS AND BY SUBMITTING THEM TO THE CITY OF ENCINITAS FOR PERMITTING DOES HEREBY RELEASE, HOLD HARMLESS AND AGREE TO INDEMNIFY AND DEFEND THE CITY OF ENCINITAS AND THE ARCHITECT, INCLUDING WITHOUT LIMITATION, ALL EMPLOYEES, OFFICERS, COUNCILMEMBERS, COMMISSIONERS, AND AGENTS AND/OR CONSULTANTS OF THE FOREGOING WHO PREPARED THESE CONSTRUCTION DOCUMENTS, AND EACH OF THEM, FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS, TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS. THE OWNER AND THE PERMITTEE, AND EACH OF THEM ACKNOWLEDGE AGREEING TO THIS COVENANT, IS A CONDITION PRECEDENT TO BEING ABLE TO UTILIZE THESE PLANS, AND, THAT WITHOUT THIS HOLD HARMLESS AND RELEASE, WOULD NOT BE ABLE BE ABLE TO UTILIZE THESE PLANS. FURTHER, OWNER AND PERMITTEE ACKNOWLEDGES THAT THE OWNER/PERMITTEE HAS BEEN ADVISED TO SEEK THE SERVICES OF ANY AND ALL CONSULTANTS, THEY CHOOSE, TO REVIEW THESE PLANS PRIOR TO USING THEM, TO SEEK ADVICE ON THE SUITABLY OF THESE PLANS FOR THEIR USE FOR THE INTENDED USE BY THE OWNER/PERMITTEE. THE INDEMNITY DOES NOT INCLUDE ANY LIABILITY ARISING OUT OF THE SOLE NEGLIGENCE OR WILLFUL MISCONDUCT OF THE PARTIES BEING INDEMNIFIED.
- BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.

scope of work:

PROJECT DESCRIPTION	=	ONE STORY DETACHED 1 BEDROOM ACCESSORY DWELLING UNIT (ADU)
PLAN CHECK NUMBER	=	BLDR-_____-YEAR

area calculations:

LOT AREAS			
GROSS LOT AREA	=	SF	
NET LOT AREA	=	SF	
(DEDUCTIONS PER CHAP 30.04)	=	(SF)	
BUILDING AREAS			
PROPOSED			
PROPOSED ADU	=	499 SF	
EXISTING			
EXISTING RESIDENCE BASEMENT	=	SF	
EXISTING RESIDENCE FIRST FLOOR	=	SF	
EXISTING RESIDENCE SECOND FLOOR	=	SF	
TOTAL EXISTING RESIDENCE	=	SF	
EXISTING GARAGE ATTACHED	=	SF	
EXISTING GARAGE DETACHED	=	SF	
EXISTING ACCESSORY STRUCTURE	=	SF	
FAR (FLOOR AREA RATIO)			
BULK FLOOR AREA (AS APPLIED TO FAR)			
FIRST FLOOR LIVING AREA	=	SF	
SECOND FLOOR LIVING AREA	=	SF	
GARAGE AREA EXCEEDING 400 SF	=	SF	
ADU LIVING AREA	=	SF	
ADU DEDUCTION	=	(SF - NTE 800 SF)	
ACCESSORY STRUCTURE TOTAL SF	=	SF	
OUTDOOR COVERED AREAS	=	SF - IF QUALIFY AS FAR	
TOTAL BULK FLOOR AREA	=	SF	
ALLOWED FAR			
FAR ALLOWED	=		
FAR ALLOWED x GROSS LOT AREA	=	SF	
PROPOSED FAR (TOTAL BULK FLOOR AREA / GROSS LOT AREA)	=	SF	
FAR PROPOSED	=		
LOT COVERAGE (LC)			
ALLOWED LOT COVERAGE (BY ZONE)	=	%	
TOTAL STRUCTURE FOOTPRINT AREA	=	SF(EXISTING + PROPOSED)	
CANTILEVERED FLOOR AREA ABOVE	=	SF	
ADU DEDUCTION	=	(SF - NTE 800 SF)	
LC SF / NET LOT AREA	=	. x 100 = %	
PROPOSED LOT COVERAGE	=	%	

agencies:

MUNICIPAL JURISDICTION	=	CITY OF ENCINITAS
ELEMENTARY SCHOOL DISTRICT	=	CARDIFF OR ENCINITAS
HIGH SCHOOL DISTRICT	=	SDUHS
SEWER DISTRICT	=	CARDIFF, ENCINITAS OR LEUCADIA
WATER DISTRICT	=	SAN DIEGUITO OR OLIVENHAIN
FIRE DEPARTMENT	=	ENCINITAS

sheet index:

Sheet #	Sheet Title
a0.0	PROJECT DATA
a0.1	CHECKLIST + SCHEDULE
a0.1F	VERY HIGH FIRE HAZARD SEVERITY ZONE
a0.2	GENERAL SPECIFICATIONS
a0.3	CAL GREEN CHECKLIST
a0.4	SITE PLAN + NOTES
a0.5	AVERAGE LOT SLOPE DIAGRAM
a1.0	FLOOR PLAN A + REVERSE A
a1.1	FLOOR PLAN B + FLOOR PLAN C
a2.0	UTILITY PLAN
a3.0	ROOF PLANS
a4.0	ELEVATION A + SECTION
a4.1	ELEVATION B + SECTION
a4.2	ELEVATION C + SECTION
a0.0	STRUCTURAL NOTES
s1.0	FOUNDATION PLANS
s2.0	ROOF FRAMING PLANS
s2.1	REVERSE ROOF FRAMING PLANS
d0.0	DETAILS
d0.1	DETAILS
d0.2	DETAILS
d0.3	DETAILS
d0.4	DETAILS
T-01 to T-04	ELEV A ENERGY REQUIREMENTS
T-01 to T-04	ELEV B ENERGY REQUIREMENTS
T-01 to T-04	ELEVATION C ENERGY REQUIREMENTS
T-05	HVAC SYSTEM ENERGY SUMMARIES

project data:

SITE ADDRESS (EXISTING RESIDENCE)	=	
SITE ADDRESS (PROPOSED ADU)	=	
PROPERTY OWNER (LEGAL)	=	
PROPERTY OWNER PHONE	=	
PROPERTY OWNER EMAIL	=	
PROPERTY OWNER ADDRESS	=	
APN	=	
LEGAL DESCRIPTION	=	
GENERAL ZONING DESIGNATION	=	RESIDENTIAL _____
ZONE	=	R-_____
ZONE OVERLAYS	=	
OCCUPANCY	=	R-3
CONSTRUCTION TYPE	=	V-B
ORIGINAL CONSTRUCTION YEAR	=	
EXISTING USE	=	___SINGLE OR ___MULTI FAMILY
PROPOSED USE	=	ACCESSORY DWELLING UNIT (ADU)
FIRE SPRINKLERS	=	SEE SELECTION ON SHEET a0.1
AVERAGE LOT SLOPE	=	_____% (FROM TABLE ON SHEET a0.5)
SLOPE ANALYSIS	=	SEE NOTE ON THIS SHEET

setback, height & story

SETBACKS	FRONT	INTERIOR SIDE	EXTERIOR SIDE	REAR
REQUIRED - STANDARD	FT	FT	FT	FT
EXISTING RESIDENCE	FT	FT	FT	FT
EXISTING ACCESSORY STRUCTURE	FT	FT	FT	FT
REQUIRED - ADU	FT	FT	FT	FT
PROPOSED - ADU	FT	FT	FT	FT
HEIGHT				
EXISTING RESIDENCE	=	FT		
EXISTING ACCESSORY STRUCTURE	=	FT		
PROPOSED ADU	=	FT		
STORY				
EXISTING RESIDENCE	=			
EXISTING ACCESSORY STRUCTURE	=			
PROPOSED ADU	=	1		

grading:

CUT	=	YD ³
FILL	=	YD ³
IMPORT	=	YD ³
EXPORT	=	YD ³
OVEREXCAVATION & RECOMPACTION	=	YD ³
MAXIMUM CUT HEIGHT	=	FT
MAXIMUM FILL HEIGHT	=	FT

landscape area:

EXISTING LANDSCAPE SITE AREA	=	SF, %
PROPOSED LANDSCAPE SITE AREA	=	SF, %
NON LANDSCAPE SITE AREA	=	SF, %
TOTAL SITE AREA	=	SF, 100%

impervious surfaces:

EXISTING IMPERVIOUS SITE AREA	=	SF, %
PROPOSED IMPERVIOUS SITE AREA	=	SF, %
NON IMPERVIOUS SITE AREA	=	SF, %
TOTAL SITE AREA	=	SF, 100%
CHANGE (+/-) IMPERVIOUS SITE AREA	=	SF, %

project team:

ARCHITECT	FIRM	DZN PARTNERS
	ADDRESS	662 2ND ST
	CITY, STATE, ZIP	ENCINITAS, CA 92024
	PHONE	(760) 753-2464
ENERGY CONSULTANT	EMAIL	B.SMITH@DZNPARTNERS.COM
	CONTACT	BART SMITH, AIA LEED AP
	FIRM	BEAR TECHNOLOGYS CONSULTANTING, INC
	ADDRESS	3431 DON ARTURO DR
ENGINEER	CITY, STATE, ZIP	CARLSBAD, CA 92010
	PHONE	(760) 635-2327
	EMAIL	WAYNE@BEARTECHCONSULTING.COM
	CONTACT	WAYNE SEWARD
	FIRM	PCSD ENGINEERING
	ADDRESS	3529 COASTVIEW COURT
	CITY, STATE, ZIP	CARLSBAD, CA 92010
	PHONE	(760) 207-1885
	EMAIL	PAUL.PCSD@GMAIL.COM
	CONTACT	PAUL CHRISTENSON

PREPARER SIGNATURE

FOR CITY STAMPS

BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.



682 SECOND ST

ENCINITAS, CA

(760) 753 2464

DZNPARTNERS.COM

1 BEDROOM PRADU

CITY: ENCINITAS

2023.03-08
2023.05-22

JOB: 202241R

PROJECT DATA

a0.0

a b b r e v i a t i o n s

&	AND	EP	ELECTRICAL PANEL	PCC	PRECAST CONCRETE
@	AT	EQ	EQUAL	PKT	POCKET
°	DEGREES	EQUIP	EQUIPMENT	PL	PLATE
Ø	DIAMETER	EW	EACH WAY	PIL	PROPERTY LINE
%	PERCENT	EXP	EXPANSION	PLS	PLASTER
d	PENNY (NAIL SIZE)	EXST	EXISTING	PLY	PLYWOOD
#	POUND OR NUMBER	EXT	EXTERIOR	PNL	PANEL
(E)	EXISTING	FA	FIRE ALARM	PR	PAIR
(N)	NEW	FAB	FABRICATE	PRE	PREFABRICATED
(NR)	NEW REPLACEMENT	FAU	FORCED AIR UNIT	PT	PRESSURE TREATED
AA	ATTIC ACCESS	FD	FLOOR DRAIN	PTR	PARTNER
AB	ANCHOR BOLT	FDN	FOUNDATION	PV	PRESSURE VALVE
AC	ASPHALT CONCRETE	FE	FIRE EXTINGUISHER	PVC	POLYVINYL CHLORIDE
A-C	ALTERNATING CURRENT	FF	FINISH FLOOR	R	RISER, RIDGE OR RADIUS
ACU	AIR CONDITIONING	FG	FINISH GRADE	RA	RETURN AIR
ACOUS	ACOUSTICAL	FIN	FINISH	RB	REINFORCING BAR
ACT	ACOUSTICAL CEILING TILE	FJ	FLOOR JOIST	RBR	RUBBER
AD	AREA DRAIN	FL	FLOURESCENT	RCP	REFLECTED CEILING PLAN
ADA	AMERICAN DISABILITY ACT	FLR	FLOOR	RD	ROOF DRAIN
AFO	ARCHED FRAMED OPENING	FLSH	FLASHING	REF	REFRIGERATOR
AGGR	AGGREGATE	FN	FIELD NAILING	REG	REGISTER
AGO	ARCH GYPSUM BOARD OPENING	FO	FRAMED OPENING	REINF	REINFORCE
AHS	ALUMINUM HORIZONTAL SLIDING	FP	FIREPLACE	REDD	REQUIRED
AL	ALUMINUM	FR	FIRE RATED	REV	REVISION
ALM	ALARM	FRMG	FRAMING	RI	RIGID INSULATION
ALT	ALTERNATE	FT	FOOT/FEET	RM	ROOM
AMP	AMPERE	FG	FOOTING	RO	ROUGH OPENING
APN	ASSESSORS PARCEL NUMBER	FXD	FIXED	RR	ROOF RAFTER
ARCH	ARCHITECT	FYSB	FRONT YARD SETBACK	RIS	RESAWN
AS	ALUMINUM SLIDING	GA	GAUGE	RYSB	REAR YARD SETBACK
ASPH	ASPHALT	GAL	GALLON	S	SOUTH
AVE	AVENUE	GALV	GALVANIZED	SA	SUPPLY AIR
AVS	ALUMINUM VERTICAL SLIDING	GB	GYPSUM BOARD	SBO	SELECTION BY OWNER
AWG	AWNING	GFI	GROUND FORCE INTERRUPT	SC	SOLID CORE
B	BOTTOM	GI	GALVANIZED IRON	SDG	SIDING
BBQ	BARBEQUE	GL	GLASS	SEC	SECTION
BD	BOARD	GLB	GLU-LAM BEAM	SF	SQUARE FEET
BFD	BIFOLDING DOOR	GO	GYPSUM BOARD OPENING	SFD	SINGLE FAMILY DWELLING
BI	BUILT IN	GR	GRADE	SH	SINGLE HUNG OR SHELF
BJ	BALCONY JOIST	GWB	GYPSUM WALL BOARD	SHR	SHEAR
BLDG	BUILDING	GYP	GYPSUM	SHT	SHEET
BLK	BLOCK	H	HIP	SHTG	SHEATHING
BLKG	BLOCKING	HB	HOSE BIBB	SIM	SIMILAR
BM	BEAM	HC	HOLLOW CORE	SP	SHEAR PANEL
BN	BOUNDARY NAIL	HIC	HANDICAPPED	S & P	SHELF AND POLE
BOT	BOTTOM	HD	HEAD	SPEC	SPECIFICATIONS
BPD	BYPASS DOOR	HDR	HEADER	SQ	SQUARE
BRG	BEARING	HDWR	HARDWARE	SS	STAINLESS STEEL
BRK	BRICK	HF	HARDY FRAME	SSW	STEEL STRONG WALL
BSMT	BASEMENT	HI	HIGH	SSYSB	STREET SIDEYARD SETBACK
BTU	BRITISH THERMAL UNIT	HM	HOLLOW METAL	ST	STAIR
BW	BOTH WAYS	HOR	HORIZONTAL	STL	STEEL
CAB	CABINET	HP	HEAT PUMP	STP	STRAP
CB	CATCH BASIN	HPR	HOPPER	STR	STRUCTURAL
CEM	CEMENT	HR	HOURL	STRG	STORAGE
CER	CERAMIC	HT	HEIGHT	SUSP	SUSPENDED
CI	CAST IRON	HTR	HEATER	SWU	SOFT WATER UNIT
CJP	CAST IN PLACE	HW	HOT WATER	SYSB	SIDE YARD SETBACK
CJ	CEILING JOIST / CONTROL JOINT	INSUL	INSULATION	T	TREAD OR TOP
CL	CENTERLINE	IN	INCH	TB	THROUGH BOLT
CLG	CEILING	INT	INTERIOR	T & B	TOP AND BOTTOM
CLKG	CAULKING	JST	JOIST	TC	TRASH COMPACTOR
CLO	CLOSET	JT	JOINT	TELE	TELEPHONE
CLR	CLEAR	KIT	KITCHEN	TEMP	TEMPORARY
CMN	COMMON	L	LINEN	TG	TEMPERED GLASS
CMU	CONCRETE MASONRY UNIT	LAM	LAMINATE	T & G	TONGUE AND GROOVE
CO	CLEANOUT	LAT	LATERAL	THK	THICK
COL	COLUMN	LAV	LAVATORY	TME	TO MATCH EXISTING
CONC	CONCRETE	LDG	LANDING	TP	TOP PLATE
CONT	CONTINUOUS	LG	LONG	TV	TELEVISION
CONTR	CONTRACTOR	LR	LARGE	TYP	TYPICAL
CP	CEMENT PLASTER	LS	LAZY SUSAN	TWH	TANKLESS WATER HEATER
CPT	CARPET	LSW	LAG SCREW	U/	UNDER
CSMT	CASEMENT	LT	LAUNDRY TUB	UC	UNDER COUNTER
CTR	CENTER	LGT	LIGHT	UNO	UNLESS NOTED OTHERWISE
CW	COLD WATER VALVE	MAX	MAXIMUM	UON	UNLESS OTHERWISE NOTED
CY	CUBIC YARD	MB	MACHINE BOLT	V	VALLEY OR VALVE
DBL	DOUBLE	MBPD	MIRROR BYPASS DOOR	VAC	VACUUM
DEMO	DEMOLITION	MC	MEDICINE CABINET	VER	VERTICAL
DF	DOUGLAS FIR	MDL	MODEL	VHS	VINYL HORIZONTAL SLIDER
DG	DUAL GLAZED	MECH	MECHANICAL	VIF	VENTIFY IN FLOOR
DH	DOUBLE HUNG	MEMB	MEMBRANE	VOL	VOLUME
DIA	DIAMETER	MFR	MANUFACTURER	VTR	VENT TO ROOF
DIM	DIMENSION	MIN	MINIMUM	VVS	VINYL VERTICAL SLIDER
DJ	DECK JOIST	MISC	MISCELLANEOUS	WEST	WEST
DN	DOWN	MS	MACHINE SCREW	WITH	WITH
DP	DEEP	MTL	METAL	WITHOUT	WITHOUT
DR	DOOR	MW	MICRO WAVE OVEN	WC	WATER CLOSET
DS	DOWNSPOUT	N	NORTH	WD	WOOD
DTP	DOUBLE TOP PLATE	NIA	NOT APPLICABLE	WDW	WINDOW
DV	DRYER VENT	NAT	NATURAL	WDWR	WARMING DRAWER
DW	DISHWASHER	NCE	NICE PART	WH	WATER HEATER
DZN	DESIGN	NIC	NOT IN CONTRACT	WHS	WOOD HORIZONTAL SLIDER
E	EAST	NO	NUMBER	WI	WROUGHT IRON
EA	EACH	NOM	NOMINAL	WIC	WALK IN CLOSET
EGR	EXISTING GRADE	NTS	NOT TO SCALE	WMH	WALL MOUNTED HEATER
EJ	EXPANSION JOINT	O/	OVER	WP	WATERPROOF
ELEC	ELECTRIC	ON	ON CENTER	WS	WOOD SCREW
ELEV	ELEVATION	OAE	OR APPROVED EQUAL	WSW	WOOD STRONG WALL
EM	ELECTRICAL METER	OH	OVERHANG	VWS	WOOD VERTICAL SLIDER
EMER	EMERGENCY	OPG	OPENING	WWM	WELDED WIRE MESH
EN	EDGE FINISH	OZ	OUNCE	YD	YARD
ENCL	ENCLOSURE	P	POLE		

door schedule - elevation a, b & c

DOOR #	WIDTH	HEIGHT	THICK	TYPE	OPERATION	CORE OR GLAZING	MATERIAL	FRAME	SCREEN	U FACTOR	SHGC	QUANTITY	NOTES
1	3'-0"	8'-0"	1-3/4"	FRENCH	SWING	DG, TG	WOOD	WOOD	OPTIONAL	.53/.58/.43	.47/.53/.35	1	ENTRY
2	8'-0"	8'-0"	1-3/4"	FRENCH	SLIDING	DG, TG	VINYL	VINYL	YES	.53/.58/.43	.47/.53/.35	1	
3	6'-0"	8'-0"	1-3/4"	FRENCH	SLIDING	DG, TG	VINYL	VINYL	YES	.53/.58/.43	.47/.53/.35	1	
4	2'-4"	8'-0"	1-1/2"	INTERIOR	SWING	HOLLOW	WOOD	WOOD	NO	N/A	N/A	2	PRIVACY
5	2'-0"	8'-0"	1-1/2"	INTERIOR	SWING	HOLLOW	WOOD	WOOD	NO	N/A	N/A	2	PRIVACY
6	2'-0"	8'-0"	1-1/2"	INTERIOR	SWING	HOLLOW	WOOD	WOOD	NO	N/A	N/A	1	PRIVACY
7	7'-0"	8'-0"	1-1/2"	CLOSET	BYPASS	-	MIRROR	ALUMINUM	NO	N/A	N/A	1	
8	2'-6"	8'-0"	1-3/4"	EXTERIOR	SWING	SOLID	WOOD	WOOD	VENTS T&B	N/A	N/A	1	WH DOOR

window schedule - elevation a & b

WINDOW #	WIDTH	HEIGHT	TYPE	MATERIAL	GLAZING	SCREEN	QUANTITY	U FACTOR	SHGC	NOTES
1	3'-0"	6'-0"	VERTICAL SLIDER	VINYL	DG	YES	3	.56/.58	.49/.50	
2	2'-0"	4'-0"	VERTICAL SLIDER	VINYL	DG	YES	1	.56/.58	.49/.50	OPAQUE
3	4'-0"	2'-0"	HORIZONTAL SLIDER	VINYL	DG	YES	1	.56/.58	.49/.50	OPAQUE
4	6'-0"	3'-0"	HORIZONTAL SLIDER	VINYL	DG	YES	1	.56/.58	.49/.50	
5	2'-6"	5'-0"	VERTICAL SLIDER	VINYL	DG	YES	1	.56/.58	.49/.50	

window schedule - elevation c

WINDOW #	WIDTH	HEIGHT	TYPE	MATERIAL	GLAZING	SCREEN	QUANTITY	U FACTOR	SHGC	NOTES
1	3'-0"	6'-0"	VERTICAL SLIDER	VINYL	DG	YES	3	.44	.40	
2	2'-0"	4'-0"	VERTICAL SLIDER	VINYL	DG	YES	1	.44	.40	OPAQUE
3	4'-0"	2'-0"	HORIZONTAL SLIDER	VINYL	DG	YES	1	.44	.40	OPAQUE
4	6'-0"	3'-0"	HORIZONTAL SLIDER	VINYL	DG	YES	1	.44	.40	
5	2'-6"	5'-0"	VERTICAL SLIDER	VINYL	DG	YES	1	.44	.40	
6	2'-0"	2'-0"	FIXED TRANSOM	VINYL	DG, TG	NO	2	.48	.30	ABOVE DOORS AT ELEV C

appliance schedule - one bedroom 1

APPLIANCE	OPERATION	MANUFACTURER	MODEL	QUANTITY	NOTES
SPLIT SYSTEM HEAT PUMP	ELECTRICITY	PANASONIC	CU-3E19RBU-5	1	OR EQUAL, INTERIOR UNITS TO BE DETERMINED
HEAT PUMP TANK WATER HEATER	ELECTRICITY	PHOENIX	PROPH40 T2 RH375-SO	1	OR EQUAL
REFRIGERATOR	ELECTRICITY	BY OWNER	BY OWNER	1	36" WIDE, COUNTER DEPTH
RANGE	ELECTRICITY	BY OWNER	BY OWNER	1	30" WIDE
MICROWAVE HOOD	ELECTRICITY	BY OWNER	BY OWNER	1	30" WIDE
DISHWASHER	ELECTRICITY	BY OWNER	BY OWNER	1	24" WIDE
STACKED WASHER/DRYER	ELECTRICITY	BY OWNER	BY OWNER	1	COMPACT UNIT
GARBAGE DISPOSAL	ELECTRICITY	BY OWNER	BY OWNER	1	AIR SWITCH

fixture schedule - one bedroom 1

FIXTURE	LOCATION	MANUFACTURER	MODEL	QUANTITY	NOTES
SINK	KITCHEN	BY OWNER	BY OWNER	1	
SHOWER FAUCET	KITCHEN	BY OWNER	BY OWNER	1	
LAVATORY	BATH	BY OWNER	BY OWNER	1	
LAVATORY FAUCET	BATH	BY OWNER	BY OWNER	1	
TOILET	BATH	BY OWNER	BY OWNER	1	
BATHTUB	BATH	BY OWNER	BY OWNER	1	30"x60" CAST IRON, OR EQUAL
BATH FILLER + SHOWER HEAD	BATH	BY OWNER	BY OWNER	1	

material schedule - one bedroom 1

LOCATION	FLOOR	BASE	CASE	COUNTER	CABINET	WALL	CEILING	NOTES
LIVING ROOM	2	4	4	-	-	1	5	OR EQUAL
NOOK	2	4	4	3	2	2	2	OR EQUAL
KITCHEN	2	4	4	3	2	2	2	OR EQUAL
BATH	2	2	4	4	1	2	2	OR EQUAL
BEDROOM	4	4	4	3	2	1	5	OR EQUAL
	1-CONCRETE	1-NONE	1-NONE	1-CONCRETE	1-PAINTED	1-FLAT PAINT	1-FLAT PAINT	
	2-TILE	2-TILE	2-TILE	2-TILE	WOOD	O/ GB	O/ GB	
	3-VINYL	3-VINYL	3-VINYL	3-STONE	2-STAINED	2-SEMGLOSS	2-SEMGLOSS	
	4-CARPET	4-P. WOOD	4-P. WOOD	4-GLASS	WOOD	PAINT O/ GB	PAINT O/ GB	
	5-WOOD	5-S. WOOD	5-S. WOOD	5-WOOD	3-METAL	5-WOOD	5-T&G WOOD	

fire sprinklers:

☒ EXISTING OR PROPOSED RESIDENCE

☐ NO

☐ YES

☒ REQUIRED AT PROPOSED ADU

☐ NO

☐ YES

fire sprinkler notes:

- IF FIRE SPRINKLERS ARE REQUIRED AT THE ADU THAN THESE NOTES APPLY.
- AUTOMATIC FIRE SPRINKLER SYSTEM - AN AUTOMATIC FIRE SPRINKLER SYSTEM SHALL BE INSTALLED AS PER N.F.P.A. 13D, THE MOST CURRENT EDITION SHALL BE USED AND THE ENCINITAS FIRE DEPARTMENT POLICIES/ORDINANCES. DETAILED SPRINKLER PLANS SHALL BE SUBMITTED TO THE FIRE PREVENTION BUREAU AND APPROVED PRIOR TO INSTALLATION. PLANS AND INSTALLATION MUST BE BY A C16 LICENSED SPRINKLER CONTRACTOR.
- SECTION 903.2 GROUP R** AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH SECTION 903.3 SHALL BE PROVIDED THROUGHOUT ALL BUILDINGS WITH A GROUP R FIRE AREA. THIS INCLUDES SINGLE-FAMILY DWELLINGS, MULTI-FAMILY DWELLINGS AND ALL RESIDENTIAL CARE FACILITIES REGARDLESS OF OCCUPANT LOAD.
- SECTION 903.2.01** ADDITIONAL AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH 903.3 MAY BE REQUIRED TO BE INSTALLED THROUGHOUT STRUCTURES WHEN THE ADDITION IS MORE THAN 50% OF THE EXISTING BUILDING OR WHEN THE ALTERED BUILDING WILL EXCEED A FIRE FLOW OF 1,500 GALLONS PER MINUTE AS CALCULATED PER SECTION 507.3. THE FIRE CODE OFFICIAL MAY REQUIRE AN AUTOMATIC SPRINKLER SYSTEM BE INSTALLED IN BUILDINGS WHERE NO WATER MAIN EXISTS TO PROVIDE THE REQUIRED FIRE FLOW OR WHERE A SPECIAL HAZARD EXISTS SUCH AS: POOR ACCESS ROADS, GRADE, BLUFFS AND CANYONS, OR HAZARDOUS BRUSH AND RESPONSE TIMES GREATER THAN 10 MINUTES BY A FIRE DEPARTMENT.
- SECTION 903.2.01** REMODELS OR RECONSTRUCTION AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH SECTION 903.3 MAY BE REQUIRED IF THE SCOPE OF WORK INCLUDES SIGNIFICANT MODIFICATION TO THE INTERIOR AND/OR ROOF OF THE BUILDING, AND THE COST OF THE INSTALLATION DOES NOT EXCEED 15 PERCENT OF THE VALUATION OF THE REMODEL.
- LOCATION AND SIZE OF WATER SERVICE UNDERGROUND SHALL BE INSTALLED AS SHOWN ON APPROVED FIRE SPRINKLER PLANS. A MINIMUM 1 INCH WATER SHALL BE INSTALLED.
- A FIRE UNDERGROUND FLUSH CERTIFICATION SHALL BE REQUIRED AT FINAL INSPECTION.
- A HYDRO INSPECTION OF THE FIRE SPRINKLER SYSTEM IS REQUIRED PRIOR TO FRAME INSPECTION. ONLY THE NEW PIPING SHALL BE TESTED.

waste water:

☒ SELECTION

☐ SEWER

☐ SEPTIC (REQUIRES SAN DIEGO COUNTY HEALTH APPROVAL)

DISTANCE TO CONNECTION = _____ FEET

onsite parking:

☒ REQUIRED

☐ NONE

☐ ONE PARKING SPACE

very high fire severity zone:

☒ SELECTION

☐ NO

☐ YES

- IF THE PROPERTY THAT WILL CONTAIN THE ADU IS IN THE VERY HIGH FIRE HAZARD SEVERITY ZONE SEE NOTES BELOW & ON SHEET a0.1F
- THE ADU SHALL COMPLY WITH CHAPTER 7A OF THE CURRENT CALIFORNIA BUILDING CODE.
- STRUCTURES IN THE VERY HIGH FIRE HAZARD SEVERITY ZONE SHALL PROVIDE & MAINTAIN A FUEL MODIFICATION ZONE. FUEL MODIFICATION ZONES: THE APPLICANT SHALL PROVIDE & MAINTAIN FIRE/FUEL BREAKS TO THE SATISFACTION OF THE ENCINITAS FIRE DEPARTMENT. FIRE/FUEL BREAKS SIZE (MINIMUM 100 FEET FROM STRUCTURE) & COMPOSITION SHALL BE DETERMINED BY THE FIRE DEPARTMENT & SHOWN ON THE IMPROVEMENT/GRADING PLANS, FINAL MAP & BUILDING PLANS.

schedule notes:

- ALL GLAZING IN DOORS SHALL BE TEMPERED.
- SEE ELEVATIONS FOR 'TG' AT WINDOWS THAT REQUIRE TEMPERED GLAZING.
- IF THE PROPERTY THAT WILL CONTAIN THE ADU IS IN THE VERY HIGH FIRE HAZARD SEVERITY ZONE SEE NOTES AND SCHEDULES ON SHEET a0.1F CONCERNING DOOR & WINDOW CONSTRUCTION AND TEMPERED GLAZING.
- SEE ELEVATIONS FOR WINDOW OPERATION DIRECTION & LOCATION OF MUNTINS.
- SEE FLOOR PLANS FOR DOOR SWING DIRECTION.
- ALL GLAZED OPENINGS SHALL MEET THE REQUIREMENTS OF THE CBC T24 SHEETS PROVIDED IN THE PLANS.
- VINYL WINDOWS AND EXTERIOR VINYL DOOR FRAMES & SASH WILL BE COMPRISED OF VINYL MATERIAL WITH WELDED CORNERS & METAL REINFORCEMENT IN THE INTERLOCK AREA.

one bedroom 1 plan selection:

☒ SELECTION

☐ STANDARD PLAN, ELEVATION A

☐ STANDARD PLAN, ELEVATION B

☐ STANDARD PLAN, ELEVATION C

☐ REVERSE PLAN, ELEVATION A

☐ REVERSE PLAN, ELEVATION B

☐ REVERSE PLAN, ELEVATION C

foundation type:

☒ SELECTION

☐ STANDARD SOIL, SLAB ON GRADE

☐ EXPANSIVE SOIL, SLAB ON GRADE

☐ STANDARD SOIL, RAISED FLOOR FOUNDATION (ENERGY CALCS AVAILABLE ON REQUEST)

☐ EXPANSIVE SOIL, RAISED FLOOR FOUNDATION (ENERGY CALCS AVAILABLE ON REQUEST)

exterior wall material:

#1	#2	MATERIAL
<input type="checkbox"/>	<input type="checkbox"/>	CEMENT PLASTER SIDING - SAND FINISH OR TME
<input type="checkbox"/>	<input type="checkbox"/>	STONE SIDING
<input type="checkbox"/>	<input type="checkbox"/>	FIBER CEMENT - BOARD & BATT SIDING
<input type="checkbox"/>	<input type="checkbox"/>	FIBER CEMENT - LAP SIDING
<input type="checkbox"/>	<input type="checkbox"/>	FIBER CEMENT - SHINGLE SIDING

window material:

☒ MATERIAL

☐ VINYL

☐ FIBERGLASS

☐ WOOD

☐ ALUMINUM CLAD WOOD

eave/rake & parapet:

#1	#2	MATERIAL
<input type="checkbox"/>	<input type="checkbox"/>	SINGLE FASCIA - IGNITION RESISTANT
<input type="checkbox"/>	<input type="checkbox"/>	EXPOSED RAFTER - IGNITION RESISTANT
<input type="checkbox"/>	<input type="checkbox"/>	STEPPED DOUBLE FASCIA - IGNITION RESISTANT
<input type="checkbox"/>	<input type="checkbox"/>	HEAVY TIMBER RAFTER TAIL - IGNITION RESISTANT
<input type="checkbox"/>	<input type="checkbox"/>	PARAPET WITH WALL MATERIAL CAP - IGNITION RESISTANT
<input type="checkbox"/>	<input type="checkbox"/>	PARAPET WITH METAL CAP - IGNITION RESISTANT
<input type="checkbox"/>	<input type="checkbox"/>	CORBEL PARAPET WITH METAL CAP - IGNITION RESISTANT

roof material:

#1	#2	MATERIAL
----	----	----------

3.24 CONTINUOUS FOOTING REINFORCEMENT
3.25 REINFORCING SHALL BE CONTINUED
CONNECTIONS

PREPARER SIGNATURE _____

— 7 —

CONSTRUCTION DOCUMENTS,
THE USER AGREES TO RELEASE

INJURY, DAMAGE OR LOSS TO
PERSONS OR PROPERTY

—

P A R T N E R S

(7 6 0) 7 5 3 2 4 6 4

1 BEDROOM

1000

1000

1000

SPECIFICATIONS

1000

1000

1000

2022 CALIFORNIA GREEN BUILDING STANDARDS CODE
RESIDENTIAL MANDATORY MEASURES, SHEET 1 (January 2023)

Y
N/A
RESPON. PART

*
NOT APPLICABLE
RESPONSIBLE PARTY (IN: ARCHITECT, ENGINEER,
OWNER, CONTRACTOR, INSPECTOR, ETC.)

7

</

┌

└

└

┐

PREPARER SIGNATURE

┌

┐

FOR CITY STAMPS

┌

┌

┐

BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.

┌

┐

┌

DZNPARTNERS

682 SECOND ST
ENCINITAS, CA
(760) 753 2464
DZNPARTNERS.COM

┌

┐

1 BEDROOM
PRADU

┌

┐

CITY: ENCINITAS

┌

┐

JOB: 202241R

┌

┐

AVERAGE LOT
SLOPE DIAGRAM

┌

┐

a0.5

┌


┐

average lot slope calcs:



A.	LENGTH LOT SLOPE RUN LINE A =	FT
	LOT SLOPE RUN LINE A ELEVATION AT POINT 1 =	FT
	LOT SLOPE RUN LINE A ELEVATION AT POINT 2 =	FT
	POINT 1 (FT) - POINT 2 (FT) / LENGTH (FT) =	% SLOPE AT RUN LINE A
B.	LENGTH LOT SLOPE RUN LINE B =	FT
	LOT SLOPE RUN LINE B ELEVATION AT POINT 1 =	FT
	LOT SLOPE RUN LINE B ELEVATION AT POINT 2 =	FT
	POINT 1 (FT) - POINT 2 (FT) / LENGTH (FT) =	% SLOPE AT RUN LINE B
C.	LENGTH LOT SLOPE RUN LINE C =	FT
	LOT SLOPE RUN LINE C ELEVATION AT POINT 1 =	FT
	LOT SLOPE RUN LINE C ELEVATION AT POINT 2 =	FT
	POINT 1 (FT) - POINT 2 (FT) / LENGTH (FT) =	% SLOPE AT RUN LINE C
T.	RUN LINE A % + RUN LINE B % + RUN LINE C % / 3 =	% TOTAL
	AVERAGE LOT SLOPE IS	%



NOTES:

- SEE SAMPLE AVERAGE LOT SLOPE EXHIBIT ON SHEET a0.5
- FOR LOTS THAT EXCEED AN AVERAGE LOT SLOPE OF 10% ADDITIONAL HEIGHT RESTRICTIONS WILL APPLY AS PER EMC 30.16



1 sample average lot slope diagram
SCALE: 1"=10'-0"





1 reverse floor plan a
SCALE: 1/4" = 1'-0"

2 floor plan a
SCALE: 1/4" = 1'-0"

drawing:		drawing:		drawing:		drawing:		
SYMBOL	=	DESCRIPTION	SYMBOL	=	DESCRIPTION	SYMBOL	=	DESCRIPTION
(N)	=	NEW		=	EXISTING FOOTING		=	BUILDING SECTION LETTER
(E)	=	EXISTING		=	NEW FOOTING		=	WALL SECTION LETTER
	=	EXISTING WALL REMOVED		=	NORTH ARROW		=	DETAIL NUMBER
	=	EXISTING WALL TO REMAIN		=	NEW POINT ELEVATION		=	INTERIOR ELEVATION
	=	NEW 4" WALL		=	EXISTING POINT ELEVATION		=	LEVEL CHANGE
	=	NEW 6" WALL		=	NEW CONTOUR		=	ROOM OR SPACE NUMBER
	=	NEW 8" WALL		=	EXISTING CONTOUR		=	ROOM NAME CEILING HEIGHT, FLOORING
	=	NEW 8" CMU WALL		=	PROPERTY LINE		=	WINDOW NUMBER
	=	NEW DIVIDING UNIT SEPARATION WALL		=	CENTER LINE		=	DOOR NUMBER
	=	BEARING WALL		=	SET BACK LINE		=	REVISION NUMBER
	=	NON-BEARING WALL FRAMING PLANS		=	FLOOR MATERIAL CHANGE		=	KEYNOTE NUMBER
	=	SHEAR PANEL LETTER		=	TRUSS NUMBER		=	STRUCTURAL GRID LINE
	=	SHEAR PANEL LENGTH		=	SHEAR DRAG LINE		=	PAD FOOTING
	=	POST		=	HOLD DOWN		=	FACTORY BUILT SHEAR PANEL
	=	FLOOR JOISTS		=	CEILING JOISTS		=	RAFTER OR TRUSS

floor plan notes:

- SEE LEGENDS TO THE LEFT FOR SYMBOLS RELATING TO THE FLOOR PLAN.
- SEE SHEET #0.1 FOR SCHEDULES RELATING TO THE FLOOR PLAN.
- THE KITCHEN SHALL HAVE UPPER CABINETS, BASE CABINETS, AND COUNTERTOPS AS DEPICTED ON THIS FLOOR PLAN AND IN THE INTERIOR ELEVATIONS.
LAVATORIES:
 - SHALL BE PLACED IN A VANITY BASE CABINET WITH A COUNTERTOP.
 - SHALL HAVE A MIRROR AT THE WALL BEHIND THE LAVATORY.
 - SHALL HAVE A MIRROR MEDICINE CABINET AT THE SIDE WHEN DEPICTED WITH A RECTANGLE IN THE WALL.**TOILETS:**
 - SHALL BE FLUSH TANK.
 - SHALL BE PLACED IN A SPACE WITH 30" CLEAR WIDTH.
 - SHALL HAVE 24" CLEAR IN FRONT OF THE FIXTURE.**BATHTUB/SOWER COMBINATIONS**
 - BATHTUB SHALL BE PORCELAIN OVER CAST IRON.
 - PROVIDE FULL HEIGHT TILE WAINSCOT ON WALLS WITHIN TUB AREA.
 - PROVIDE SLIDING CLEAR TEMPERED GLASS TUB/SOWER ENCLOSURE OR EQUAL.**SHOWERS**
 - FLOOR TO BE TILE OVER ASPHALTIC WATERPROOF MEMBRANE LINER, TYPICAL.
 - DRAIN TO BE LINEAR OR ROUND AS DEPICTED ON THE FLOOR PLAN.
 - ENTRY CURB SHALL BE 4" WIDE AND TALL WITH TILE FINISH, TYP.
 - SHALL HAVE A CLEAR TEMPERED GLASS SHOWER ENCLOSURE WITH OPENING AS SHOWN ON THE FLOOR PLAN OR EQUAL.
 - WALLS IN SHOWER AREA WILL HAVE A FULL HEIGHT TILE WAINSCOT.
 - SEATS SHOWN IN SHOWERS SHALL BE 16" HIGH AND WILL BE TILED TO MATCH THE WALLS.
 - EACH SHOWER SHALL HAVE A 12" WIDE X 16" HIGH NICHE FOR SOAP AND SHAMPOO BOTTLES IN A WAINSCOT WALL.
- CLOSETS SHALL HAVE A SHELF AND POLE AS SHOWN ON THE FLOOR PLAN.

BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.



682 SECOND ST
ENCINITAS, CA
(760) 753 2464
DZNPARTNERS.COM



1 BEDROOM
PRADU

CITY: ENCINITAS

JOB: 202241R

FLOOR PLAN A +
REVERSE A

a1.0



1 floor plan c
SCALE: 1/4" = 1'-0"

2 floor plan b
SCALE: 1/4" = 1'-0"

drawing:		drawing:		drawing:		drawing:		
SYMBOL	=	DESCRIPTION	SYMBOL	=	DESCRIPTION	SYMBOL	=	DESCRIPTION
(N)	=	NEW		=	EXISTING FOOTING		=	BUILDING SECTION LETTER
(E)	=	EXISTING		=	NEW FOOTING		=	WALL SECTION LETTER
	=	EXISTING WALL REMOVED		=	NORTH ARROW		=	DETAIL NUMBER
	=	EXISTING WALL TO REMAIN		=	NEW POINT ELEVATION		=	INTERIOR ELEVATION
	=	NEW 4" WALL		=	EXISTING POINT ELEVATION		=	LEVEL CHANGE
	=	NEW 6" WALL		=	NEW CONTOUR		=	ROOM OR SPACE NUMBER
	=	NEW 8" WALL		=	EXISTING CONTOUR		=	ROOM NAME CEILING HEIGHT, FLOORING
	=	NEW 8" CMU WALL		=	PROPERTY LINE		=	WINDOW NUMBER
	=	NEW DWELLING UNIT SEPARATION WALL		=	CENTER LINE		=	DOOR NUMBER
	=	BEARING WALL		=	SET BACK LINE		=	REVISION NUMBER
	=	NON-BEARING WALL OR FRAMING PLANS		=	FLOOR MATERIAL CHANGE		=	KEYNOTE NUMBER
	=						=	SHEAR PANEL LETTER
	=						=	SHEAR PANEL LENGTH
	=						=	TRUSS NUMBER
	=						=	STRUCTURAL GRID LINE
	=						=	SHEAR DRAG LINE
	=						=	PAD FOOTING
	=						=	POST
	=						=	HOLD DOWN
	=						=	FACTORY BUILT SHEAR PANEL
	=						=	FLOOR JOISTS
	=						=	CEILING JOISTS
	=						=	RAFTER OR TRUSS

floor plan notes:

- SEE LEGENDS TO THE LEFT FOR SYMBOLS RELATING TO THE FLOOR PLAN.
- SEE SHEET #0.1 FOR SCHEDULES RELATING TO THE FLOOR PLAN.
- THE KITCHEN SHALL HAVE UPPER CABINETS, BASE CABINETS, AND COUNTERTOPS AS DEPICTED ON THIS FLOOR PLAN AND IN THE INTERIOR ELEVATIONS.
LAVATORIES:
 - SHALL BE PLACED IN A VANITY BASE CABINET WITH A COUNTERTOP.
 - SHALL HAVE A MIRROR AT THE WALL BEHIND THE LAVATORY.
 - SHALL HAVE A MIRROR MEDICINE CABINET AT THE SIDE WHEN DEPICTED WITH A RECTANGLE IN THE WALL.**TOILETS:**
 - SHALL BE FLUSH TANK.
 - SHALL BE PLACED IN A SPACE WITH 30" CLEAR WIDTH.
 - SHALL HAVE 24" CLEAR IN FRONT OF THE FIXTURE.**BATHTUB/SOWER COMBINATIONS**
 - BATHTUB SHALL BE PORCELAIN OVER CAST IRON.
 - PROVIDE FULL HEIGHT TILE WAINSCOT ON WALLS WITHIN TUB AREA.
 - PROVIDE SLIDING CLEAR TEMPERED GLASS TUB/SOWER ENCLOSURE OR EQUAL.**SHOWERS**
 - FLOOR TO BE TILE OVER ASPHALTIC WATERPROOF MEMBRANE LINER, TYPICAL.
 - DRAIN TO BE LINEAR OR ROUND AS DEPICTED ON THE FLOOR PLAN.
 - ENTRY CURB SHALL BE 4" WIDE AND TALL WITH TILE FINISH, TYP.
 - SHALL HAVE A CLEAR TEMPERED GLASS SHOWER ENCLOSURE WITH OPENING AS SHOWN ON THE FLOOR PLAN OR EQUAL.
 - WALLS IN SHOWER AREA WILL HAVE A FULL HEIGHT TILE WAINSCOT.
 - SEATS SHOWN IN SHOWERS SHALL BE 16" HIGH AND WILL BE TILED TO MATCH THE WALLS.
 - EACH SHOWER SHALL HAVE A 12" WIDE X 16" HIGH NICHE FOR SOAP AND SHAMPOO BOTTLES IN A WAINSCOT WALL.
- CLOSETS SHALL HAVE A SHELF AND POLE AS SHOWN ON THE FLOOR PLAN.

BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.



682 SECOND ST
ENCINITAS, CA
(760) 753 2464
DZNPARTNERS.COM

1 BEDROOM
PRADU

CITY: ENCINITAS

JOB: 202241R

FLOOR PLAN B +
FLOOR PLAN C

a1.1

photovoltaic requirements:

2022 CALIFORNIA ENERGY CODE SECTION 150.1(c)14:
ALL LOW-RISE RESIDENTIAL BUILDINGS SHALL HAVE A PHOTOVOLTAIC (PV) SYSTEM MEETING THE MINIMUM QUALIFICATION REQUIREMENTS AS SPECIFIED IN JOINT APPENDIX JA11, WITH ANNUAL ELECTRICAL OUTPUT EQUAL TO OR GREATER THAN THE DWELLING'S ANNUAL ELECTRICAL USAGE AS DETERMINED BY EQUATION 150.1-C:
EQUATION 150.1-C
ANNUAL PHOTOVOLTAIC ELECTRICAL OUTPUT
 $KW_{PV} = (CFA \times A)/1000 + (NDwell \times X \times B)$

WHERE:

 KW_{PV} = KWDC SIZE OF THE PV SYSTEM
CFA = CONDITIONED FLOOR AREA
NDwell = NUMBER OF DWELLING UNITS
A = ADJUSTMENT FACTOR FROM TABLE 150.1-C
B = DWELLING ADJUSTMENT FACTOR FROM TABLE 150.1-C

EXCEPTION 1 TO SECTION 150.1(C)14:
NO PV SYSTEM IS REQUIRED IF THE EFFECTIVE ANNUAL SOLAR ACCESS IS RESTRICTED TO LESS THAN 80 CONTIGUOUS SQUARE FEET BY SHADING FROM EXISTING PERMANENT NATURAL OR MANMADE BARRIERS EXTERNAL TO THE DWELLING, INCLUDING BUT NOT LIMITED TO TREES, HILLS, AND ADJACENT STRUCTURES. THE EFFECTIVE ANNUAL SOLAR ACCESS SHALL BE 70 PERCENT OR GREATER OF THE OUTPUT OF AN UNSHADED PV ARRAY ON AN ANNUAL BASIS.

EXCEPTION 2 TO SECTION 150.1(C)14:
IN CLIMATE ZONE 15, THE PV SYSTEM SIZE SHALL BE THE SMALLER OF A SIZE THAT CAN BE ACCOMMODATED BY THE EFFECTIVE ANNUAL SOLAR ACCESS OR A PV SYSTEM SIZE REQUIRED BY THE EQUATION 150.1-C, BUT NO LESS THAN 1.5 WATT DC PER SQUARE FOOT OF CONDITIONED FLOOR AREA.

EXCEPTION 3 TO SECTION 150.1(C)14:
IN ALL CLIMATE ZONES, FOR DWELLING UNITS WITH TWO HABITABLE STORIES, THE PV SYSTEM SIZE SHALL BE THE SMALLER OF A SIZE THAT CAN BE ACCOMMODATED BY THE EFFECTIVE ANNUAL SOLAR ACCESS OR A PV SYSTEM SIZE REQUIRED BY THE EQUATION 150.1-C, BUT NO LESS THAN 1.0 WATT DC PER SQUARE FOOT OF CONDITIONED FLOOR AREA

EXCEPTION 4 TO SECTION 150.1(C)14:
IN ALL CLIMATE ZONES, FOR LOW-RISE RESIDENTIAL DWELLINGS WITH THREE HABITABLE STORIES AND SINGLE-FAMILY DWELLINGS WITH THREE OR MORE HABITABLE STORIES, THE PV SYSTEM SIZE SHALL BE THE SMALLER OF A SIZE THAT CAN BE ACCOMMODATED BY THE EFFECTIVE ANNUAL SOLAR ACCESS OR A PV SYSTEM SIZE REQUIRED BY THE EQUATION 150.1-C, BUT NO LESS THAN 0.8 WATT DC PER SQUARE FOOT OF CONDITIONED FLOOR AREA.

EXCEPTION 5 TO SECTION 150.1(C)14:
FOR A DWELLING UNIT PLAN THAT IS APPROVED BY THE PLANNING DEPARTMENT PRIOR TO JANUARY 1, 2020 WITH AVAILABLE SOLAR READY ZONE BETWEEN 90 AND 200 SQUARE FEET, THE PV SYSTEM SIZE IS LIMITED TO THE LESSER OF THE SIZE THAT CAN BE ACCOMMODATED BY THE EFFECTIVE ANNUAL SOLAR ACCESS OR A SIZE THAT IS REQUIRED BY THE EQUATION 150.1-C.

EXCEPTION 6 TO SECTION 150.1(C)14:
PV SYSTEM SIZES FROM EQUATION 150.1-C MAY BE REDUCED BY 25 PERCENT IF INSTALLED IN CONJUNCTION WITH A BATTERY STORAGE SYSTEM. THE BATTERY STORAGE SYSTEM SHALL MEET THE QUALIFICATION REQUIREMENTS SPECIFIED IN JOINT APPENDIX JA12 AND HAVE A MINIMUM CAPACITY OF 7.5 KWH.

residential ventilation requirements:


- KITCHENS REQUIRE EXHAUST FANS WITH A MINIMUM 100 CFM DUCTED TO THE EXTERIOR. DETAIL COMPLIANCE BY INCLUDING A COMPLYING EXHAUST FAN OR A DUCTED RANGE HOOD TO THE EXTERIOR. 3 SONES MAXIMUM.
- EACH BATHROOM CONTAINING A BATHTUB, SHOWER OR TUB/SHOWER COMBINATION SHALL BE MECHANICALLY VENTILATED FOR PURPOSES OF HUMIDITY CONTROL IN ACCORDANCE WITH THE CALIFORNIA MECHANICAL CODE, CHAPTER 4; AND THE CALIFORNIA GREEN BUILDING STANDARDS CODE, CHAPTER 4, DIVISION 4.5.
- BATHROOMS REQUIRE EXHAUST FANS (MINIMUM 50 CFM SWITCHED OR 20 CM CONTINUOUS) TO BE DUCTED TO THE EXTERIOR. A BATHROOM IS DEFINED "AS A ROOM WITH A BATHTUB, SHOWER, OR SPA OR SOME SIMILAR SOURCE OF MOISTURE"
- RESIDENTIAL BATHROOM EXHAUST FANS SHALL BE ENERGY STAR RATED AND SHALL BE CONTROL BY A HUMIDISTAT CAPABLE OF AN ADJUSTMENT BETWEEN 50 AND 80% HUMIDITY. CALGREEN 4.506.1. EXCEPTION: CONTROL BY A HUMIDISTAT IS NOT REQUIRED IF THE BATHROOM EXHAUST FAN IS ALSO THE DWELLING WHOLE HOUSE VENTILATION. A) ALL FANS INSTALLED TO MEET ALL OF THE PRECEDING VENTILATION REQUIREMENTS MUST BE SPECIFIED AT A NOISE RATING OF A MAXIMUM 1 "SONE" (CONTINUOUS USE) OR 3 "SONE" (INTERMITTENT).
- EXHAUST DUCT SIZE, LENGTH AND OUTLET LOCATION FOR FANS AND HOODS TO BE NOTED ON THE PLANS.

electric:

- SELECTION
 - NEW METER WITH _____ AMP PANEL
 - SUBPANEL _____ AMP TO EXISTING _____ AMP MAIN PANEL

DISTANCE TO CONNECTION = _____ FEET


CONTACT SDG&E REGARDING ELECTRIC SERVICE TO THIS DETACHED ADU. ANY EXISTING SERVICE UPGRADE OR NEW SERVICE FOR THE ADU WILL REQUIRE A SEPARATE PERMIT FROM THE CITY OF ENCINITAS.



utility plan notes:

- SEE LEGENDS BELOW FOR SYMBOLS RELATING TO THE UTILITY PLAN.
- SEE SHEET #0.1 FOR SCHEDULES RELATING TO THE UTILITY PLAN.
- RECEPTACLE OUTLET LOCATION PER NEC ARTICLE 210.52.
- GFCI PROTECTED OUTLETS FOR LOCATIONS DESCRIBED IN NEC 210.8(A): LAUNDRY AREAS, KITCHEN DISHWASHERS, KITCHENS, GARAGES, BATH ROOMS, OUTDOORS, WITHIN 6' OF A SINK, ETC. RECEPTACLE OUTLET LOCATION PER NEC ARTICLE 210.52.
- BATH RECEPTACLE OUTLETS SHALL BE SUPPLIED BY A MINIMUM OF ONE 20 AMP CIRCUIT. SUCH CIRCUITS SHALL HAVE NO OTHER OUTLETS. THIS CIRCUIT MAY SERVE MULTIPLE BATHS (NEC ART. 210-52(D)).
- TAMPER RESISTANT RECEPTACLES ARE REQUIRED FOR ALL LOCATIONS DESCRIBED IN 210.52 (IE ALL RECEPTACLES IN A DWELLING).
- WEATHER RESISTANT TYPE FOR RECEPTACLES INSTALLED IN DAMP OR WET LOCATIONS.
- ARC-FAULT PROTECTION FOR ALL OUTLETS (NOT JUST RECEPTACLES) LOCATED IN ROOMS DESCRIBED IN NEC 210.12(A): KITCHENS, LAUNDRY AREAS, FAMILY, LIVING BEDROOMS, DINING, HALLS, ETC.
- OUTLETS MUST BE WITHIN 6FT OF ANY OPENING AND NOT TO EXCEED 12FT APART. ANY ISOLATED WALL 2FT OR WIDER TO HAVE OUTLET(S).
- ALL EXTERIOR LIGHTING SHALL BE HIGH EFFICACY, OAE
- RECESSED LIGHTS SHOWN IN SLOPED CEILINGS SHALL BE A MODEL DESIGNED TO PROVIDE A PERPENDICULAR LIGHT SOURCE IN A SLOPED CEILING.
- PROVIDE UFER GROUND AT ELECTRIC SERVICE LOCATION IN FOUNDATION. GROUND SHALL BE A 20' LONG #4 REINFORCING BAR, OAE.
- PROVIDE SMOKE DETECTORS IN EACH SLEEPING ROOM AND AT A POINT CENTRALLY LOCATED IN AN AREA GIVING ACCESS TO EACH SEPARATE SLEEPING AREA. SMOKE DETECTORS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING AND SHALL BE EQUIPPED WITH A BATTERY BACKUP. SMOKE DETECTORS MAYBE SOLELY BATTERY POWERED WHEN INSTALLED IN EXISTING BUILDINGS. (CRC §R314.6)
- WHERE MORE THAN ONE COMBINATION SMOKE/CARBON MONOXIDE DETECTOR IS REQUIRED, THE ALARM SHALL BE INTERCONNECTED IN A MANNER THAT ACTIVATION OF ONE ALARM SHALL ACTIVATE ALL THE ALARMS IN THE RESIDENCE.
- CONTROL VALVES IN BATHTUBS, WHIRLPOOL BATHTUBS, SHOWERS AND TUB-SHOWER COMBINATIONS MUST BE PRESSURE BALANCED OR THERMOSTATIC MIXING VALVES. CPC SECTION 414.5 AND 418.0.
- ALL HOT WATER PIPING SIZED 1/2" OR LARGER IS REQUIRED TO BE INSULATED AS FOLLOWS: 1" PIPE SIZE OR LESS: 1" THICK INSULATION. LARGER PIPE SIZES REQUIRE 1 1/2" THICK INSULATION. NOTE: IN ADDITION, THE 1/2" SIZE HOT WATER PIPE TO THE KITCHEN SINK IS REQUIRED TO BE INSULATED. ES 150.0(J)2
- SEE T24 DOCUMENTATION SHEET FOR MORE INFORMATION ON WATER HEATING, SPACE HEATING, AND COOLING EQUIPMENT SPECIFICATIONS.
- SHOW THE LOCATIONS OR PROVIDE NOTES OF ALL CARBON MONOXIDE ALARMS TO MEET THE REQUIREMENTS OF CALIFORNIA RESIDENTIAL CODE SECTION R315.
 - INSTALLED IN DWELLING UNITS AND IN SLEEPING UNITS WITHIN WHICH FUEL-BURNING APPLIANCES ARE INSTALLED AND IN DWELLING UNITS THAT HAVE ATTACHED GARAGES.
 - WHERE MORE THAN ONE CARBON MONOXIDE ALARM IS REQUIRED TO BE INSTALLED THE ALARM SHALL BE INTERCONNECTED IN A MANNER THAT ACTIVATION OF ONE ALARM SHALL ACTIVATE ALL THE ALARMS IN THE INDIVIDUAL UNIT.
 - WHERE AREAS OF NO CONSTRUCTION IS TAKING PLACE CARBON MONOXIDE DETECTORS CAN BE SOLELY BATTERY POWERED.
- CARBON MONOXIDE ALARMS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING IS SERVED FROM A COMMERCIAL SOURCE (E.G., BATTERY. WIRING SHALL BE PERMANENT AND WITHOUT A DISCONNECTING SWITCH OTHER THAN THOSE REQUIRED FOR OVER-CURRENT PROTECTION.
- SHOW THE LOCATIONS OR PROVIDE NOTES OF ALL SMOKE ALARMS MEETING THE REQUIREMENTS OF CRC SECTION R314.
 - ON THE CEILING OR WALL OUTSIDE OF EACH SEPARATE SLEEPING AREA IN THE IMMEDIATE VICINITY OF BED ROOMS.
 - IN EACH ROOM USED FOR SLEEPING PURPOSES.
 - IN EACH STORE WITHIN A DWELLING UNIT, INCLUDING BASEMENTS.
 - IN DWELLING UNITS WITH MULTIPLE LEVELS AND WITHOUT AN INTERVENING DOOR BETWEEN THE ADJACENT LEVELS, A SMOKE ALARM INSTALLED ON THE UPPER LEVEL SHALL SUFFICE FOR THE ADJACENT LOWER LEVEL PROVIDED THAT THE LOWER LEVEL IS LESS THAN ONE FULL STORY BELOW THE UPPER LEVEL.
 - WHERE AREAS OF NO CONSTRUCTION IS TAKING PLACE SMOKE DETECTORS CAN BE SOLELY BATTERY POWERED ONLY.

1 utility plan SCALE: 1/4" = 1'-0"



PREPARER SIGNATURE

FOR CITY STAMPS

BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.



682 SECOND STREET
ENCINITAS, CA
(760) 753 2464
DZNPARTNERS.COM

1 BEDROOM PRADU

CITY: ENCINITAS

JOB: 202241R

UTILITY PLAN

a2.0

electrical:

SYMBOL	=	DESCRIPTION
LED	=	LIGHT EMITTING DIODE
(E)	=	ELECTRICAL METER
I	=	ELECTRICAL PANEL
(H)	=	DUPLEX OUTLET
(H/2)	=	HALF HOT DUPLEX OUTLET
(Q)	=	QUADRAPLEX OUTLET
(GFI)	=	GROUND FORCE OUTLET
(WP GFI)	=	WATERPROOF GFI OUTLET
(IF)	=	IN-FLOOR OUTLET
(GD)	=	GARBAGE DISPOSAL OUTLET
(DG)	=	DEDICATED GROUND OUTLET
(220V)	=	220V OUTLET
(WP GFI 220)	=	WATERPROOF 220V OUTLET
\$	=	1 WAY SWITCH
\$3	=	3 WAY SWITCH

electrical:

SYMBOL	=	DESCRIPTION
(S)	=	DIMMER SWITCH
(K)	=	KEY OPERATED SWITCH
(WP)	=	WEATHERPROOF SWITCH
(VS)	=	VACANCY SENSOR SWITCH
(D)	=	DOOR OPERATED SWITCH
(F)	=	VENT FAN
(FAQ)	=	INDOOR QUALITY FAN
(FHP)	=	WHOLE HOUSE FAN
(H)	=	HEAT LAMP
(J)	=	JUNCTION BOX
(L)	=	LIGHT
(M)	=	MOTION DETECTOR
(P)	=	PHOTOELECTRIC SENSOR
(H/F)	=	HEAT LAMP/FAN COMBO
(L/F)	=	LED LIGHT/FAN COMBO

electrical:

SYMBOL	=	DESCRIPTION
(LH/F)	=	LED LIGHT/HEAT LAMP/FAN COMBO
(C)	=	CEILING SURFACE MOUNT FIXTURE
(W)	=	WALL MOUNTED FIXTURE
(H)	=	HANGING FIXTURE
(S)	=	WALL SCONCE
(R)	=	RECESSED CEILING FIXTURE
(C)	=	RECESSED CEILING WALL WASH FIXTURE
(M)	=	RECESSED MOISTURE RESISTANT CEILING FIXTURE
(F)	=	FLOOD FIXTURE
(T)	=	TRACK LIGHT FIXTURE
(F)	=	FLOURESCENT TUBE FIXTURE
(L)	=	LED UNDERCABINET FIXTURE
(S)	=	STEP LIGHT
(L)	=	GRID CEILING LIGHT

plumbing:

SYMBOL	=	DESCRIPTION
(W)	=	WATER METER
(F W M)	=	FIRE WATER METER
(WH)	=	TANK WATER HEATER
(HP WH)	=	ELECTRIC HEAT PUMP WATER HEATER
(WH)	=	TANKLESS WATER HEATER
(WC)	=	WATER CONDITIONER
(SO)	=	WATER SERVICE SHUTOFF
(HB)	=	HOSE BIB
(CW)	=	COLD WATER VALVE
(RP)	=	RECESSED PLUMBING
(V)	=	SHOWERHEAD
(V)	=	OVERHEAD SHOWERHEAD
(A)	=	ADJUSTABLE SHOWERHEAD
(L)	=	GRID CEILING LIGHT

plumbing:

SYMBOL	=	DESCRIPTION
(S)	=	FIRE SPRINKLER
(X)	=	ROUND SHOWER DRAIN
(L)	=	LINEAR SHOWER DRAIN
(CO)	=	CLEAN OUT
(FD)	=	FLOOR DRAIN
(FS)	=	FLOOR SINK
(OS)	=	OVERFLOW SCUPPER
(D)	=	DECK OR ROOF DRAIN
(D)	=	DECK OR ROOF DRAIN + OVERFLOW SCUPPER
(DS)	=	DOWNSPOUT
(U)	=	URINAL
(B)	=	BIDET
(T)	=	TOILET - FLOOR MOUNT

plumbing:

SYMBOL	=	DESCRIPTION
(T)	=	TOILET - WALL MOUNT
(F)	=	FAUCET
(P)	=	PEDESTAL SINK
(B)	=	BATH SINK
(T)	=	BATHTUB
(F)	=	FREESTANDING BATHTUB
(S)	=	BAR OR HAND SINK
(S)	=	SINGLE SINK
(S)	=	DOUBLE SINK
(S)	=	TRIPLE SINK
(S)	=	APRON SINK

mechanical:

SYMBOL	=	DESCRIPTION
(S)	=	SPLIT SYSTEM HEAT PUMP EXTERIOR UNIT
(S)	=	SPLIT SYSTEM HEAT PUMP INTERIOR UNIT
(T)	=	THERMOSTAT
(S)	=	SUPPLY AIR WALL REGISTER
(S)	=	SUPPLY AIR CEILING REGISTER
(S)	=	SUPPLY AIR FLOOR REGISTER
(RA)	=	RETURN AIR WALL REGISTER
(S)	=	RETURN AIR CEILING REGISTER
(S)	=	RETURN AIR FLOOR REGISTER

mechanical:

SYMBOL	=	DESCRIPTION
(S)	=	RIGID SUPPLY AIR DUCT
(S)	=	RIGID RETURN AIR DUCT
(S)	=	FLEXIBLE SUPPLY AIR DUCT
(FE)	=	FIRE EXTINGUISHER
(VM)	=	VACUUM MOTOR
(V)	=	VACUUM OUTLET
(DV)	=	DRYER VENT
(FV)	=	FAN VENT
(RV)	=	RANGE / OVEN VENT

media+safety:


SYMBOL	=	DESCRIPTION
(A)	=	ALARM SOURCE
(A)	=	AUDIO SOURCE
(D)	=	DATA SOURCE
(PP)	=	PHONE PANEL
(TP)	=	TELEVISION PANEL
(VP)	=	VIDEO PANEL
(TV)	=	CABLE TELEVISION JACK
(DP)	=	DATAPORT NETWORK JACK
(S)	=	TELEPHONE JACK
(S)	=	DOORBELL OR GARAGE DOOR

media+safety:



SYMBOL	=	DESCRIPTION
(S)	=	DOORBELL CHIMES
(DB)	=	DOORBELL TRANSFORMER
(A)	=	ALARM SYSTEM PAD
(CO)	=	CARBON MONOXIDE DETECTOR
(S)	=	SMOKE DETECTOR
(S)	=	SMOKE & CARBON MONOXIDE DETECTOR
(S)	=	EMERGENCY LIGHT FIXTURE
(EXIT)	=	ILLUMINATED EXIT SIGN
(S)	=	SPEAKER
(S)	=	VIDEO CAMERA

┌


┐





1 roof plan c
SCALE: 1/4" = 1'-0"



2 roof plan b
SCALE: 1/4" = 1'-0"



3 roof plan a
SCALE: 1/4" = 1'-0"



roof plan notes:

1. ALL ROOFING SHALL BE CLASS A RATED.
2. ROOFING SELECTION PER ROOF MATERIAL CHECKLIST ON SHEET a0.1
3. ATTIC PROPOSED OF 196 sf
ATTIC VENTING REQUIRED: 36 sf / 150 sq ft VENT AREA
ATTIC VENTING PROVIDED: 2 sf [4 O'HAGIN VENTS @ 1/2 sf EACH]
4. IF THE ADU IS IN THE VALLEY SZ THE O'HAGIN ROOF VENTS SHALL BE O'HAGIN FIRE & ICE LINE - FLAME AND EMBER RESISTANT ROOF VENTS
5. WHERE NO ATTIC IS PROPOSED DETAILS 88.07 & 88.00.4 PROVIDE INSULATION ALTERNATIVES.

PREPARER SIGNATURE

FOR CITY STAMPS

BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.



682 SECOND ST
ENCINITAS, CA
(760) 753 2464
DZNPARTNERS.COM

**1 BEDROOM
PRADU**

CITY: ENCINITAS


JOB: 202241R

ROOF PLANS


a3.0

└

└




1 rear elevation a
SCALE: 1/4" = 1'-0"




4 front elevation a
SCALE: 1/4" = 1'-0"

elevation + section notes:


1. ROOF PLAN NOTES THE LOCATION OF GUTTERS, DOWNSPOUTS & ROOF MOUNTED ATTIC VENTS.
2. ADJUSTMENT OF ROOF PITCH OR PLATE HEIGHT MAY BE REQUIRED IF RAISED FLOOR FOUNDATION IS SELECTED TO MEET HEIGHT REQUIREMENTS.
3. ELEVATIONS & SECTIONS SHALL SHOW BOTH FINISH (CONTINUOUS) & EXISTING (DASHED) GRADE AND THE CORRESPONDING HEIGHT LIMITATION LINE FROM THE LOWER OF THE FINISH OR EXISTING GRADE.
4. IF THE AVERAGE LOT SLOPE EXCEEDS 10% (NOT INCLUDING RR ZONED LOTS) THAN THE ADDITIONAL SLOPED LOT HEIGHT LIMITATION LINES SHALL BE SHOWN AS WELL.




2 left elevation a
SCALE: 1/4" = 1'-0"



5 right elevation a
SCALE: 1/4" = 1'-0"



3 section a
SCALE: 1/4" = 1'-0"



6 section b
SCALE: 1/4" = 1'-0"

PREPARER SIGNATURE

FOR CITY STAMPS

BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.


DZN PARTNERS
682 SECOND ST
ENCINITAS, CA
(760) 753 2464
DZNPARTNERS.COM

1 BEDROOM PRADU
CITY: ENCINITAS

JOB: 202241R



ELEVATION A + SECTION

a4.0




1 rear elevation b

SCALE: 1/4" = 1'-0"




4 front elevation b

SCALE: 1/4" = 1'-0"





elevation + section notes:

1. ROOF PLAN NOTES THE LOCATION OF GUTTERS, DOWNSPOUTS & ROOF MOUNTED ATTIC VENTS.
2. ADJUSTMENT OF ROOF PITCH OR PLATE HEIGHT MAY BE REQUIRED IF RAISED FLOOR FOUNDATION IS SELECTED TO MEET HEIGHT REQUIREMENTS.
3. ELEVATIONS & SECTIONS SHALL SHOW BOTH FINISH (CONTINUOUS) & EXISTING (DASHED) GRADE AND THE CORRESPONDING HEIGHT LIMITATION LINE FROM THE LOWER OF THE FINISH OR EXISTING GRADE.
4. IF THE AVERAGE LOT SLOPE EXCEEDS 10% (NOT INCLUDING RR ZONED LOTS) THAN THE ADDITIONAL SLOPED LOT HEIGHT LIMITATION LINES SHALL BE SHOWN AS WELL.





2 left elevation b

SCALE: 1/4" = 1'-0"





5 right elevation b

SCALE: 1/4" = 1'-0"



3 section c

SCALE: 1/4" = 1'-0"



6 section d

SCALE: 1/4" = 1'-0"



BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.



682 SECOND ST
ENCINITAS, CA
(760) 753 2464
DZNPARTNERS.COM


1 BEDROOM
PRADU

CITY: ENCINITAS

JOB: 202241R


ELEVATION B +
SECTION

a4.1




1 rear elevation c

SCALE: 1/4" = 1'-0"



4 front elevation c

SCALE: 1/4" = 1'-0"



elevation + section notes:

1. ROOF PLAN NOTES THE LOCATION OF GUTTERS, DOWNSPOUTS & ROOF MOUNTED ATTIC VENTS.
2. ADJUSTMENT OF ROOF PITCH OR PLATE HEIGHT MAY BE REQUIRED IF RAISED FLOOR FOUNDATION IS SELECTED TO MEET HEIGHT REQUIREMENTS.
3. ELEVATIONS & SECTIONS SHALL SHOW BOTH FINISH (CONTINUOUS) & EXISTING (DASHED) GRADE AND THE CORRESPONDING HEIGHT LIMITATION LINE FROM THE LOWER OF THE FINISH OR EXISTING GRADE.
4. IF THE AVERAGE LOT SLOPE EXCEEDS 10% (NOT INCLUDING RR ZONED LOTS) THAN THE ADDITIONAL SLOPED LOT HEIGHT LIMITATION LINES SHALL BE SHOWN AS WELL.



BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.



682 SECOND ST
ENCINITAS, CA
(760) 753 2464
DZNPARTNERS.COM



2 left elevation c

SCALE: 1/4" = 1'-0"





5 right elevation c

SCALE: 1/4" = 1'-0"





3 section e

SCALE: 1/4" = 1'-0"



6 section f

SCALE: 1/4" = 1'-0"



1 BEDROOM
PRADU

CITY: ENCINITAS

JOB: 202241R

ELEVATION C +
SECTION


a4.2

F

T

PREPARER SIGNATURE



FOR CITY STAMPS



2

reverse foundation plan


SCALE: 1/4" = 1'-0"



1

raised floor foundation

SCALE: 1/4" = 1'-0"




raised floor foundation notes:

- EXPANSIVE SOIL LOCATIONS SHALL PROVIDE FOOTING DIMENSIONS SPECIFIED IN DETAILS 3, 4, 7, 8 & 12/ d0.0 FOR EXPANSIVE SOILS.
- ROOF FRAMING PLAN FOR OTHER ELEVATIONS MAY HAVE DIFFERENT SHEAR PANEL LENGTHS. VERIFY SHEAR PANEL LENGTHS WITH ROOF FRAMING PLAN PRIOR TO PLACING HOLD DOWN AND/OR ANCHOR BOLTS.
- PROVIDE FOUNDATION VENTS FOR RAISED FLOOR AREA AT 1 SQ. FT. OF VENT AREA FOR EVERY 150 SQ. FT. OF RAISED FLOOR AREA. 499/150 = 3.33 SQ. FT. TWELVE (12) 3"x14" FOUNDATION VENTS ARE REQUIRED AND SHALL BE EVENLY DISTRIBUTED AT THE FOUNDATION PERIMETER. CRC §408.1
- PROVIDE A 18"x24" FOUNDATION ACCESS TO RAISED FLOOR FOUNDATION AREAS. CRC §408.4
- PROVIDE R-19 BATT INSULATION AT UNDER-FLOOR JOISTS, TYP.
- FLOOR DIAPHRAGM SHALL BE 23/32" APA STURD-I-FLOOR, EXPOSURE 1, 40/20, TONGUE & GROOVE WITH 10d COMMON NAILS @ 6" OC AT BOUNDARY (BN) & PANEL EDGE NAILING (EN) AND 12" OC AT INTERMEDIATE FRAMING MEMBERS (FN).

3

foundation plan

SCALE: 1/4" = 1'-0"



foundation plan notes:

- EXPANSIVE SOIL LOCATIONS SHALL SUBSTITUTE DETAIL 2/60.0 FOR DETAIL 1/60.0 AT PERIMETER FOOTINGS.
- EXPANSIVE SOIL LOCATIONS SHALL SUBSTITUTE DETAIL 6/60.0 FOR DETAIL 5/60.0 AT INTERIOR FOOTINGS.
- ROOF FRAMING PLAN FOR OTHER ELEVATIONS MAY HAVE DIFFERENT SHEAR PANEL LENGTHS. VERIFY SHEAR PANEL LENGTHS WITH ROOF FRAMING PLAN PRIOR TO PLACING HOLD DOWN AND/OR ANCHOR BOLTS.

BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.

DZN PARTNERS
682 SECOND ST
ENCINITAS, CA
(760) 753 2464
DZNPARTNERS.COM

1 BEDROOM PRADU
CITY: ENCINITAS

JOB: 202241R

FOUNDATION PLANS

s1.0

L


T

L


roof framing plan notes:

- ENCLOSED RAFTER SPACES DO NOT REQUIRE VENTING IF THE FOLLOWING SPECIFIC INSULATION DESIGN IS USED, PER SECTION 9005/EM3.9.
 - IF THE INSULATION IS AIR-PERMEABLE AND IT IS INSTALLED DIRECTLY BELOW THE ROOF SHEATHING WITH RIGID BOARD OR SHEET INSULATION WITH A MINIMUM R-5 VALUE INSTALLED ABOVE THE ROOF SHEATHING. (OR)
 - IF THE INSULATION IS AIR-IMPERMEABLE AND IT IS IN DIRECT CONTACT WITH THE UNDERSIDE OF THE ROOF SHEATHING. (OR)
 - IF TWO LAYERS OF INSULATION ARE INSTALLED BELOW THE ROOF SHEATHING: AN AIR-IMPERMEABLE LAYER IN DIRECT CONTACT WITH THE UNDERSIDE OF THE ROOF SHEATHING AND AN ADDITIONAL LAYER OF AIR PERMEABLE INSULATION INSTALLED DIRECTLY UNDER THE AIR-IMPERMEABLE INSULATION.DETAILS 88/d0.7 & 88/d0.4 PROVIDE MORE INFORMATION ABOUT THESE ROOF INSULATION ALTERNATIVES.
- ROOF DIAPHRAGM SHALL BE 15/32" APA RATED SHEATHING (MIN), EXPOSURE 1, 24" MAXIMUM SPAN RATING WITH 8d COMMON NAILS @ 6" OC AT BOUNDARY (BN), PANEL EDGE NAILING (EN) AND 12" OC AT INTERMEDIATE FRAMING MEMBERS (FN).
- 4X6 IS THE MINIMUM MEMBER ALLOWED AT A TRELLIS.
- TRELLIS MEMBERS AND OTHER WEATHER EXPOSED MEMBERS SHALL BE PRESSURE TREATED DOUGLAS FIR (PTDF) OR NATURALLY PEST AND ROT RESISTANT WOOD SPECIES SUCH AS REDWOOD OR CEDAR, TYP, OAE


FOR CITY STAMPS



1 roof framing plan c
SCALE: 1/4" = 1'-0"



2 roof framing plan b
SCALE: 1/4" = 1'-0"



3 roof framing plan a
SCALE: 1/4" = 1'-0"

BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.



682 SECOND ST
ENCINITAS, CA
(760) 753 2464
DZNPARTNERS.COM

1 BEDROOM
PRADU

CITY: ENCINITAS

JOB: 202241R

ROOF FRAMING
PLANS

s2.0



roof framing plan notes:

- ENCLOSED RAFTER SPACES DO NOT REQUIRE VENTING IF THE FOLLOWING SPECIFIC INSULATION DESIGN IS USED, PER SECTION 9005.5/EM3.9.
 - IF THE INSULATION IS AIR-**PERMEABLE** AND IT IS INSTALLED DIRECTLY BELOW THE ROOF SHEATHING WITH RIGID BOARD OR SHEET INSULATION WITH A MINIMUM R-5 VALUE INSTALLED ABOVE THE ROOF SHEATHING. (OR)
 - IF THE INSULATION IS AIR-**IMPERMEABLE** AND IT IS IN DIRECT CONTACT WITH THE UNDERSIDE OF THE ROOF SHEATHING. (OR)
 - IF **TWO LAYERS** OF INSULATION ARE INSTALLED BELOW THE ROOF SHEATHING: AN AIR-**IMPERMEABLE** LAYER IN DIRECT CONTACT WITH THE UNDERSIDE OF THE ROOF SHEATHING AND AN ADDITIONAL LAYER OF AIR-**PERMEABLE** INSULATION INSTALLED DIRECTLY UNDER THE AIR-IMPERMEABLE INSULATION.
DETAILS 88/d0.7 & 88/d0.4 PROVIDE MORE INFORMATION ABOUT THESE ROOF INSULATION ALTERNATIVES.
- ROOF DIAPHRAGM SHALL BE 15/32" APA RATED SHEATHING (MIN), EXPOSURE 1, 24" MAXIMUM SPAN RATING WITH 8d COMMON NAILS @ 6" OC AT BOUNDARY (BN) & PANEL EDGE NAILING (EN) AND 12" OC AT INTERMEDIATE FRAMING MEMBERS (FN).
- 4X6 IS THE MINIMUM MEMBER ALLOWED AT A TRELLIS.
- TRELLIS MEMBERS AND OTHER WEATHER EXPOSED MEMBERS SHALL BE PRESSURE TREATED DOUGLAS FIR (PTDF) OR NATURALLY PEST AND ROT RESISTANT WOOD SPECIES SUCH AS REDWOOD OR CEDAR, TYP.OAE

FOR CITY STAMPS


1 reverse roof framing plan c

SCALE: 1/4" = 1'-0"




2 reverse roof framing plan b

SCALE: 1/4" = 1'-0"



3 reverse roof framing plan a

SCALE: 1/4" = 1'-0"



BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.



682 SECOND ST
ENCINITAS, CA
(760) 753 2464
DZNPARTNERS.COM

1 BEDROOM
PRADU


CITY: ENCINITAS

JOB: 202241R


REVERSE ROOF
FRAMING PLANS

s2.1


MODEL NO.	ANCHOR BOLT	CONNECTION TO POST	EMBEDMENT	EDGE DISTANCE	MIN WD MEMBER THICKNESS
HDU2	5/8" (SSTB16)	6-SDS 1/2"x2 1/2"	12 3/4"	1 3/4"	3"
HDU4	5/8" (SSTB20)	10-SDS 1/2"x2 1/2"	16 3/4"	1 3/4"	3"
HDU5	5/8" (SSTB24)	14-SDS 1/2"x2 1/2"	20 3/4"	1 3/4"	3"
HDU8	5/8" (SSTB28)	20-SDS 1/2"x2 1/2"	24 3/4"	1 3/4"	3"
HDU11	1" (SB1X30)	30-SDS 1/2"x2 1/2"	24"	1 3/4"	5 1/2"
HDU14	1" (SB1X30)	36-SDS 1/2"x2 1/2"	24"	1 3/4"	7 1/4"




17 HOLDOWN AT STEM WALL FOOTING
SCALE: 1" = 1'-0"
A-DT-FDN-SW-0096




18 STANDARD HOOK DETAILS
SCALE = N.T.S.
A-DT-FDN-SG-0041




19 LAP SIDING AT FOUNDATION
SCALE: 1" = 1'-0"
A-DT-FIN-PC5-L5-0001




20 SILL PLATE ANCHOR BOLTING
SCALE: 1" = 1'-0"
A-DT-FDN-SG-ANC-002




13 HOLDOWN - INTERIOR FOOTING
SCALE: 1" = 1'-0"
A-DT-FDN-SG-ANC-017




14 POST FOOTING WITHIN SLAB
SCALE: 1" = 1'-0"
A-DT-FDN-CP-0020




15 BOARD AND BATT SIDING AT FOUNDATION
SCALE: 1" = 1'-0"
A-DT-FIN-PC5-BB-0001




16 TYPICAL CONCRETE / MASONRY WALL REINFORCEMENT
SCALE: 1" = 1'-0"
A-DT-FDN-SW-0021




9 HOLDOWN - PERIMETER FOOTING
SCALE: 1" = 1'-0"
A-DT-FDN-SG-ANC-013




10 TYPICAL POST FOOTING
SCALE: 1" = 1'-0"
A-DT-FDN-CP-0003




11 CEMENT PLASTER WEEP SCREED AT FOUNDATION
SCALE: 1" = 1'-0"
A-DT-FIN-PL-0001




12 FLOOR JOIST AND GIRDER BEAMS AT PAD FOOTING
SCALE: 1" = 1'-0"
A-DT-FDN-SW-0133




5 SLAB ON GRADE ONE STORY INTERIOR FOOTING
SCALE: 1" = 1'-0"
A-DT-FDN-SG-INT-014




6 ONE STORY INTERIOR EXPANSIVE SOIL FOOTING
SCALE: 1" = 1'-0"
A-DT-FDN-SG-INT-015




7 ONE-STOREY INTERIOR STEM WALL FOOTING - PERPENDICULAR
SCALE: 1" = 1'-0"
A-DT-FDN-SW-0073




8 ONE-STOREY INTERIOR STEM WALL FOOTING - PARALLEL
SCALE: 1" = 1'-0"
A-DT-FDN-SW-0134




1 SLAB ON GRADE ONE STORY PERIMETER FOOTING
SCALE: 1" = 1'-0"
A-DT-FDN-SG-PTR-025



2 ONE STORY PERIMETER EXPANSIVE SOIL FOOTING
SCALE: 1" = 1'-0"
A-DT-FDN-SG-PTR-026



3 ONE STORY EXTERIOR STEM WALL FOOTING-PERPENDICULAR
SCALE: 1" = 1'-0"
A-DT-FDN-SW-0002



4 ONE STORY EXTERIOR STEM WALL FOOTING-PARALLEL
SCALE: 1" = 1'-0"
A-DT-FDN-SW-0135

PREPARER SIGNATURE

FOR CITY STAMPS

BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.



6822 SECOND ST
ENCINITAS, CA
(760) 753 2464

DZNPARTNERS.COM


PRADU

CITY: ENCINITAS


JOB: 202241R

DETAILS


d0.0




37 DRAG STRAP AT TOP PLATE TO BEAM OR TOP PLATE
SCALE: 3/4" = 1'-0"
A-DT-FMG-WF-0013




33 TYPICAL SHEAR PANEL
SCALE: N.T.S.
A-DT-FMG-WF-0018




29 WOOD ROOF AND FLOOR SHEATHING LAYOUT
SCALE: 1" = 1'-0"
A-DT-FMG-FF-0002




25 JOIST CUTTING, BORING AND NOTCHING
SCALE: N.T.S.
A-DT-FMG-FF-0005




21 STUD CUTTING, BORING AND NOTCHING
SCALE: N.T.S.
A-DT-FMG-WF-0004




38 POST TO BEAM WITH CCQ/ECCQ
SCALE: 1" = 1'-0"
A-DT-FMG-PB-0007




34 FRAMING FOR ROUGH WINDOW OR DOOR OPENING
SCALE: 1/2" = 1'-0"
A-DT-FMG-WF-0006




30 STUD WALL INTERSECTION
SCALE: 1" = 1'-0"
A-DT-FMG-WF-0005




26 DOUBLE TOP-PLATE SPLICE
SCALE: N.T.S.
A-DT-FMG-WF-0019




22 NON-BEARING/NON-SHEAR PARTITIONS AT TOP
SCALE: 1" = 1'-0"
A-DT-FMG-WF-0008




39 SIDING TO PLASTER AT INSIDE CORNER
SCALE: 1" = 1'-0"
A-DT-FIN-PC5-BB-0004




35 SHEAR WALL DETAIL
SCALE: N.T.S.
A-DT-FMG-WF-0020




31 OPENING BLOCKING AND STRAPPING IN SHEAR PANEL
SCALE: 1/2" = 1'-0"
A-DT-FMG-WF-0009




27 DIAPHRAGM OPENING AT SKYLIGHT
SCALE: 1" = 1'-0"
A-DT-FEN-SL-0007




23 NON-BEARING INTERIOR STUD WALL TO CONCRETE SLAB
SCALE: 1" = 1'-0"
A-DT-FMG-WF-COM-0005




40 SIDING AT OUTSIDE CORNER
SCALE: 1" = 1'-0"
A-DT-FIN-PC5-BB-0002




36 SIDING AT INSIDE CORNER
SCALE: 1" = 1'-0"
A-DT-FIN-PC5-BB-0003



32 ADHERED SIMULATED BRICK OR STONE VENEER AT STUD WALL
SCALE: 1" = 1'-0"
A-DT-FMG-WF-0026



28 CURB MOUNTED SKYLIGHT AT SLOPED ROOF
SCALE: 1" = 1'-0"
A-DT-FEN-SL-0001



24 WINDOW FLASHING
SCALE: 1/2" = 1'-0"
A-DT-FEN-WD-0002

PREPARER SIGNATURE

FOR CITY STAMPS

BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.



682 SECOND ST
ENCINITAS, CA
(760) 753 2464
DZNPARTNERS.COM





















PRADU

CITY: ENCINITAS

JOB: 202241R

DETAILS

d0.1



PREPARER SIGNATURE

FOR CITY STAMPS

BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.

6822 SECOND ST
ENCINITAS, CA
(760) 753 2464
DZNPARTNERS.COM












PRADU

CITY: ENCINITAS

JOB: 202241R

DETAILS

d0.2



FOR CITY STAMPS

d0.3

97

93

89

85

81

98

94

90

86

82

99

95

91

87

83


100

96


92

88


84




89 EXTERIOR ONE HOUR WALL - FIBER CEMENT SIDING EXTERIOR
SCALE: 2' = 1'-0"
A-DT-FIN-FR-WAL-033




85 RIDGE BEAM INTERSECTION WITH VALLEY RAFTERS ABOVE
SCALE: 1' = 1'-0"
A-DT-FIN-FR-RDG-028




81 RAFTERS TO RIDGE BEAM
SCALE: 1' = 1'-0"
A-DT-FMG-RF-RDG-024




90 KING POST WITH SLOPED AND/OR SKEWED TOP BEAM
SCALE: 1' = 1'-0"
A-DT-FMG-PB-0142




86 INSULATION AT UNVENTED ROOF ASSEMBLY - IMPERMEABLE ONLY
SCALE: 1' = 1'-0"
A-DT-FMG-RF-0326




82 FIRE RESISTANCE - ONE HOUR WOOD FRAMED WALLS
SCALE: 1' = 1'-0"
A-DT-FIN-FR-WAL-001




91 PERPENDICULAR JOISTS AT EDGE
SCALE: 1' = 1'-0"
A-DT-FMG-FF-0154




87 INSULATION AT UNVENTED ROOF ASSEMBLY - BOTH TYPES
SCALE: 1' = 1'-0"
A-DT-FMG-RF-0325




83 EXTERIOR STAIRS AT STEM WALL FOOTING
SCALE: 1' = 1'-0"
A-DT-FIN-FR-WAL-025



92 HOLD DOWN AT SHEAR WALL INTERSECTION
SCALE: 1' = 1'-0"
A-DT-FDN-SG-ANC-018



88 INSULATION AT UNVENTED ROOF ASSEMBLY - OVER/UNDER
SCALE: 1' = 1'-0"
A-DT-FMG-RF-0327



84 EXTERIOR STAIRS AT STEM WALL FOOTING
SCALE: 1' = 1'-0"
A-DT-FDN-SW-0136

PREPARER SIGNATURE

FOR CITY STAMPS

BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.



682 SECOND ST
ENCINITAS, CA
(760) 753 2464
DZNPARTNERS.COM

PRADU

CITY: ENCINITAS

JOB: 202241R

DETAILS

d0.4

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan A

Calculation Date/Time: 2023-01-14T16:40:10-08:00

(Page 1 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BA.1-03.rbd22x

GENERAL INFORMATION			
01	Project Name	Encinitas PRADU - 1-Bedroom Plan A	
02	Run Title	Title 24 Analysis	
03	Project Location	Encinitas PRADU Street	
04	City	Encinitas	05 Standards Version
06	Zip code	92024	07 Software Version
08	Climate Zone	7	09 Front Orientation (deg/ Cardinal)
10	Building Type	Single family	11 Number of Dwelling Units
12	Project Scope	Newly Constructed	13 Number of Bedrooms
14	Addition Cond. Floor Area (ft²)	0	15 Number of Stories
16	Existing Cond. Floor Area (ft²)	n/a	17 Fenestration Average U-factor
18	Total Cond. Floor Area (ft²)	499	19 Glazing Percentage (%)
20	ADU Bedroom Count	n/a	

COMPLIANCE RESULTS

01	Building Complies with Computer Performance
02	This building incorporates features that require field testing and/or verification by a certified HERS rater under the supervision of a CEC-approved HERS provider.
03	This building incorporates one or more Special Features shown below

Registration Number: 223-P010006670A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 16:41:01

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan A

Calculation Date/Time: 2023-01-14T16:40:10-08:00

(Page 3 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BA.1-03.rbd22x

ENERGY USE SUMMARY						
Energy Use	Standard Design Source Energy (EDR1) (kBtu/ft²-yr)	Standard Design TDV Energy (EDR2) (kTDV/ft²-yr)	Proposed Design Source Energy (EDR1) (kBtu/ft²-yr)	Proposed Design TDV Energy (EDR2) (kTDV/ft²-yr)	Compliance Margin (EDR1)	Compliance Margin (EDR2)
Space Heating	0.13	0.6	0.75	5.22	-0.62	-4.62
Space Cooling	0.87	18.49	0.65	17.26	0.22	1.23
IAQ Ventilation	0.46	4.94	0.46	4.94	0	0
Water Heating	3.16	36.89	2.2	27.07	0.96	9.82
Self Utilization/Flexibility Credit			0			0
North Facing Efficiency Compliance Total	4.62	60.92	4.06	54.49	0.56	6.43
Space Heating	0.13	0.6	0.91	6.37	-0.78	-5.77
Space Cooling	0.87	18.49	0.71	18.39	0.16	0.1
IAQ Ventilation	0.46	4.94	0.46	4.94	0	0
Water Heating	3.16	36.89	2.22	27.07	0.94	9.82
Self Utilization/Flexibility Credit				0		0
East Facing Efficiency Compliance Total	4.62	60.92	4.3	56.77	0.32	4.15

Registration Number: 223-P010006670A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 16:41:01

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan A

Calculation Date/Time: 2023-01-14T16:40:10-08:00

(Page 2 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BA.1-03.rbd22x

ENERGY DESIGN RATINGS						
	Energy Design Ratings			Compliance Margins		
	Source Energy (EDR1)	Efficiency ¹ EDR (EDR2efficiency)	Total ² EDR (EDR2total)	Source Energy (EDR1)	Efficiency ¹ EDR (EDR2efficiency)	Total ² EDR (EDR2total)
Standard Design	31.4	45.1	31.9			
Proposed Design						
North Facing	30.1	40.3	29.7	1.3	4.8	2.2
East Facing	30.6	42	30.4	0.8	3.1	1.5
South Facing	30.1	39.8	29.4	1.3	5.3	2.5
West Facing	30.3	41.6	30.2	1.1	3.5	1.7
RESULT ³ : PASS						
¹ Efficiency EDR includes improvements like a better building envelope and more efficient equipment						
² Total EDR includes efficiency and demand response measures such as photovoltaic (PV) system and batteries						
³ Building complies when source energy, efficiency and total compliance margins are greater than or equal to zero and unmet load hour limits are not exceeded						
• Standard Design PV Capacity: 1.56 kWdc						
• Proposed PV Capacity Scaling: North (1.56 kWdc) East (1.56 kWdc) South (1.56 kWdc) West (1.56 kWdc)						

Registration Number: 223-P010006670A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 16:41:01

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan A

Calculation Date/Time: 2023-01-14T16:40:10-08:00

(Page 4 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BA.1-03.rbd22x

ENERGY USE SUMMARY						
Energy Use	Standard Design Source Energy (EDR1) (kBtu/ft²-yr)	Standard Design TDV Energy (EDR2) (kTDV/ft²-yr)	Proposed Design Source Energy (EDR1) (kBtu/ft²-yr)	Proposed Design TDV Energy (EDR2) (kTDV/ft²-yr)	Compliance Margin (EDR1)	Compliance Margin (EDR2)
Space Heating	0.13	0.6	0.81	5.67	-0.68	-5.07
Space Cooling	0.87	18.49	0.58	16.08	0.29	2.41
IAQ Ventilation	0.46	4.94	0.46	4.94	0	0
Water Heating	3.16	36.89	2.21	27.06	0.95	9.83
Self Utilization/Flexibility Credit				0		0
South Facing Efficiency Compliance Total	4.62	60.92	4.06	53.75	0.56	7.17
Space Heating	0.13	0.6	0.75	5.25	-0.62	-4.65
Space Cooling	0.87	18.49	0.71	19.04	0.16	-0.55
IAQ Ventilation	0.46	4.94	0.46	4.94	0	0
Water Heating	3.16	36.89	2.21	26.97	0.95	9.92
Self Utilization/Flexibility Credit				0		0
West Facing Efficiency Compliance Total	4.62	60.92	4.13	56.2	0.49	4.72

Registration Number: 223-P010006670A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 16:41:01

General Notes



R19-04-30011
NR19-04-30020

TITLE 24, PART 6 ENERGY COMPLIANCE DOCUMENTATION

No.	Revision/Issue	Date

Firm Name and Address



BEAR TECHNOLOGIES CONSULTING, INC.
3431 DON ARTURO DRIVE,
CARLSBAD, CALIFORNIA 92010
(760) 635-2327
wayne@beartechconsulting.com
http://www.beartechconsulting.com

Project Name and Address

ENCINITAS PRADU - 1 BEDROOM PLAN A
ENCINITAS PRADU STREET
ENCINITAS, CALIFORNIA 92024

Project
23Q1019-1BA.1-03

Date
01/17/2023

Scale

Sheet

T-01

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan A

Calculation Date/Time: 2023-01-14T16:40:10-08:00

(Page 5 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BA.1-03.ribd22x

ENERGY USE INTENSITY				
	Standard Design (kBtu/ft ² - yr)	Proposed Design (kBtu/ft ² - yr)	Compliance Margin (kBtu/ft ² - yr)	Margin Percentage
North Facing				
Gross EUI ¹	23.74	23.61	0.13	0.55
Net EUI ²	6.96	6.83	0.13	1.87
East Facing				
Gross EUI ¹	23.74	23.86	-0.12	-0.51
Net EUI ²	6.96	7.09	-0.13	-1.87
South Facing				
Gross EUI ¹	23.74	23.51	0.23	0.97
Net EUI ²	6.96	6.73	0.23	3.3
West Facing				
Gross EUI ¹	23.74	23.86	-0.12	-0.51
Net EUI ²	6.96	7.08	-0.12	-1.72
Notes				
1. Gross EUI is Energy Use Total (not including PV) / Total Building Area.				
2. Net EUI is Energy Use Total (including PV) / Total Building Area.				

Registration Number: 223-P010006670A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS inc.
Report Generated: 2023-01-14 16:41:01

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan A

Calculation Date/Time: 2023-01-14T16:40:10-08:00

(Page 7 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BA.1-03.ribd22x

BUILDING - FEATURES INFORMATION										
01	02	03	04	05	06	07				
Project Name	Conditioned Floor Area (ft ²)	Number of Dwelling Units	Number of Bedrooms	Number of Zones	Number of Ventilation Cooling Systems	Number of Water Heating Systems				
Encinitas PRADU - 1-Bedroom Plan A	499	1	1	1	1	1				
ZONE INFORMATION										
01	02	03	04	05	06	07				
Zone Name	Zone Type	HVAC System Name	Zone Floor Area (ft ²)	Avg. Ceiling Height	Water Heating System 1	Status				
ADU 1-Bedroom A	Conditioned	Ductless Mini-Split1	499	8	DHW Sys 1	New				
OPAQUE SURFACES										
01	02	03	04	05	06	07	08			
Name	Zone	Construction	Azimuth	Orientation	Gross Area (ft ²)	Window and Door Area (ft2)	Tilt (deg)			
Front Wall	ADU 1-Bedroom A	_WALL: 2x4 Exterior	0	Front	321	54.5	90			
Left Wall	ADU 1-Bedroom A	_WALL: 2x4 Exterior	90	Left	126	48	90			
Rear Wall	ADU 1-Bedroom A	_WALL: 2x4 Exterior	180	Back	321	70	90			
Right Wall	ADU 1-Bedroom A	_WALL: 2x4 Exterior	270	Right	126	64	90			
Roof 2	ADU 1-Bedroom A	_ROOF: CLG.	n/a	n/a	200	n/a	n/a			
OPAQUE SURFACES - CATHEDRAL CEILINGS										
01	02	03	04	05	06	07	08	09	10	11
Name	Zone	Construction	Azimuth	Orientation	Area (ft ²)	Skylight Area (ft ²)	Roof Rise (x in 12)	Roof Reflectance	Roof Emittance	Cool Roof
Roof	ADU 1-Bedroom A	_ROOF: SLPD. CLG.	0	Front	299	0	4	0.1	0.85	No

Registration Number: 223-P010006670A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS inc.
Report Generated: 2023-01-14 16:41:01

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan A

Calculation Date/Time: 2023-01-14T16:40:10-08:00

(Page 6 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BA.1-03.ribd22x

REQUIRED PV SYSTEMS											
01	02	03	04	05	06	07	08	09	10	11	12
DC System Size (kWdc)	Exception	Module Type	Array Type	Power Electronics	CFI	Azimuth (deg)	Tilt Input	Array Angle (deg)	Tilt: (x in 12)	Inverter Eff. (%)	Annual Solar Access (%)
1.56	NA	Standard (14-17%)	Fixed	none	true	150-270	n/a	n/a	<= 7:12	96	98
REQUIRED SPECIAL FEATURES											
The following are features that must be installed as condition for meeting the modeled energy performance for this computer analysis.											
<ul style="list-style-type: none">Whole house fanExposed slab floor in conditioned zoneVariable capacity heat pump compliance option (verification details from VCHP Staff report, Appendix B, and RA3)Northwest Energy Efficiency Alliance (NEEA) rated heat pump water heater; specific brand/model, or equivalent, must be installed											
HERS FEATURE SUMMARY											
The following is a summary of the features that must be field-verified by a certified HERS Rater as a condition for meeting the modeled energy performance for this computer analysis. Additional detail is provided in the building tables below. Registered EF2Rs and CF3Rs are required to be completed in the HERS Registry.											
<ul style="list-style-type: none">Indoor air quality ventilationKitchen range hoodWhole house fan airflow and fan efficacyVerified EER/EER2Verified SEER/SEER2Verified Refrigerant ChargeAirflow in habitable rooms (SC3.1.4.1.7)Verified HSPF2Verified heat pump rated heating capacityWall-mounted thermostat in zones greater than 150 ft2 (SC3.4.5)Ductless indoor units located entirely in conditioned space (SC3.1.4.1.8)											

Registration Number: 223-P010006670A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS inc.
Report Generated: 2023-01-14 16:41:01

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan A

Calculation Date/Time: 2023-01-14T16:40:10-08:00

(Page 8 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BA.1-03.ribd22x

ATTIC													
01	02	03	04		05		06		07		08		
Name	Construction	Type	Roof Rise (x in 12)		Roof Reflectance		Roof Emittance		Radiant Barrier		Cool Roof		
Attic ADU 1-Bedroom A	Attic RoofADU 1-Bedroom A	Ventilated	4		0.1		0.85		Yes		No		
FENESTRATION / GLAZING													
01	02	03	04	05	06	07	08	09	10	11	12	13	14
Name	Type	Surface	Orientation	Azimuth	Width (ft)	Height (ft)	Mult.	Area (ft²)	U-factor	U-factor Source	SHGC	SHGC Source	Exterior Shading
w1	Window	Front Wall	Front	0			1	18	0.58	NFRC	0.65	NFRC	Bug Screen
d1	Window	Front Wall	Front	0			1	24	0.58	NFRC	0.65	NFRC	Bug Screen
w5	Window	Front Wall	Front	0			1	12.5	0.58	NFRC	0.65	NFRC	Bug Screen
d3	Window	Left Wall	Left	90			1	48	0.58	NFRC	0.65	NFRC	Bug Screen
w4	Window	Rear Wall	Back	180			1	18	0.58	NFRC	0.65	NFRC	Bug Screen
w3	Window	Rear Wall	Back	180			1	8	0.58	NFRC	0.65	NFRC	Bug Screen
w2	Window	Rear Wall	Back	180			1	8	0.58	NFRC	0.65	NFRC	Bug Screen
w1 2	Window	Rear Wall	Back	180			1	18	0.58	NFRC	0.65	NFRC	Bug Screen
w1 3	Window	Rear Wall	Back	180			1	18	0.58	NFRC	0.65	NFRC	Bug Screen
d2	Window	Right Wall	Right	270			1	64	0.58	NFRC	0.65	NFRC	Bug Screen

Registration Number: 223-P010006670A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS inc.
Report Generated: 2023-01-14 16:41:01

General Notes



R19-04-30011
NR19-04-30020

TITLE 24, PART 6 ENERGY COMPLIANCE DOCUMENTATION

No.	Revision/Issue	Date

Firm Name and Address



BEAR TECHNOLOGIES CONSULTING, INC.
3431 DON ARTURO DRIVE,
CARLSBAD, CALIFORNIA 92010
(760) 635-2327
wayne@beartechconsulting.com
http://www.beartechconsulting.com

Project Name and Address

ENCINITAS PRADU - 1 BEDROOM PLAN A
ENCINITAS PRADU STREE
ENCINITAS, CALIFORNIA 92024

Project
23Q1019-1BA.1-03

Sheet

Date
01/17/2023

T-02

Scale

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan A

Calculation Description: Title 24 Analysis

Calculation Date/Time: 2023-01-14T16:40:10-08:00

Input File Name: 23Q1019-1BA.1-03.ribd22x

(Page 9 of 13)

01	02	03	04	05	06	07	08
Name	Zone	Area (ft²)	Perimeter (ft)	Edge Insul. R-value and Depth	Edge Insul. R-value and Depth	Carpeted Fraction	Heated
Slab On Grade	ADU 1-Bedroom A	499	99	none	0	0%	No

OPAQUE SURFACE CONSTRUCTIONS

01	02	03	04	05	06	07	08
Construction Name	Surface Type	Construction Type	Framing	Total Cavity R-value	Interior / Exterior Continuous R-value	U-factor	Assembly Layers
_WALL: 2x4 Exterior	Exterior Walls	Wood Framed Wall	2x4 @ 16 in. O. C.	R-15	None / None	0.095	Inside Finish: Gypsum Board Cavity / Frame: R-15 / 2x4 Exterior Finish: All Other Siding
_ROOF: SLPD, CLG.	Cathedral Ceilings	Wood Framed Ceiling	2x10 @ 24 in. O. C.	R-30	None / None	0.035	Roofing: Light Roof (Asphalt Shingle) Roof Deck: Wood Siding/sheathing/decking Cavity / Frame: R-30 / 2x10 Inside Finish: Gypsum Board
Attic Roof/ADU 1-Bedroom A	Attic Roofs	Wood Framed Ceiling	2x4 @ 24 in. O. C.	R-0	None / 0	0.644	Roofing: Light Roof (Asphalt Shingle) Roof Deck: Wood Siding/sheathing/decking Cavity / Frame: no insul. / 2x4
_ROOF: CLG.	Ceilings (below attic)	Wood Framed Ceiling	2x4 @ 16 in. O. C.	R-30	None / None	0.032	Over Ceiling Joists: R-20.9 insul. Cavity / Frame: R-9.1 / 2x4 Inside Finish: Gypsum Board

BUILDING ENVELOPE - HERS VERIFICATION

01	02	03	04	05
Quality Insulation Installation (QII)	High R-value Spray Foam Insulation	Building Envelope Air Leakage	CFM50	CFM50
Not Required	Not Required	N/A	n/a	n/a

Registration Number:

223-P010006670A-000-000-00000000-0000

CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time:

2023-01-17 12:07:36

Report Version: 2022.0.000

Schema Version: rev 20220901

HERS Provider:

CalCERTS Inc.

Report Generated: 2023-01-14 16:41:01

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan A

Calculation Description: Title 24 Analysis

Calculation Date/Time: 2023-01-14T16:40:10-08:00

Input File Name: 23Q1019-1BA.1-03.ribd22x

(Page 10 of 13)

01	02	03	04	05	06	07	08	09
Name	System Type	Distribution Type	Water Heater Name	Number of Units	Solar Heating System	Compact Distribution	HERS Verification	Water Heater Name (#)
DHW Sys 1	Domestic Hot Water (DHW)	Standard	DHW Heater 1	1	n/a	None	n/a	DHW Heater 1 (1)

WATER HEATERS - NEEA HEAT PUMP

01	02	03	04	05	06	07	08
Name	# of Units	Tank Vol. (gal)	NEEA Heat Pump Brand	NEEA Heat Pump Model	Tank Location	Duct Inlet Air Source	Duct Outlet Air Source
DHW Heater 1	1	50	AOSmith	AOSmithFPTU50	ADU 1-Bedroom A	ADU 1-Bedroom A	ADU 1-Bedroom A

WATER HEATING - HERS VERIFICATION

01	02	03	04	05	06	07
Name	Pipe Insulation	Parallel Piping	Compact Distribution	Compact Distribution Type	Recirculation Control	Shower Drain Water Heat Recovery
DHW Sys 1 - 1/1	Not Required	Not Required	Not Required	None	Not Required	Not Required

SPACE CONDITIONING SYSTEMS

01	02	03	04	05	06	07	08	09
Name	System Type	Heating Unit Name	Heating Equipment Count	Cooling Unit Name	Cooling Equipment Count	Fan Name	Distribution Name	Required Thermostat Type
Ductless Mini-Split1	Heat pump heating cooling	Heat Pump System 1	1	Heat Pump System 1	1	n/a	n/a	Setback

Registration Number:

223-P010006670A-000-000-00000000-0000

CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time:

2023-01-17 12:07:36

Report Version: 2022.0.000

Schema Version: rev 20220901

HERS Provider:

CalCERTS Inc.

Report Generated: 2023-01-14 16:41:01

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan A

Calculation Description: Title 24 Analysis

Calculation Date/Time: 2023-01-14T16:40:10-08:00

Input File Name: 23Q1019-1BA.1-03.ribd22x

(Page 11 of 13)

01	02	03	04	05	06	07	08	09	10	11	12	13
Name	System Type	Number of Units	Efficiency Type	HSPF / HSPF2 / COP	Cap 47	Cap 17	Efficiency Type	SEER / SEER2	EER / CEER	Zonally Controlled	Compressor Type	HERS Verification
Heat Pump System 1	VCHP-ductless	1	HSPF2	13.1	28000	16800	EER2SEER2	18.9	13	Zonally Controlled	Multi-speed	Heat Pump System 1-hers-htpump

HVAC HEAT PUMPS - HERS VERIFICATION

01	02	03	04	05	06	07	08	09
Name	Verified Airflow	Airflow Target	Verified EER/EER2	Verified SEER/SEER2	Verified Refrigerant Charge	Verified HSPF/HSPF2	Verified Heating Cap 47	Verified Heating Cap 17
Heat Pump System 1-hers-htpump	Not Required	0	Not Required	Not Required	Yes	No	Yes	Yes

VARIABLE CAPACITY HEAT PUMP COMPLIANCE OPTION - HERS VERIFICATION

01	02	03	04	05	06	07	08	09	10
Name	Certified Low-Static VCHP System	Airflow to Habitable Rooms	Ductless Units in Conditioned Space	Wall Mount Thermostat	Air Filter Sizing & Pressure Drop Rating	Low Leakage Ducts in Conditioned Space	Minimum Airflow per RA3.3 and SC3.3.3.4.1	Certified non-continuous Fan	Indoor Fan not Running Continuously
Heat Pump System 1	Not required	Required	Required	Required	Not required	Not required	Not required	Not required	Not required

INDOOR AIR QUALITY (IAQ) FANS

01	02	03	04	05	06	07	08	09
Dwelling Unit	Airflow (CFM)	Fan Efficacy (W/CFM)	IAQ Fan Type	Includes Heat/Energy Recovery?	IAQ Recovery Effectiveness - SRE	Includes Fault Indicator Display?	HERS Verification	Status
Sfam IAQVentRpt	30	0.35	Exhaust	No	n/a	No	Yes	

Registration Number:

223-P010006670A-000-000-00000000-0000

CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time:

2023-01-17 12:07:36

Report Version: 2022.0.000

Schema Version: rev 20220901

HERS Provider:

CalCERTS Inc.

Report Generated: 2023-01-14 16:41:01

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan A

Calculation Description: Title 24 Analysis

Calculation Date/Time: 2023-01-14T16:40:10-08:00

Input File Name: 23Q1019-1BA.1-03.ribd22x

(Page 12 of 13)

01	02	03	04	05	06	07	08	09
Name	Airflow Rate (CFM/h2)	Cooling Vent CFM	Cooling Vent Watts/CFM	Total Watts	Number of Fans	CFVCS Type	Exhausts to	HERS Verification
WH Fan 1	0.04	20	0.05	1	1	Not a CFVCS	Outside	Required

PROJECT NOTES

This report is based on the drawings received on 01/03/2023.

SCOPE OF WORK: Construct a ADU - 1-Bedroom (A Elevation).

1) DO NOT USE FOR ACTUAL HEATING/COOLING DESIGN. 2) The Title 24 calculations used for this project are used for the purpose of complying with the current Title 24 code provisions and are intended to be used in order to obtain compliance per Title 24 regulations. They are NOT intended to be used as a substitute for the heating and cooling loads required for the structure(s) that are normally done by a mechanical engineer(s) or HVAC contractor(s) and in NO CIRCUMSTANCES is this to be used in lieu of the normal calculation methods used by a mechanical engineer(s) or HVAC contractor(s). 3) The assembly components found in this document are for modeling purposes only and may not reflect the actual conditions of the walls, roof(s), floor(s), windows and doors of the structure.

Registration Number:

223-P010006670A-000-000-00000000-0000

CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time:

2023-01-17 12:07:36

Report Version: 2022.0.000

Schema Version: rev 20220901

HERS Provider:

CalCERTS Inc.

Report Generated: 2023-01-14 16:41:01

General Notes



R19-04-30011
NR19-04-30020

TITLE 24, PART 6 ENERGY COMPLIANCE DOCUMENTATION

No. Revision/Issue Date

Firm Name and Address



BEAR TECHNOLOGIES CONSULTING, INC.
3431 DON ARTURO DRIVE,
CARLSBAD, CALIFORNIA 92010
(760) 635-2327
wayne@beartechconsulting.com
http://www.beartechconsulting.com

Project Name and Address

ENCINITAS PRADU - 1 BEDROOM PLAN A
ENCINITAS PRADU STREE
ENCINITAS, CALIFORNIA 92024

Project
23Q1019-1BA.1-03

Date
01/17/2023

Scale

Sheet

T-03

2022 Single-Family Residential Mandatory Requirements Summary	
NOTE: Single-family residential buildings subject to the Energy Codes must comply with all applicable mandatory measures, regardless of the compliance approach used. Review the respective section for more information. (04/2022)	
Building Envelope:	
§ 110.6(a)(1):	Air Leakage. Manufactured fenestration, exterior doors, and exterior pet doors must limit air leakage to 0.3 CFM per square foot or less when tested per NFRC-200, ASTM F283, or AIAA/USMA/CSA 1915.5-2004/2011.*
§ 110.6(a)(5):	Labeling. Fenestration products and exterior doors must have a label meeting the requirements of § 10-111(a).
§ 110.6(a)(9):	Field fabricated exterior doors and fenestration products must use U-factors and solar heat gain coefficient (SHGC) values from Tables 110.6-A, 110.6-B, or A4.4 for exterior doors. They must be gasketed and/or weather stripped.
§ 110.7:	Air Leakage. All joints, penetrations, and other openings in the building envelope that are potential sources of air leakage must be caulked, gasketed, or weather stripped.
§ 110.8(a):	Insulation Certification by Manufacturers. Insulation must be certified by the Department of Consumer Affairs, Bureau of Household Goods and Services (BHGS).
§ 110.8(a):	Insulation Requirements for Heated Slab Floors. Heated slab floors must be insulated per the requirements of § 110.8(g).
§ 110.8(i):	Roofing Products Solar Reflectance and Thermal Emittance. The thermal emittance and aged solar reflectance values of the roofing material must meet the requirements of § 110.8(j) and be labeled per §10-113 when the installation of a cool roof is specified on the CFR.
§ 110.8(j):	Radiant Barrier. When required, radiant barriers must have an emittance of 0.05 or less and be certified to the Department of Consumer Affairs.
§ 150.0(a):	Roof Deck, Ceiling and Rafter Roof Insulation. Roof decks in newly constructed attics in climate zones 4 and 5-16 area-weighted average U-factor not exceeding U-0.104. Ceiling and rafter roofs minimum R-22 insulation in wood-frame ceiling, or area-weighted average U-factor must not exceed 0.045. Rafter roof alterations minimum R-19 or area-weighted average U-factor of 0.054 or less. Attic access doors must have permanently attached insulation using adhesive or mechanical fasteners. The attic access must be gasketed to prevent air leakage. Insulation must be installed in direct contact with a roof or ceiling which is sealed to limit infiltration and exfiltration, as specified in § 110.7, including but not limited to placing insulation either above or below the roof deck or on top of a drywall ceiling.
§ 150.0(b):	Loose-fill Insulation. Loose fill insulation must meet the manufacturer's required density for the labeled R-value.
§ 150.0(c):	Wall Insulation. Minimum R-13 insulation in 2x4 inch wood framing wall or have a U-factor of 0.102 or less, or R-20 in 2x6 inch wood framing or have a U-factor of 0.077 or less. Cavity non-frame assemblies must have an overall assembly U-factor not exceeding 0.102. Masonry walls must meet Tables 150.1-A or B.*
§ 150.0(d):	Raised-floor Insulation. Minimum R-10 insulation in raised wood framed floor or 0.037 maximum U-factor.*
§ 150.0(f):	Slab Edge Insulation. Slab edge insulation must meet all of the following: have a water vapor permeance no greater than 2.0 perm per inch; be protected from physical damage and UV light deterioration; and, when installed as part of a heated slab floor, meet the requirements of § 110.8(g).
§ 150.0(g):	Vapor Retarder. In climate zones 1 through 16, the earth floor of unvented crawl spaces must be covered with a Class I or Class II vapor retarder. This requirement also applies to controlled ventilation crawl space for buildings complying with the exception to § 150.0(g).
§ 150.0(g)(2):	Vapor Retarder. In climate zones 14 and 16, a Class I or Class II vapor retarder must be installed on the conditioned space side of all insulation in all exterior walls, vented attics, and unvented attics with air-permeable insulation.
§ 150.0(g)(2):	Fenestration Products. Fenestration, including skylights, separating conditioned space from unconditioned space or outdoors must have a maximum U-factor of 0.45 or area-weighted average U-factor of all fenestration must not exceed 0.45.
Fireplaces, Decorative Gas Appliances, and Gas Logs:	
§ 110.5(a):	Pilot Light. Continuously burning pilot lights are not allowed for indoor and outdoor fireplaces.
§ 150.0(a)(1):	Closable Doors. Masonry or factory-built fireplaces must have a closable metal or glass door covering the entire opening of the firebox.
§ 150.0(a)(2):	Combustion Intake. Masonry or factory-built fireplaces must have a combustion outside air intake, which is at least six square inches in area and is equipped with a readily accessible, operable, non-flaming damper for manual service.
§ 150.0(a)(3):	Flue Damper. Masonry or factory-built fireplaces must have a flue damper with a readily accessible control.*
Space Conditioning, Water Heating, and Plumbing Systems:	
§ 110.0(a) § 110.3:	Certification. Heating, ventilation, and air conditioning (HVAC) equipment, water heaters, showerheads, faucets, and all other regulated appliances must be certified by the manufacturer to the California Energy Commission.
§ 110.2(a):	HVAC Efficiency. Equipment must meet the applicable efficiency requirements in Table 110.2-A through Table 110.2-F.*
§ 110.2(b):	Controls for Heat Pumps with Supplementary Electric Resistance Heaters. Heat pumps with supplementary electric resistance heaters must have controls that prevent supplementary heater operation when the heating load can be met by the heat pump alone; and in which the cut-on temperature for compression heating is higher than the cut-on temperature for supplementary heating; and the cut-off temperature for compression heating is higher than the cut-off temperature for supplementary heating.
§ 110.2(c):	Thermostats. All heating or cooling systems not controlled by a central energy management control system (EMCS) must have a setback thermostat.*
§ 110.3(c)(3):	Insulation. Unified service water heater storage tanks and solar water-heating backup tanks must have adequate insulation, or tank surface heat loss rating.
§ 110.3(c)(3):	Isolation Valves. Instantaneous water heaters with an input rating greater than 6.8 kBtu per hour (2 kW) must have isolation valves with hose bibbs or other fittings on both cold and hot water lines to allow for shutting the water heater when the valves are closed.

5/6/22

2022 Single-Family Residential Mandatory Requirements Summary	
Space Conditioning System Airflow Rate and Fan Efficiency. Space conditioning systems that use ducts to supply cooling must have a hole for the placement of a static pressure probe, or a permanently installed static pressure probe in the supply plenum. Airflow must be ≥ 200 CFM per ton of nominal cooling capacity, and an air-handling unit fan efficiency ≥ 0.45 watts per CFM for gas furnace or handlers and ≥ 0.58 watts per CFM for all others. Small duct high velocity systems must provide an airflow ≥ 250 CFM per ton of nominal cooling capacity, and an air-handling unit fan efficiency ≥ 0.62 watts per CFM. Field verification testing is required in accordance with Reference Residential Appendix RA3.3.*	
Ventilation and Indoor Air Quality:	
§ 150.0(a)(1):	Requirements for Ventilation and Indoor Air Quality. All dwelling units must meet the requirements of ASHRAE Standard 62.2, Ventilation and Acceptable Indoor Air Quality in Residential Buildings subject to the amendments specified in § 150.0(a)1.*
§ 150.0(a)(1B):	Central Fan Integrated (CFI) Ventilation Systems. Continuous operation of CFI air handlers is not allowed to provide the whole-dwelling unit airflow required per §150.0(a)(1C). A motorized damper(s) must be installed on the supply (duct(s)) that prevents all airflow through the space conditioning duct system when the damper(s) is closed and/or controlled per §150.0(a)(1B)(ii). CFI ventilation systems must have controls that track outdoor air ventilation run time, and either open or close the motorized damper(s) for compliance with §150.0(a)(1C).
§ 150.0(a)(1C):	Whole-Dwelling Unit Mechanical Ventilation for Single-Family Detached and townhouses. Single-family detached dwelling units, and attached dwelling units not sharing ceilings or floors with other dwelling units, occupiable spaces, public garages, or commercial spaces must have mechanical ventilation airflow specified in § 150.0(a)(1C)-i.
§ 150.0(a)(1G):	Local Mechanical Exhaust. Kitchens and bathrooms must have local mechanical exhaust; nonvented kitchens must have demand-controlled exhaust system meeting requirements of §150.0(a)(1G) enclosed kitchens and bathrooms can use demand-controlled or continuous exhaust meeting §150.0(a)(1G)-iv. Airflow must be measured by the installer per §150.0(a)(1G)-v, and rated for sound per §150.0(a)(1G)-vi.*
§ 150.0(a)(1H4):	Airflow Measurement and Sound Ratings of Whole-Dwelling Unit Ventilation Systems. The airflow required per § 150.0(a)(1C) must be measured by using a flow hood, flow grid, or other airflow measuring device at the fan's inlet or outlet terminal(s) per Reference Residential Appendix RA3.7. Whole-Dwelling unit ventilation systems must be rated for sound per ASHRAE 62.2 § 7.4 at no less than the minimum airflow rate required by §150.0(a)(1C).
§ 150.0(a)(2):	Field Verification and Diagnostic Testing. Whole-Dwelling Unit ventilation airflow, vented range hood airflow and sound rating, and HVAC and ERV fan efficiency must be verified in accordance with Reference Residential Appendix RA3.7. Vented range hoods must be verified per Reference Residential Appendix RA3.7.4.2 to confirm if it is rated by HVH or AHAM to comply with the airflow rates and sound requirements per §150.0(a)(1G).
Pool and Spa Systems and Equipment:	
§ 110.4(a):	Certification by Manufacturers. Any pool or spa heating system or equipment must be certified to have all of the following: compliance with the Appliance Efficiency Regulations and listing in MAEDS; an on-off switch mounted outside of the heater that allows shutting off the heater without adjusting the thermostat setting; a permanent waterproof plate or card with operating instructions; and must not use electric resistance heating.*
§ 110.4(a)(1):	Piping. Any pool or spa heating system or equipment must be installed with at least 36 inches of pipe between the filter and the heater, or dedicated suction and return lines, or bulkhead or bulkhead connections to allow for future solar water heating.
§ 110.4(a)(2):	Covers. Outdoor pools or spas that have a heat pump or gas heater must have a cover.
§ 110.4(a)(3):	Directional Inlets and Time Switches for Pools. Pools must have directional inlets that adequately mix the pool water, and a time switch with an auto pump to be set or programmed to run only during off-peak electric demand periods.
§ 110.5:	Pilot Light. Natural gas pool and spa heaters must have a continuously burning pilot light.
§ 150.0(a):	Pool Systems and Equipment Installation. Residential pool systems or equipment must meet the specified requirements for pump sizing, flow rate, piping, filters, and valves.
Lighting:	
§ 110.9:	Lighting Controls and Components. All lighting control devices and systems, ballasts, and luminaires must meet the applicable requirements of § 110.9.*
§ 150.0(a)(1A):	Luminaire Efficacy. All installed luminaires must meet the requirements in Table 150.0-A, except lighting integral to exhaust fans, kitchen range hoods, bath vanity mirrors, and grille-type doors, regardless lighting type. Plan 5 watts, and lighting integral to doors, cabinets, and linen closets with an efficacy of at least 62 lumens per watt.
§ 150.0(a)(1B):	Screw-based luminaires. Screw-based luminaires must contain lamps that comply with Reference Joint Appendix JA3.*
§ 150.0(a)(1C):	Recessed Downlight Luminaires in Ceilings. Luminaires recessed into ceilings must not contain screw-based sockets, must be airtight, and must be sealed to the ceiling with a California Electrical Code-compliant sealant.
§ 150.0(a)(1D):	Light Sources in Enclosed or Recessed Luminaires. Lamps and other separable light sources that are not compliant with the JAB elevated temperature requirements, including marking requirements, must not be installed in enclosed or recessed luminaires.
§ 150.0(a)(1E):	Blank Electrical Boxes. The number of electrical boxes that are more than five feet above the finished floor and do not contain a luminaire or other device shall be no more than the number of bedrooms. These boxes must be served by a dimmer, vacancy sensor control, low-voltage wiring, or a fan speed control.
§ 150.0(a)(1F):	Lighting Integral to Exhaust Fans. Lighting integral to exhaust fans (except when installed by the manufacturer in kitchen exhaust hoods) must meet the applicable requirements of § 150.0(a).

5/6/22

2022 Single-Family Residential Mandatory Requirements Summary	
§ 110.5:	Pilot Lights. Continuously burning pilot lights are prohibited for natural gas, fan-type central furnaces, household cooking appliances (except appliances without an electrical supply voltage connection with pilot lights that consume less than 150 Btu per hour); and pool and spa heaters.
§ 150.0(h)(1):	Building Cooling and Heating Loads. Heating and/or cooling loads are calculated in accordance with the ASHRAE Handbook, Equipment Volume, Applications Volume, and Fundamentals Volume, the SMACNA Residential Control System Installation Standards Manual, or the ACCA Manual of Design Conditions specified in § 150.0(h)(2).
§ 150.0(h)(3A):	Clearances. Air conditioner and heat pump outdoor condensing units must have a clearance of at least five feet from the outlet of any dryer.
§ 150.0(h)(3B):	Liquid Line Drier. Air conditioners and heat pump systems must be equipped with liquid line filter driers if required, as specified by the manufacturer's instructions.
§ 150.0(i)(1):	Water Piping, Solar Water-heating System Piping, and Space Conditioning System Line Insulation. All domestic hot water piping must be insulated as specified in § 150.11 of the California Plumbing Code.*
§ 150.0(i)(2):	Insulation Protection. Piping insulation must be protected from damage, including that due to sunlight, moisture, equipment maintenance, and wind as required by §120.3(h). Insulation exposed to weather must be water resistant and protected from UV light (no adhesive tapes). Insulation covering chilled water piping and refrigerant suction piping located outside the conditioned space must include, or be protected by, a Class I or Class II vapor retarder. Pipe insulation buried below grade must be installed in a waterproof and non-crushable casing or sleeve.
§ 150.0(i)(1):	Gas or Propane Water Heating Systems. Systems using gas or propane water heaters to serve individual dwelling units must designate a space at least 2.5 x 2.5 x 7' suitable for the future installation of a heat pump water heater, and meet electrical and plumbing requirements, based on the distance between this designated space and the water heater location; and a condensate drain no more than 2" higher than the base of the water heater.
§ 150.0(i)(3):	Solar Water-heating Systems. Solar water-heating systems and collectors must be certified and rated by the Solar Rating and Certification Corporation (SRCC), the International Association of Plumbing and Mechanical Officials, Research and Testing (IAPMO RST), or by a listing agency that is approved by the executive director.
Ducts and Fans:	
§ 110.8(g)(3):	Ducts. Insulation installed on an existing space-conditioning duct must comply with § 804.0 of the California Mechanical Code (CMC), if a contractor installs the insulation, the contractor must certify to the customer, in writing, that the insulation meets this requirement.
§ 150.0(j)(1):	CMC Compliance. All air distribution system ducts and plenums must meet CMCS 601.0-606.0 and ANSI/SMACNA 605-2009 HVAC Duct Construction Standards Metal and Flexible 3rd Edition. Portions of supply-air and return-air ducts and plenums must be insulated to R-6.0 or higher; ducts located entirely in conditioned space as confirmed through field verification and diagnostic testing (RA3.1.4.3.8) do not require insulation. Connections of metal ducts and inner cores of flexible ducts must be mechanically fastened. Openings must be sealed with mastic, tape, or other duct-sealing system that meets the applicable UL requirements, or aerosol sealant that meets UL 723. The combination of mastic and other mesh tape must be used to seal openings greater than 1/4". If mastic or tape is used, Building cavities, air handler support panel or constructed plenums designed or constructed with materials other than sealed sheet metal, duct board or flexible duct must not be used to convey conditioned air. Bidding cavities and support platforms may contain ducts; ducts installed in these spaces must not be compressed.*
§ 150.0(j)(2):	Factory-fabricated Duct Systems. Factory-fabricated duct systems must comply with applicable requirements for duct construction, connections, and closures; joints and seams of duct systems and their components must not be sealed with cloth back rubber adhesive duct tapes unless such tape is used in combination with mastic and draw bands.
§ 150.0(j)(3):	Field-fabricated Duct Systems. Field-fabricated duct systems must comply with applicable requirements for: pressure-sensitive tapes, mastics, sealants, and other requirements specified for duct construction.
§ 150.0(j)(7):	Backdraft Damper. Fan systems that exchange air between the conditioned space and outdoors must have backdraft or automatic damper.
§ 150.0(j)(8):	Gravity Ventilation Systems. Gravity ventilating systems serving conditioned space must have either automatic or readily accessible, manually operated dampers in all openings to the outside, except combustion inlet and outlet air openings and elevator shaft vents.
§ 150.0(j)(9):	Protection of Insulation. Insulation must be protected from damage due to sunlight, moisture, equipment maintenance, and wind as required by §120.3(h). Insulation exposed to weather must be water resistant and protected from UV light (no adhesive tapes). Insulation covering chilled water piping and refrigerant suction piping located outside the conditioned space must include, or be protected by, a Class I or Class II vapor retarder. Pipe insulation buried below grade must be installed in a waterproof and non-crushable casing or sleeve.
§ 150.0(j)(10):	Porous Inner Core Flex Duct. Porous inner cores of flex ducts must have a non-porous layer or air barrier between the inner core and outer support barrier.
§ 150.0(j)(11):	Duct System Sealing and Leakage Test. When space conditioning systems use forced air duct systems to supply conditioned air to an occupiable space, the ducts must be sealed and air leakage tested, as confirmed through field verification and diagnostic testing, in accordance with Reference Residential Appendix RA3.1.
§ 150.0(j)(12):	Air Filtration. Space conditioning systems with ducts exceeding 10 feet and the supply side of ventilation systems must have MERV 13 or equivalent filters. Filters for space conditioning systems must be replaced at least once a year. Clean filter pressure drop and labeling must comply with requirements in §150.0(m)(2). Filters must be accessible to regular service. Filter racks or grilles must use gaskets, sealing, or other means to close gaps around the inserted filters to and prevent air from bypassing the filter.*

5/6/22

2022 Single-Family Residential Mandatory Requirements Summary	
§ 150.0(h)(10):	Screw-based luminaires. Screw-based luminaires must contain lamps that comply with Reference Joint Appendix JA3.*
§ 150.0(h)(14):	Light Sources in Enclosed or Recessed Luminaires. Lamps and other separable light sources that are not compliant with the JAB elevated temperature requirements, including marking requirements, must not be installed in enclosed or recessed luminaires.
§ 150.0(h)(1):	Light Sources in Drawers, Cabinets, and Linen Closets. Light sources internal to drawers, cabinets or linen closets are not required to comply with Table 150.0-A or be controlled by vacancy sensors provided that they are rated to consume no more than 5 watts of power, and no more than 150 lumens, and are equipped with controls that automatically turn the lighting off when the drawer, cabinet or linen closet is closed.
§ 150.0(i)(2A):	Interior Switches and Controls. All forward phase out dimmers used with LED light sources must comply with NEMA SSL-7A.
§ 150.0(i)(2B):	Interior Switches and Controls. Exhaust fans must be controlled separately from lighting systems.*
§ 150.0(i)(2A):	Accessible Controls. Lighting must have readily accessible wall-mounted controls that allow the lighting to be manually turned on and off.*
§ 150.0(i)(2B):	Multiple Controls. Controls must not bypass a dimmer, occupant sensor, or vacancy sensor function if the dimmer or sensor is installed to comply with § 150.0(h).
§ 150.0(i)(2C):	Mandatory Requirements. Lighting controls must comply with the applicable requirements of § 110.9.
§ 150.0(i)(2D):	Energy Management Control Systems. An energy management control system (EMCS) may be used to comply with dimming, occupancy, and control requirements if it provides the functionality of the specified control per § 110.9 and the physical controls specified in § 150.0(i)(2A).
§ 150.0(i)(2E):	Automatic Shutoff Controls. In bathrooms, garages, laundry rooms, utility rooms and walk-in closets, at least one installed luminaire must be controlled by an occupancy or vacancy sensor providing automatic off functionality. Lighting inside drawers and cabinets with opaque fronts or doors must have controls that turn the light off when the drawer or door is closed.
§ 150.0(i)(2F):	Dimmers. Lighting in habitable spaces (e.g., living rooms, dining rooms, kitchens, and bedrooms) must have readily accessible wall-mounted dimming controls that allow the lighting to be manually adjusted up and down. Forward phase out dimmers controlling LED light sources in these spaces must comply with NEMA SSL-7A.
§ 150.0(i)(2G):	Independent controls. Integrated lighting of exhaust fans must be controlled independently from the fans. Lighting under cabinets or shelves, lighting in display cabinets, and switched outlets must be controlled separately from ceiling-installed lighting.
§ 150.0(i)(3A):	Residential Outdoor Lighting. For single-family residential buildings, outdoor lighting permanently mounted to a residential building, or to other buildings on the same lot, must have a manual on/off switch and either a photo cell and motion sensor or automatic time switch control or an astronomical time clock. An energy management control system that provides the specified control functionality and meets all applicable requirements may be used to meet these requirements.
§ 150.0(i)(4):	Internally illuminated address signs. Internally illuminated address signs must either comply with § 140.8 or consume no more than 5 watts of power.
§ 150.0(i)(5):	Residential Garages for Eight or More Vehicles. Lighting for residential parking garages for eight or more vehicles must comply with the applicable requirements for nonresidential garages in §§ 110.9, 130.0, 130.1, 130.4, 140.6, and 141.0.
Solar Readiness:	
§ 110.10(a)(1):	Single-Family Residences. Single-family residences located in subdivisions with 10 or more single-family residences and where the application for a tentative subdivision map by the residence has been deemed complete and approved by the enforcement agency, which do not have a photovoltaic system installed, must comply with the requirements of § 110.10(a)(4).
§ 110.10(a)(2):	Minimum Solar Zone Area. The solar zone must have a minimum total area as described below. The solar zone must comply with access, pathway, window ventilation, and spacing requirements as specified in Table 24, Part 3 or other parts of Title 24 or in any requirements adopted by a local jurisdiction. The solar zone total area must be comprised of areas that have no dimension less than 5 feet and are no less than 80 square feet each for buildings with roof areas less than or equal to 10,000 square feet or no less than 160 square feet each for buildings with roof areas greater than 10,000 square feet. For single-family residences, the solar zone must be located on the roof or overhang of the building and have a total area no less than 250 square feet.*
§ 110.10(a)(1A):	Access. All sections of the solar zone located on steep-sloped roofs must have an azimuth between 90-302° of true north.
§ 110.10(a)(2):	Shading. The solar zone must not contain any obstructions, including but not limited to: vents, chimneys, architectural features, and roof-mounted equipment.
§ 110.10(a)(3A):	Shading. Any obstruction located on the roof or any other part of the building that projects above a solar zone must be located at least twice the horizontal distance of the height difference between the highest point of the obstruction and the horizontal projection of the nearest point of the solar zone, measured in the vertical plane.
§ 110.10(a)(4):	Structural Design Loads on Construction Documents. For areas of the roof designated as a solar zone, the structural design loads for roof dead load and roof live load must be clearly indicated on the construction documents.
§ 110.10(a)(5):	Interconnection Pathways. The construction documents must indicate a location reserved for inverters and metering equipment and a pathway reserved for routing of conduit from the solar zone to the point of interconnection with the electrical service; and for single-family residences and central water-heating systems, a pathway reserved for routing plumbing from the solar zone to the water-heating system.
§ 110.10(a)(6):	Documentation. A copy of the construction documents or a comparable document reflecting the information from § 110.10(a)(5) must be provided to the occupant.
§ 110.10(a)(7):	Main Electrical Service Panel. The main electrical service panel must have a minimum busbar rating of 200 amps.
§ 110.10(a)(8):	Main Electrical Service Panel. The main electrical service panel must have a reserved space to allow for the installation of a double pole circuit breaker for a future solar electric installation. The reserved space must be permanently marked as "For Future Solar Electric."

5/6/22

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan A

Calculation Date/Time: 2023-01-14T16:40:10-08:00

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BA-1-03.rbd22x

(Page 13 of 13)

DOCUMENTATION AUTHOR'S DECLARATION STATEMENT

1. I certify that this Certificate of Compliance documentation is accurate and complete.

Documentation Author Name: Wayne Seward

Signature Date: 2023-01-17 12:03:28

Address: 3431 Don Arturo Drive

City/State/Zip: Carlsbad, CA 92010

Phone: 760-635-2327

Signature: Wayne Seward

CABEC CERTIFIED ENERGY ANALYST

RESPONSIBLE PERSON'S DECLARATION STATEMENT

I certify the following under penalty of perjury, under the laws of the State of California:

1. I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design identified on this Certificate of Compliance.

2. I certify that the energy features and performance specifications identified on this Certificate of Compliance conform to the requirements of Title 24, Part 1 and Part 6 of the California Code of Regulations.

3. The building design features or system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations, plans and specifications submitted to the enforcement agency for approval with this building permit application.

Responsible Designer Name: Bart M Smith

Signature Date: 2023-01-17 12:07:36

Address: 682 2nd Street

City/State/Zip: Encinitas, CA 92024

Phone: 760-753-2464

Signature: Bart M Smith

CABEC CERTIFIED ENERGY ANALYST

Registration Number: 223-P01006670A-000-000-0000000-0000

Registration Date/Time: 2023-01-17 12:07:36

CA Building Energy Efficiency Standards - 2022 Residential Compliance

Report Version: 2022.0.000

Schema Version: rev 2020901

HERS Provider: CalCERTS inc.

Report Generated: 2023-01-14 16:41:01

Digitally signed by CalCERTS. This digital signature is provided in order to secure the content of this registered document, and in no way implies Registration Provider responsibility for the accuracy of the information.

Easy to Verify at CalCERTS.com

*Exceptions may apply.

5/6/22

General Notes

CABEC CERTIFIED ENERGY ANALYST

R19-04-30011

NR19-04-30020

TITLE 24, PART 6 ENERGY COMPLIANCE DOCUMENTATION

No. Revision/Issue Date

Firm Name and Address

BEAR TECHNOLOGIES CONSULTING, INC.
3431 DON ARTURO DRIVE,
CARLSBAD, CALIFORNIA 92010
(760) 635-2327
wayne@bear-techconsulting.com
http://www.bear-techconsulting.com

Project Name and Address

ENCINITAS PRADU - 1 BEDROOM PLAN A
ENCINITAS PRADU STREET
ENCINITAS, CALIFORNIA 92024

Project
23Q1019-1BA-1-03

Date
01/17/2023

Scale

Sheet
T-04

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan B

Calculation Date/Time: 2023-01-14T17:00:35-08:00

(Page 1 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BB.1-04.rbd22x

GENERAL INFORMATION					
01	Project Name	Encinitas PRADU - 1-Bedroom Plan B			
02	Run Title	Title 24 Analysis			
03	Project Location	Encinitas PRADU Street			
04	City	Encinitas	05	Standards Version	2022
06	Zip code	92024	07	Software Version	EnergyPro 9.0
08	Climate Zone	7	09	Front Orientation (deg/ Cardinal)	All orientations
10	Building Type	Single family	11	Number of Dwelling Units	1
12	Project Scope	Newly Constructed	13	Number of Bedrooms	1
14	Addition Cond. Floor Area (ft ²)	0	15	Number of Stories	1
16	Existing Cond. Floor Area (ft ²)	n/a	17	Fenestration Average U-factor	0.58
18	Total Cond. Floor Area (ft ²)	499	19	Glazing Percentage (%)	47.40%
20	ADU Bedroom Count	n/a			

COMPLIANCE RESULTS	
01	Building Complies with Computer Performance
02	This building incorporates features that require field testing and/or verification by a certified HERS rater under the supervision of a CEC-approved HERS provider.
03	This building incorporates one or more Special Features shown below

Registration Number: 223-P010006673A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:01:27

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan B

Calculation Date/Time: 2023-01-14T17:00:35-08:00

(Page 3 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BB.1-04.rbd22x

ENERGY USE SUMMARY						
Energy Use	Standard Design Source Energy (EDR1) (kBtu/ft ² -yr)	Standard Design TDV Energy (EDR2) (kTDV/ft ² -yr)	Proposed Design Source Energy (EDR1) (kBtu/ft ² -yr)	Proposed Design TDV Energy (EDR2) (kTDV/ft ² -yr)	Compliance Margin (EDR1)	Compliance Margin (EDR2)
Space Heating	0.13	0.62	0.67	4.71	-0.54	-4.09
Space Cooling	0.86	18.34	0.64	16.91	0.22	1.43
IAQ Ventilation	0.46	4.94	0.46	4.94	0	0
Water Heating	3.16	36.92	2.2	27.06	0.96	9.86
Self Utilization/Flexibility Credit				0		0
North Facing Efficiency Compliance Total	4.61	60.82	3.97	53.62	0.64	7.2
Space Heating	0.13	0.62	0.82	5.73	-0.69	-5.11
Space Cooling	0.86	18.34	0.69	17.73	0.17	0.61
IAQ Ventilation	0.46	4.94	0.46	4.94	0	0
Water Heating	3.16	36.92	2.22	27.05	0.94	9.87
Self Utilization/Flexibility Credit				0		0
East Facing Efficiency Compliance Total	4.61	60.82	4.19	55.45	0.42	5.37

Registration Number: 223-P010006673A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:01:27

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan B

Calculation Date/Time: 2023-01-14T17:00:35-08:00

(Page 2 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BB.1-04.rbd22x

ENERGY DESIGN RATINGS						
	Energy Design Ratings			Compliance Margins		
	Source Energy (EDR1)	Efficiency ¹ EDR (EDR2efficiency)	Total ² EDR (EDR2total)	Source Energy (EDR1)	Efficiency ¹ EDR (EDR2efficiency)	Total ² EDR (EDR2total)
Standard Design	31.4	45	31.9			
Proposed Design						
North Facing	29.9	39.6	29.4	1.5	5.4	2.5
East Facing	30.4	41	30	1	4	1.9
South Facing	29.9	39.1	29.2	1.5	5.9	2.7
West Facing	30	40.6	29.8	1.4	4.4	2.1
RESULT ³ : PASS						
¹ Efficiency EDR includes improvements like a better building envelope and more efficient equipment						
² Total EDR includes efficiency and demand response measures such as photovoltaic (PV) system and batteries						
³ Building complies when source energy, efficiency and total compliance margins are greater than or equal to zero and unmet load hour limits are not exceeded						
Standard Design PV Capacity: 1.56 kWdc						
Proposed PV Capacity Scaling: North (1.56 kWdc) East (1.56 kWdc) South (1.56 kWdc) West (1.56 kWdc)						

Registration Number: 223-P010006673A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:01:27

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan B

Calculation Date/Time: 2023-01-14T17:00:35-08:00

(Page 4 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BB.1-04.rbd22x

ENERGY USE SUMMARY						
Energy Use	Standard Design Source Energy (EDR1) (kBtu/ft ² -yr)	Standard Design TDV Energy (EDR2) (kTDV/ft ² -yr)	Proposed Design Source Energy (EDR1) (kBtu/ft ² -yr)	Proposed Design TDV Energy (EDR2) (kTDV/ft ² -yr)	Compliance Margin (EDR1)	Compliance Margin (EDR2)
Space Heating	0.13	0.62	0.73	5.09	-0.6	-4.47
Space Cooling	0.86	18.34	0.57	15.86	0.29	2.48
IAQ Ventilation	0.46	4.94	0.46	4.94	0	0
Water Heating	3.16	36.92	2.21	27.04	0.95	9.88
Self Utilization/Flexibility Credit				0		0
South Facing Efficiency Compliance Total	4.61	60.82	3.97	52.93	0.64	7.89
Space Heating	0.13	0.62	0.67	4.66	-0.54	-4.04
Space Cooling	0.86	18.34	0.68	18.42	0.18	-0.08
IAQ Ventilation	0.46	4.94	0.46	4.94	0	0
Water Heating	3.16	36.92	2.2	26.95	0.96	9.97
Self Utilization/Flexibility Credit				0		0
West Facing Efficiency Compliance Total	4.61	60.82	4.01	54.97	0.6	5.85

Registration Number: 223-P010006673A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:01:27

General Notes



R19-04-30011
NR19-04-30020

TITLE 24, PART 6 ENERGY COMPLIANCE DOCUMENTATION

No.	Revision/Issue	Date

Firm Name and Address
BEAR TECHNOLOGIES CONSULTING, INC.
3431 DON ARTURO DRIVE,
CARLSBAD, CALIFORNIA 92010
(760) 635-2327
wayne@beartechconsulting.com
http://www.beartechconsulting.com

Project Name and Address
ENCINITAS PRADU - 1 BEDROOM PLAN B
ENCINITAS PRADU STREET
ENCINITAS, CALIFORNIA 92024

Project 23Q1019-1BB1-04	Sheet T-01
Date 01/19/2023	
Scale	

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan B

Calculation Date/Time: 2023-01-14T17:00:35-08:00

(Page 5 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BB.1-04.rbd22x

ENERGY USE INTENSITY				
	Standard Design (kBtu/ft ² - yr)	Proposed Design (kBtu/ft ² - yr)	Compliance Margin (kBtu/ft ² - yr)	Margin Percentage
North Facing				
Gross EUI ¹	23.74	23.52	0.22	0.93
Net EUI ²	6.98	6.76	0.22	3.15
East Facing				
Gross EUI ¹	23.74	23.72	0.02	0.08
Net EUI ²	6.98	6.96	0.02	0.29
South Facing				
Gross EUI ¹	23.74	23.43	0.31	1.31
Net EUI ²	6.98	6.66	0.32	4.58
West Facing				
Gross EUI ¹	23.74	23.72	0.02	0.08
Net EUI ²	6.98	6.96	0.02	0.29
Notes				
1. Gross EUI is Energy Use Total (not including PV) / Total Building Area.				
2. Net EUI is Energy Use Total (including PV) / Total Building Area.				

Registration Number: 223-P010006673A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:01:27

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan B

Calculation Date/Time: 2023-01-14T17:00:35-08:00

(Page 7 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BB.1-04.rbd22x

BUILDING - FEATURES INFORMATION							
01	02	03	04	05	06	07	
Project Name	Conditioned Floor Area (ft ²)	Number of Dwelling Units	Number of Bedrooms	Number of Zones	Number of Ventilation Cooling Systems	Number of Water Heating Systems	
Encinitas PRADU - 1-Bedroom Plan B	499	1	1	1	1	1	

ZONE INFORMATION						
01	02	03	04	05	06	07
Zone Name	Zone Type	HVAC System Name	Zone Floor Area (ft ²)	Avg. Ceiling Height	Water Heating System 1	Status
ADU 1-Bedroom B	Conditioned	Ductless Mini-Split1	499	8	DHW Sys 1	New

OPAQUE SURFACES							
01	02	03	04	05	06	07	08
Name	Zone	Construction	Azimuth	Orientation	Gross Area (ft ²)	Window and Door Area (ft2)	Tilt (deg)
Front Wall	ADU 1-Bedroom B	_WALL: 2x4 Exterior	0	Front	192	42	90
Front Wall 2	ADU 1-Bedroom B	_WALL: 2x8 Exterior	0	Front	129	12.5	90
Left Wall	ADU 1-Bedroom B	_WALL: 2x4 Exterior	90	Left	138	48	90
Rear Wall	ADU 1-Bedroom B	_WALL: 2x4 Exterior	180	Back	192	54	90
Rear Wall 2	ADU 1-Bedroom B	_WALL: 2x8 Exterior	180	Back	129	16	90
Right Wall	ADU 1-Bedroom B	_WALL: 2x4 Exterior	270	Right	138	64	90
Roof 2	ADU 1-Bedroom B	_ROOF: CLG.	n/a	n/a	220	n/a	n/a

OPAQUE SURFACES - CATHEDRAL CEILINGS										
01	02	03	04	05	05	07	08	09	10	11
Name	Zone	Construction	Azimuth	Orientation	Area (ft ²)	Skylight Area (ft ²)	Roof Rise (x in 12)	Roof Reflectance	Roof Emittance	Cool Roof
Roof	ADU 1-Bedroom B	_ROOF: SLPD. CLG.	0	Front	279	0	5	0.1	0.85	No

Registration Number: 223-P010006673A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:01:27

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan B

Calculation Date/Time: 2023-01-14T17:00:35-08:00

(Page 6 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BB.1-04.rbd22x

REQUIRED PV SYSTEMS											
01	02	03	04	05	06	07	08	09	10	11	12
DC System Size (kWdc)	Exception	Module Type	Array Type	Power Electronics	CFI	Azimuth (deg)	Tilt Input	Array Angle (deg)	Tilt: (x in 12)	Inverter Eff. (%)	Annual Solar Access (%)
1.56	NA	Standard (14-17%)	Fixed	none	true	150-270	n/a	n/a	<=7:12	96	98
REQUIRED SPECIAL FEATURES											
The following are features that must be installed as condition for meeting the modeled energy performance for this computer analysis.											
<ul style="list-style-type: none"> Whole house fan Exposed slab floor in conditioned zone Variable capacity heat pump compliance option (verification details from VCHP Staff report, Appendix B, and RA3) Northwest Energy Efficiency Alliance (NEEA) rated heat pump water heater; specific brand/model, or equivalent, must be installed 											
HERS FEATURE SUMMARY											
The following is a summary of the features that must be field-verified by a certified HERS Rater as a condition for meeting the modeled energy performance for this computer analysis. Additional detail is provided in the building tables below. Registered CF2Rs and CF3Rs are required to be completed in the HERS Registry.											
<ul style="list-style-type: none"> Indoor air quality ventilation Kitchen range hood Whole house fan airflow and fan efficacy Verified EER/EER2 Verified SEER/SEER2 Verified Refrigerant Charge Airflow in habitable rooms (SC3.1.4.1.7) Verified HSPF2 Verified heat pump rated heating capacity Wall-mounted thermostat in zones greater than 150 ft2 (SC3.4.5) Ductless indoor units located entirely in conditioned space (SC3.1.4.1.8) 											

Registration Number: 223-P010006673A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:01:27

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan B

Calculation Date/Time: 2023-01-14T17:00:35-08:00

(Page 8 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BB.1-04.rbd22x

ATTIC							
01	02	03	04	05	06	07	08
Name	Construction	Type	Roof Rise (x in 12)	Roof Reflectance	Roof Emittance	Radiant Barrier	Cool Roof
Attic ADU 1-Bedroom B	Attic RoofADU 1-Bedroom B	Ventilated	5	0.1	0.85	Yes	No

FENESTRATION / GLAZING													
01	02	03	04	05	06	07	08	09	10	11	12	13	14
Name	Type	Surface	Orientation	Azimuth	Width (ft)	Height (ft)	Mult.	Area (ft²)	U-factor	U-factor Source	SHGC	SHGC Source	Exterior Shading
w1	Window	Front Wall	Front	0			1	18	0.58	NFRC	0.65	NFRC	Bug Screen
d1	Window	Front Wall	Front	0			1	24	0.58	NFRC	0.65	NFRC	Bug Screen
w5	Window	Front Wall 2	Front	0			1	12.5	0.58	NFRC	0.65	NFRC	Bug Screen
d3	Window	Left Wall	Left	90			1	48	0.58	NFRC	0.65	NFRC	Bug Screen
w4	Window	Rear Wall	Back	180			1	18	0.58	NFRC	0.65	NFRC	Bug Screen
w1 2	Window	Rear Wall	Back	180			1	18	0.58	NFRC	0.65	NFRC	Bug Screen
w1 3	Window	Rear Wall	Back	180			1	18	0.58	NFRC	0.65	NFRC	Bug Screen
w3	Window	Rear Wall 2	Back	180			1	8	0.58	NFRC	0.65	NFRC	Bug Screen
w2	Window	Rear Wall 2	Back	180			1	8	0.58	NFRC	0.65	NFRC	Bug Screen
d2	Window	Right Wall	Right	270			1	64	0.58	NFRC	0.65	NFRC	Bug Screen

Registration Number: 223-P010006673A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:01:27

General Notes



R19-04-30011
NR19-04-30020

TITLE 24, PART 6 ENERGY COMPLIANCE DOCUMENTATION

No.	Revision/Issue	Date

Firm Name and Address



BEAR TECHNOLOGIES CONSULTING, INC.
3431 DON ARTURO DRIVE,
CARLSBAD, CALIFORNIA 92010
(760) 635-2327
wayne@beartechconsulting.com
http://www.beartechconsulting.com

Project Name and Address

ENCINITAS PRADU - 1 BEDROOM PLAN B
ENCINITAS PRADU STREE
ENCINITAS, CALIFORNIA 92024

Project
23Q1019-1BB1-04

Date
01/19/2023

Scale

T-02

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan B

Calculation Date/Time: 2023-01-14T17:00:35-08:00

(Page 9 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BB.1-04.rbd22x

01	02	03	04	05	06	07	08
Name	Zone	Area (ft ²)	Perimeter (ft)	Edge Insul. R-value and Depth	Edge Insul. R-value and Depth	Carpeted Fraction	Heated
Slab On Grade	ADU 1-Bedroom B	499	99	none	0	0%	No

OPAQUE SURFACE CONSTRUCTIONS

01	02	03	04	05	06	07	08
Construction Name	Surface Type	Construction Type	Framing	Total Cavity R-value	Interior / Exterior Continuous R-value	U-factor	Assembly Layers
_WALL: 2x4 Exterior	Exterior Walls	Wood Framed Wall	2x4 @ 16 in. O. C.	R-15	None / None	0.095	Inside Finish: Gypsum Board Cavity / Frame: R-15 / 2x4 Exterior Finish: All Other Siding
_WALL: 2x8 Exterior	Exterior Walls	Wood Framed Wall	2x8 @ 16 in. O. C.	R-25	None / None	0.056	Inside Finish: Gypsum Board Cavity / Frame: R-25 / 2x8 Exterior Finish: All Other Siding
_ROOF: SLPD. CLG.	Cathedral Ceilings	Wood Framed Ceiling	2x10 @ 24 in. O. C.	R-30	None / None	0.035	Roofing: Light Roof (Asphalt Shingle) Roof Deck: Wood Siding/sheathing/decking Cavity / Frame: R-30 / 2x10 Inside Finish: Gypsum Board
Attic RoofADU 1-Bedroom B	Attic Roofs	Wood Framed Ceiling	2x4 @ 24 in. O. C.	R-0	None / 0	0.644	Roofing: Light Roof (Asphalt Shingle) Roof Deck: Wood Siding/sheathing/decking Cavity / Frame: no insul. / 2x4
_ROOF: CLG.	Ceilings (below attic)	Wood Framed Ceiling	2x4 @ 16 in. O. C.	R-30	None / None	0.032	Over Ceiling Joists: R-20.9 Insul. Cavity / Frame: R-9.1 / 2x4 Inside Finish: Gypsum Board

Registration Number: 223-P010006673A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:01:27

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan B

Calculation Date/Time: 2023-01-14T17:00:35-08:00

(Page 10 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BB.1-04.rbd22x

01	02	03	04	05
Quality Insulation Installation (QII)	High R-value Spray Foam Insulation	Building Envelope Air Leakage	CFM50	CFM50
Not Required	Not Required	N/A	n/a	n/a

WATER HEATING SYSTEMS

01	02	03	04	05	06	07	08	09
Name	System Type	Distribution Type	Water Heater Name	Number of Units	Solar Heating System	Compact Distribution	HERS Verification	Water Heater Name (#)
DHW Sys 1	Domestic Hot Water (DHW)	Standard	DHW Heater 1	1	n/a	None	n/a	DHW Heater 1 (1)

WATER HEATERS - NEEA HEAT PUMP

01	02	03	04	05	06	07	08
Name	# of Units	Tank Vol. (gal)	NEEA Heat Pump Brand	NEEA Heat Pump Model	Tank Location	Duct Inlet Air Source	Duct Outlet Air Source
DHW Heater 1	1	50	AOSmith	AOSmithFPTU50	ADU 1-Bedroom B	ADU 1-Bedroom B	ADU 1-Bedroom B

WATER HEATING - HERS VERIFICATION

01	02	03	04	05	06	07
Name	Pipe Insulation	Parallel Piping	Compact Distribution	Compact Distribution Type	Recirculation Control	Shower Drain Water Heat Recovery
DHW Sys 1 - 1/1	Not Required	Not Required	Not Required	None	Not Required	Not Required

Registration Number: 223-P010006673A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:01:27

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan B

Calculation Date/Time: 2023-01-14T17:00:35-08:00

(Page 11 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BB.1-04.rbd22x

01	02	03	04	05	06	07	08	09
Name	System Type	Heating Unit Name	Heating Equipment Count	Cooling Unit Name	Cooling Equipment Count	Fan Name	Distribution Name	Required Thermostat Type
Ductless Mini-Split1	Heat pump heating cooling	Heat Pump System 1	1	Heat Pump System 1	1	n/a	n/a	Setback

HVAC - HEAT PUMPS

01	02	03	04	05	06	07	08	09	10	11	12	13
Name	System Type	Number of Units	Efficiency Type	Heating HSPF2 / COP	Cap 47	Cap 17	Efficiency Type	SEER / SEER2	EER / EER / CEER	Zonally Controlled	Compressor Type	HERS Verification
Heat Pump System 1	VCHP-ductless	1	HSPF2	13.1	28000	16800	EER2SEER2	18.9	13	Zonally Controlled	Multi-speed	Heat Pump System 1-hers-htpump

HVAC HEAT PUMPS - HERS VERIFICATION

01	02	03	04	05	06	07	08	09
Name	Verified Airflow	Airflow Target	Verified EER/SEER2	Verified SEER/SEER2	Verified Refrigerant Charge	Verified HSPF/HSPF2	Verified Heating Cap 47	Verified Heating Cap 17
Heat Pump System 1-hers-htpump	Not Required	0	Not Required	Not Required	Yes	No	Yes	Yes

VARIABLE CAPACITY HEAT PUMP COMPLIANCE OPTION - HERS VERIFICATION

01	02	03	04	05	06	07	08	09	10
Name	Certified Low-Static VCHP System	Airflow to Habitable Rooms	Ductless Units in Conditioned Space	Wall Mount Thermostat	Air Filter Sizing & Pressure Drop Rating	Low Leakage Ducts in Conditioned Space	Minimum Airflow per RA3.3 and SC3.3.3.4.1	Certified non-continuous Fan	Indoor Fan not Running Continuously
Heat Pump System 1	Not required	Required	Required	Required	Not required	Not required	Not required	Not required	Not required

Registration Number: 223-P010006673A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:01:27

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan B

Calculation Date/Time: 2023-01-14T17:00:35-08:00

(Page 12 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BB.1-04.rbd22x

01	02	03	04	05	06	07	08	09
Dwelling Unit	Airflow (CFM)	Fan Efficacy (W/CFM)	IAQ Fan Type	Includes Heat/Energy Recovery?	IAQ Recovery Effectiveness - SRE	Includes Fault Indicator Display?	HERS Verification	Status
SFan IAQVentRpt	30	0.35	Exhaust	No	n/a	No	Yes	

COOLING VENTILATION

01	02	03	04	05	06	07	08	09
Name	Airflow Rate (CFM/ft2)	Cooling Vent CFM	Cooling Vent Watts/CFM	Total Watts	Number of Fans	CFVCS Type	Exhausts to	HERS Verification
WH Fan 1	0.04	20	0.05	1	1	Not a CFVCS	Outside	Required

PROJECT NOTES

This report is based on the drawings received on 01/03/2023.

SCOPE OF WORK: Construct a ADU - 1-Bedroom (B Elevation).

1) DO NOT USE FOR ACTUAL HEATING/COOLING DESIGN. 2) The Title 24 calculations used for this project are used for the purpose of complying with the current Title 24 code provisions and are intended to be used in order to obtain compliance per Title 24 regulations. They are NOT intended to be used as a substitute for the heating and cooling loads required for the structure(s) that are normally done by a mechanical engineer(s) or HVAC contractor(s) and in NO CIRCUMSTANCES is this to be used in lieu of the normal calculation methods used by a mechanical engineer(s) or HVAC contractor(s). 3) The assembly components found in this document are for modeling purposes only and may not reflect the actual conditions of the walls, roof(s), floor(s), windows and doors of the structure.

Registration Number: 223-P010006673A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:07:36
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:01:27

General Notes



R19-04-30011
NR19-04-30020

TITLE 24, PART 6 ENERGY COMPLIANCE DOCUMENTATION

No.	Revision/Issue	Date

Firm Name and Address



BEAR TECHNOLOGIES CONSULTING, INC.
3431 DON ARTURO DRIVE,
CARLSBAD, CALIFORNIA 92010
(760) 635-2327
wayne@beartechconsulting.com
http://www.beartechconsulting.com

Project Name and Address

ENCINITAS PRADU - 1 BEDROOM PLAN B
ENCINITAS PRADU STREE
ENCINITAS, CALIFORNIA 92024

Project 23Q1019-1BB.1-04	Sheet T-03
Date 01/19/2023	
Scale	

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan C

Calculation Description: Title 24 Analysis

Calculation Date/Time: 2023-01-14T17:20:13-08:00

Input File Name: 23Q1019-1BC.1-03.rbd22x

(Page 1 of 13)

GENERAL INFORMATION							
01	Project Name		Encinitas PRADU - 1-Bedroom Plan C				
02	Run Title		Title 24 Analysis				
03	Project Location		Encinitas PRADU Street				
04	City		Encinitas	05	Standards Version		2022
06	Zip code		92024	07	Software Version		EnergyPro 9.0
08	Climate Zone		7	09	Front Orientation (deg/ Cardinal)		All orientations
10	Building Type		Single family	11	Number of Dwelling Units		1
12	Project Scope		Newly Constructed	13	Number of Bedrooms		1
14	Addition Cond. Floor Area (ft²)		0	15	Number of Stories		1
16	Existing Cond. Floor Area (ft²)		n/a	17	Fenestration Average U-factor		0.58
18	Total Cond. Floor Area (ft²)		499	19	Glazing Percentage (%)		49.00%
20	ADU Bedroom Count		n/a				

COMPLIANCE RESULTS

01	Building Complies with Computer Performance
02	This building incorporates features that require field testing and/or verification by a certified HERS rater under the supervision of a CEC-approved HERS provider.
03	This building incorporates one or more Special Features shown below

Registration Number: 223-P010006674A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:08:33
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:21:06

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan C

Calculation Description: Title 24 Analysis

Calculation Date/Time: 2023-01-14T17:20:13-08:00

Input File Name: 23Q1019-1BC.1-03.rbd22x

(Page 3 of 13)

ENERGY USE SUMMARY						
Energy Use	Standard Design Source Energy (EDR1) (kBtu/ft ² -yr)	Standard Design TDV Energy (EDR2) (kTDV/ft ² -yr)	Proposed Design Source Energy (EDR1) (kBtu/ft ² -yr)	Proposed Design TDV Energy (EDR2) (kTDV/ft ² -yr)	Compliance Margin (EDR1)	Compliance Margin (EDR2)
Space Heating	0.1	0.46	0.71	4.96	-0.61	-4.5
Space Cooling	0.87	18.4	0.68	18.05	0.19	0.35
IAQ Ventilation	0.46	4.94	0.46	4.94	0	0
Water Heating	3.15	36.89	2.2	26.98	0.95	9.91
Self Utilization/Flexibility Credit				0		0
North Facing Efficiency Compliance Total	4.58	60.69	4.05	54.93	0.53	5.76
Space Heating	0.1	0.46	0.85	5.93	-0.75	-5.47
Space Cooling	0.87	18.4	0.71	18.54	0.16	-0.14
IAQ Ventilation	0.46	4.94	0.46	4.94	0	0
Water Heating	3.15	36.89	2.22	27.06	0.93	9.83
Self Utilization/Flexibility Credit				0		0
East Facing Efficiency Compliance Total	4.58	60.69	4.24	56.47	0.34	4.22

Registration Number: 223-P010006674A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:08:33
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:21:06

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan C

Calculation Description: Title 24 Analysis

Calculation Date/Time: 2023-01-14T17:20:13-08:00

Input File Name: 23Q1019-1BC.1-03.rbd22x

(Page 2 of 13)

ENERGY DESIGN RATINGS						
	Energy Design Ratings			Compliance Margins		
	Source Energy (EDR1)	Efficiency ¹ EDR (EDR2efficiency)	Total ² EDR (EDR2total)	Source Energy (EDR1)	Efficiency ¹ EDR (EDR2efficiency)	Total ² EDR (EDR2total)
Standard Design	31.5	45.2	31.9			
Proposed Design						
North Facing	30.2	40.9	29.9	1.3	4.3	2
East Facing	30.6	42.1	30.4	0.9	3.1	1.5
South Facing	30.2	40.3	29.6	1.3	4.9	2.3
West Facing	30.3	41.7	30.2	1.2	3.5	1.7
RESULT ³ : PASS						
¹ Efficiency EDR includes improvements like a better building envelope and more efficient equipment						
² Total EDR includes efficiency and demand response measures such as photovoltaic (PV) system and batteries						
³ Building complies when source energy, efficiency and total compliance margins are greater than or equal to zero and unmet load hour limits are not exceeded						
<ul style="list-style-type: none"> Standard Design PV Capacity: 1.56 kWdc Proposed PV Capacity Scaling: North (1.56 kWdc) East (1.56 kWdc) South (1.56 kWdc) West (1.56 kWdc) 						

Registration Number: 223-P010006674A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:08:33
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:21:06

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan C

Calculation Description: Title 24 Analysis

Calculation Date/Time: 2023-01-14T17:20:13-08:00

Input File Name: 23Q1019-1BC.1-03.rbd22x

(Page 4 of 13)

ENERGY USE SUMMARY						
Energy Use	Standard Design Source Energy (EDR1) (kBtu/ft ² -yr)	Standard Design TDV Energy (EDR2) (kTDV/ft ² -yr)	Proposed Design Source Energy (EDR1) (kBtu/ft ² -yr)	Proposed Design TDV Energy (EDR2) (kTDV/ft ² -yr)	Compliance Margin (EDR1)	Compliance Margin (EDR2)
Space Heating	0.1	0.46	0.77	5.39	-0.67	-4.93
Space Cooling	0.87	18.4	0.61	16.77	0.26	1.63
IAQ Ventilation	0.46	4.94	0.46	4.94	0	0
Water Heating	3.15	36.89	2.21	27.04	0.94	9.85
Self Utilization/Flexibility Credit				0		0
South Facing Efficiency Compliance Total	4.58	60.69	4.05	54.14	0.53	6.55
Space Heating	0.1	0.46	0.7	4.9	-0.6	-4.44
Space Cooling	0.87	18.4	0.71	19.21	0.16	-0.81
IAQ Ventilation	0.46	4.94	0.46	4.94	0	0
Water Heating	3.15	36.89	2.2	26.94	0.95	9.95
Self Utilization/Flexibility Credit				0		0
West Facing Efficiency Compliance Total	4.58	60.69	4.07	55.99	0.51	4.7

Registration Number: 223-P010006674A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:08:33
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:21:06

General Notes



R19-04-30011
NR19-04-30020

TITLE 24, PART 6 ENERGY COMPLIANCE DOCUMENTATION

No.	Revision/Issue	Date

Firm Name and Address



BEAR TECHNOLOGIES CONSULTING, INC.
3431 DON ARTURO DRIVE,
CARLSBAD, CALIFORNIA 92010
(760) 635-2327
wayne@beartechconsulting.com
http://www.beartechconsulting.com

Project Name and Address

ENCINITAS PRADU - 1 BEDROOM PLAN C
ENCINITAS PRADU STREET
ENCINITAS, CALIFORNIA 92024

Project
23Q1019-1BC.1-03

Date
01/19/2023

Scale

Sheet

T-01

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan C

Calculation Date/Time: 2023-01-14T17:20:13-08:00

(Page 5 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BC.1-03.rbd22x

ENERGY USE INTENSITY				
	Standard Design (kBtu/ft ² - yr)	Proposed Design (kBtu/ft ² - yr)	Compliance Margin (kBtu/ft ² - yr)	Margin Percentage
North Facing				
Gross EUI ¹	23.71	23.69	0.02	0.08
Net EUI ²	6.94	6.92	0.02	0.29
East Facing				
Gross EUI ¹	23.71	23.86	-0.15	-0.63
Net EUI ²	6.94	7.09	-0.15	-2.16
South Facing				
Gross EUI ¹	23.71	23.58	0.13	0.55
Net EUI ²	6.94	6.8	0.14	2.02
West Facing				
Gross EUI ¹	23.71	23.85	-0.14	-0.59
Net EUI ²	6.94	7.08	-0.14	-2.02
Notes				
1. Gross EUI is Energy Use Total (not including PV) / Total Building Area.				
2. Net EUI is Energy Use Total (including PV) / Total Building Area.				

Registration Number: 223-P01000674A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:08:33
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:21:06

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan C

Calculation Date/Time: 2023-01-14T17:20:13-08:00

(Page 7 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BC.1-03.rbd22x

BUILDING - FEATURES INFORMATION										
01	02	03	04	05	06	07				
Project Name	Conditioned Floor Area (ft²)	Number of Dwelling Units	Number of Bedrooms	Number of Zones	Number of Ventilation Cooling Systems	Number of Water Heating Systems				
Encinitas PRADU - 1-Bedroom Plan C	499	1	1	1	1	1				
ZONE INFORMATION										
01	02	03	04	05	06	07				
Zone Name	Zone Type	HVAC System Name	Zone Floor Area (ft²)	Avg. Ceiling Height	Water Heating System 1	Status				
ADU 1-Bedroom C	Conditioned	Ductless Mini-Split1	499	8	DHW Sys 1	New				
OPAQUE SURFACES										
01	02	03	04	05	06	07	08			
Name	Zone	Construction	Azimuth	Orientation	Gross Area (ft²)	Window and Door Area (ft2)	Tilt (deg)			
Front Wall	ADU 1-Bedroom C	_WALL: 2x4 Exterior	0	Front	294	54.5	90			
Left Wall	ADU 1-Bedroom C	_WALL: 2x4 Exterior	90	Left	126	52	90			
Rear Wall	ADU 1-Bedroom C	_WALL: 2x4 Exterior	180	Back	321	70	90			
Right Wall	ADU 1-Bedroom C	_WALL: 2x4 Exterior	270	Right	126	68	90			
Roof 2	ADU 1-Bedroom C	_ROOF: CLG.	n/a	n/a	200	n/a	n/a			
OPAQUE SURFACES - CATHEDRAL CEILINGS										
01	02	03	04	05	06	07	08	09	10	11
Name	Zone	Construction	Azimuth	Orientation	Area (ft²)	Skylight Area (ft²)	Roof Rise (x in 12)	Roof Reflectance	Roof Emittance	Cool Roof
Roof	ADU 1-Bedroom C	_ROOF: SLPD, CLG.	0	Front	299	0	5	0.1	0.85	No

Registration Number: 223-P01000674A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:08:33
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:21:06

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan C

Calculation Date/Time: 2023-01-14T17:20:13-08:00

(Page 6 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BC.1-03.rbd22x

REQUIRED PV SYSTEMS											
01	02	03	04	05	06	07	08	09	10	11	12
DC System Size (kWdc)	Exception	Module Type	Array Type	Power Electronics	CFI	Azimuth (deg)	Tilt Input	Array Angle (deg)	Tilt: (x in 12)	Inverter Eff. (%)	Annual Solar Access (%)
1.56	NA	Standard (14-17%)	Fixed	none	true	150-270	n/a	n/a	<=7:12	96	98
REQUIRED SPECIAL FEATURES											
The following are features that must be installed as condition for meeting the modeled energy performance for this computer analysis.											
<ul style="list-style-type: none">Whole house fanExposed slab floor in conditioned zoneVariable capacity heat pump compliance option (verification details from VCHP Staff report, Appendix B, and RA3)Northwest Energy Efficiency Alliance (NEEA) rated heat pump water heater; specific brand/model, or equivalent, must be installed											
HERS FEATURE SUMMARY											
The following is a summary of the features that must be field-verified by a certified HERS Rater as a condition for meeting the modeled energy performance for this computer analysis. Additional detail is provided in the building tables below. Registered CF2Rs and CF3Rs are required to be completed in the HERS Registry											
<ul style="list-style-type: none">Indoor air quality ventilationKitchen range hoodWhole house fan airflow and fan efficacyVerified EER/EER2Verified SEER/SEER2Verified Refrigerant ChargeAirflow in habitable rooms (SC3.1.4.1.7)Verified HSPF2Verified heat pump rated heating capacityWall-mounted thermostat in zones greater than 150 ft2 (SC3.4.5)Ductless indoor units located entirely in conditioned space (SC3.1.4.1.8)											

Registration Number: 223-P01000674A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:08:33
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:21:06

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan C

Calculation Date/Time: 2023-01-14T17:20:13-08:00

(Page 8 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BC.1-03.rbd22x

ATTIC							
01	02	03	04	05	06	07	08
Name	Construction	Type	Roof Rise (x in 12)	Roof Reflectance	Roof Emittance	Radiant Barrier	Cool Roof
Attic ADU 1-Bedroom C	Attic RoofADU 1-Bedroom C	Ventilated	5	0.1	0.85	Yes	No

FENESTRATION / GLAZING													
01	02	03	04	05	06	07	08	09	10	11	12	13	14
Name	Type	Surface	Orientation	Azimuth	Width (ft)	Height (ft)	Mult.	Area (ft²)	U-factor	U-factor Source	SHGC	SHGC Source	Exterior Shading
w1	Window	Front Wall	Front	0			1	18	0.58	NFRC	0.65	NFRC	Bug Screen
d1	Window	Front Wall	Front	0			1	24	0.58	NFRC	0.65	NFRC	Bug Screen
w5	Window	Front Wall	Front	0			1	12.5	0.58	NFRC	0.65	NFRC	Bug Screen
d3	Window	Left Wall	Left	90			1	48	0.58	NFRC	0.65	NFRC	Bug Screen
w6	Window	Left Wall	Left	90			1	4	0.58	NFRC	0.65	NFRC	Bug Screen
w4	Window	Rear Wall	Back	180			1	18	0.58	NFRC	0.65	NFRC	Bug Screen
w3	Window	Rear Wall	Back	180			1	8	0.58	NFRC	0.65	NFRC	Bug Screen
w2	Window	Rear Wall	Back	180			1	8	0.58	NFRC	0.65	NFRC	Bug Screen
w1 2	Window	Rear Wall	Back	180			1	18	0.58	NFRC	0.65	NFRC	Bug Screen
w1 3	Window	Rear Wall	Back	180			1	18	0.58	NFRC	0.65	NFRC	Bug Screen
d2	Window	Right Wall	Right	270			1	64	0.58	NFRC	0.65	NFRC	Bug Screen
w6 2	Window	Right Wall	Right	270			1	4	0.58	NFRC	0.65	NFRC	Bug Screen

Registration Number: 223-P01000674A-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:08:33
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:21:06

General Notes



R19-04-30011
NR19-04-30020

TITLE 24, PART 6 ENERGY COMPLIANCE DOCUMENTATION

No.	Revision/Issue	Date

Firm Name and Address



BEAR TECHNOLOGIES CONSULTING, INC.
3431 DON ARTURO DRIVE,
CARLSBAD, CALIFORNIA 92010
(760) 635-2327
wayne@beartechconsulting.com
http://www.beartechconsulting.com

Project Name and Address

ENCINITAS PRADU - 1 BEDROOM PLAN C
ENCINITAS PRADU STREE
ENCINITAS, CALIFORNIA 92024

Project
23Q1019-1BC.1-03

Sheet

Date
01/19/2023

T-02

Scale

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan C

Calculation Date/Time: 2023-01-14T17:20:13-08:00

(Page 9 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BC.1-03.rbd22x

01	02	03	04	05	06	07	08
Name	Zone	Area (ft²)	Perimeter (ft)	Edge Insul. R-value and Depth	Edge Insul. R-value and Depth	Carpeted Fraction	Heated
Slab On Grade	ADU 1-Bedroom C	499	96	none	0	0%	No

OPAQUE SURFACE CONSTRUCTIONS

01	02	03	04	05	06	07	08
Construction Name	Surface Type	Construction Type	Framing	Total Cavity R-value	Interior / Exterior Continuous R-value	U-factor	Assembly Layers
_WALL: 2x4 Exterior	Exterior Walls	Wood Framed Wall	2x4 @ 16 in. O. C.	R-15	None / None	0.095	Inside Finish: Gypsum Board Cavity / Frame: R-15 / 2x4 Exterior Finish: All Other Siding
_ROOF: SLPD. CLG.	Cathedral Ceilings	Wood Framed Ceiling	2x10 @ 24 in. O. C.	R-30	None / None	0.035	Roofing: Light Roof (Asphalt Shingle) Roof Deck: Wood Siding/sheathing/decking Cavity / Frame: R-30 / 2x10 Inside Finish: Gypsum Board
Attic RoofADU 1-Bedroom C	Attic Roofs	Wood Framed Ceiling	2x4 @ 24 in. O. C.	R-0	None / 0	0.644	Roofing: Light Roof (Asphalt Shingle) Roof Deck: Wood Siding/sheathing/decking Cavity / Frame: no Insul. / 2x4
_ROOF: CLG.	Ceilings (below attic)	Wood Framed Ceiling	2x4 @ 16 in. O. C.	R-30	None / None	0.032	Over Ceiling Joists: R-20.9 Insul. Cavity / Frame: R-9.1 / 2x4 Inside Finish: Gypsum Board

BUILDING ENVELOPE - HERS VERIFICATION

01	02	03	04	05
Quality Insulation Installation (QII)	High R-value Spray Foam Insulation	Building Envelope Air Leakage	CFM50	CFM50
Not Required	Not Required	N/A	n/a	n/a

Registration Number: 223-P010006674A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:08:33
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:21:06

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan C

Calculation Date/Time: 2023-01-14T17:20:13-08:00

(Page 11 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BC.1-03.rbd22x

HVAC - HEAT PUMPS

01	02	03	04	05	06	07	08	09	10	11	12	13
Name	System Type	Number of Units	Efficiency Type	HSPF / HSPF2 / COP	Cap 47	Cap 17	Efficiency Type	SEER / SEER2	EER / EER / CEER	Zonally Controlled	Compressor Type	HERS Verification
Heat Pump System 1	VCHP-ductless	1	HSPF2	13.1	28000	16800	EER2SEER2	18.9	13	Zonally Controlled	Multi-speed	Heat Pump System 1-hers-htpump

HVAC HEAT PUMPS - HERS VERIFICATION

01	02	03	04	05	06	07	08	09
Name	Verified Airflow	Airflow Target	Verified EER/EER2	Verified SEER/SEER2	Verified Refrigerant Charge	Verified HSPF/HSPF2	Verified Heating Cap 47	Verified Heating Cap 17
Heat Pump System 1-hers-htpump	Not Required	0	Not Required	Not Required	Yes	No	Yes	Yes

VARIABLE CAPACITY HEAT PUMP COMPLIANCE OPTION - HERS VERIFICATION

01	02	03	04	05	06	07	08	09	10
Name	Certified Low-Static VCHP System	Airflow to Habitable Rooms	Ductless Units in Conditioned Space	Wall Mount Thermostat	Air Filter Sizing & Pressure Drop Rating	Low Leakage Ducts in Conditioned Space	Minimum Airflow per RA3.3 and SC3.3.3.4.1	Certified non-continuous Fan	Indoor Fan not Running Continuously
Heat Pump System 1	Not required	Required	Required	Required	Not required	Not required	Not required	Not required	Not required

INDOOR AIR QUALITY (IAQ) FANS

01	02	03	04	05	06	07	08	09
Dwelling Unit	Airflow (CFM)	Fan Efficacy (W/CFM)	IAQ Fan Type	Includes Heat/Energy Recovery?	IAQ Recovery Effectiveness - SRE	Includes Fault Indicator Display?	HERS Verification	Status
Sfam IAQVentRpt	30	0.35	Exhaust	No	n/a	No	Yes	

Registration Number: 223-P010006674A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:08:33
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:21:06

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan C

Calculation Date/Time: 2023-01-14T17:20:13-08:00

(Page 10 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BC.1-03.rbd22x

01	02	03	04	05	06	07	08	09
Name	System Type	Distribution Type	Water Heater Name	Number of Units	Solar Heating System	Compact Distribution	HERS Verification	Water Heater Name (H)
DHW Sys 1	Domestic Hot Water (DHW)	Standard	DHW Heater 1	1	n/a	None	n/a	DHW Heater 1 (1)

WATER HEATERS - NEEA HEAT PUMP

01	02	03	04	05	06	07	08
Name	# of Units	Tank Vol. (gal)	NEEA Heat Pump Brand	NEEA Heat Pump Model	Tank Location	Duct Inlet Air Source	Duct Outlet Air Source
DHW Heater 1	1	50	AOSmith	AOSmithFPTU50	ADU 1-Bedroom C	ADU 1-Bedroom C	ADU 1-Bedroom C

WATER HEATING - HERS VERIFICATION

01	02	03	04	05	06	07
Name	Pipe Insulation	Parallel Piping	Compact Distribution	Compact Distribution Type	Recirculation Control	Shower Drain Water Heat Recovery
DHW Sys 1 - 1/1	Not Required	Not Required	Not Required	None	Not Required	Not Required

SPACE CONDITIONING SYSTEMS

01	02	03	04	05	06	07	08	09
Name	System Type	Heating Unit Name	Heating Equipment Count	Cooling Unit Name	Cooling Equipment Count	Fan Name	Distribution Name	Required Thermostat Type
Ductless Mini-Split1	Heat pump heating cooling	Heat Pump System 1	1	Heat Pump System 1	1	n/a	n/a	Setback

Registration Number: 223-P010006674A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:08:33
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:21:06

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan C

Calculation Date/Time: 2023-01-14T17:20:13-08:00

(Page 12 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BC.1-03.rbd22x

COOLING VENTILATION

01	02	03	04	05	06	07	08	09
Name	Airflow Rate (CFM/ft2)	Cooling Vent CFM	Cooling Vent Watts/CFM	Total Watts	Number of Fans	CFVCS Type	Exhausts to	HERS Verification
WH Fan 1	0.04	20	0.05	1	1	Not a CFVCS	Outside	Required

PROJECT NOTES

This report is based on the drawings received on 01/03/2023.

SCOPE OF WORK: Construct a ADU - 1-Bedroom (C Elevation).

1) DO NOT USE FOR ACTUAL HEATING/COOLING DESIGN. 2) The Title 24 calculations used for this project are used for the purpose of complying with the current Title 24 code provisions and are intended to be used in order to obtain compliance per Title 24 regulations. They are NOT intended to be used as a substitute for the heating and cooling loads required for the structure(s) that are normally done by a mechanical engineer(s) or HVAC contractor(s) and in NO CIRCUMSTANCES is this to be used in lieu of the normal calculation methods used by a mechanical engineer(s) or HVAC contractor(s). 3) The assembly components found in this document are for modeling purposes only and may not reflect the actual conditions of the walls, roof(s), floor(s), windows and doors of the structure.

Registration Number: 223-P010006674A-000-000-00000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance

Registration Date/Time: 2023-01-17 12:08:33
Report Version: 2022.0.000
Schema Version: rev 20220901

HERS Provider: CalCERTS Inc.
Report Generated: 2023-01-14 17:21:06

General Notes



R19-04-30011
NR19-04-30020

TITLE 24, PART 6 ENERGY COMPLIANCE DOCUMENTATION

No.	Revision/Issue	Date

Firm Name and Address



BEAR TECHNOLOGIES CONSULTING, INC.
3431 DON ARTURO DRIVE,
CARLSBAD, CALIFORNIA 92010
(760) 635-2327
wayne@beartechconsulting.com
http://www.beartechconsulting.com

Project Name and Address

ENCINITAS PRADU - 1 BEDROOM PLAN C
ENCINITAS PRADU STREE
ENCINITAS, CALIFORNIA 92024

Project	Sheet
23Q1019-1BC.1-03	T-03
Date 01/19/2023	
Scale	



2022 Single-Family Residential Mandatory Requirements Summary

Note: Single-family residential buildings subject to the Energy Codes must comply with all applicable mandatory measures, regardless of the compliance approach used. Review the respective section for more information.
(04/2022)

Building Envelope:	
§ 110.6(a):	Air Leakage. Manufactured fenestration, exterior doors, and exterior pet doors must limit air leakage to 0.3 CFM per square foot or less when tested per NFRC-400, ASTM E283, or AIAA/VOMACSA 1011.S (04/40/2011).
§ 110.6(a)(5):	Labeling. Fenestration products and exterior doors must have a label meeting the requirements of § 110.11(a).
§ 110.6(a)(6):	Field-fabricated exterior doors and fenestration products must use U-factors and solar heat gain coefficient (SHGC) values from Tables 110.6.A, 110.6.B, or 110.6.C for exterior doors. They must be caulked and/or weatherstripped.
§ 110.7:	Air Leakage. All joints, penetrations, and other openings in the building envelope that are potential sources of air leakage must be caulked, gasketed, or weatherstripped.
§ 110.8(a):	Insulation Certification by Manufacturers. Insulation must be certified by the Department of Consumer Affairs, Bureau of Household Goods and Services (BHGS).
§ 110.8(a)(1):	Insulation Requirements for Heated Slab Floors. Heated slab floors must be insulated per the requirements of § 110.8(g).
§ 110.8(a)(2):	Roofing Products Solar Reflectance and Thermal Emittance. The thermal emittance and aged solar reflectance values of the roofing material must meet the requirements of § 110.8(h) and be labeled per § 110.113 when the installation of a cool roof is specified on the CFPB.
§ 110.8(j):	Radiant Barrier. When required, radiant barriers must have an emittance of 0.05 or less and be certified to the Department of Consumer Affairs.
§ 110.8(k):	Roof Deck, Ceiling and Rafter Roof Insulation. Roof decks in newly constructed attics in climate zones 4 and 6-16 area-weighted average U-factor not exceeding U-0.184. Ceiling and rafter roofs minimum R-22 insulation in wood-frame ceiling; or area-weighted average U-factor not exceed 0.043. Rafter roof alterations minimum R-19 or area-weighted average U-factor of 0.054 or less. Attic access doors must have permanently attached insulation using adhesive or mechanical fasteners. The attic access must be gasketed to prevent air leakage. Insulation must be installed in direct contact with a roof or ceiling which is sealed to limit infiltration and exfiltration, as specified in § 110.7, including but not limited to placing insulation either above or below the roof deck or on top of a drywall ceiling.
§ 110.8(l):	Loose-fill Insulation. Loose-fill insulation must meet the manufacturer's required density for the labeled R-value.
§ 110.8(m):	Wall Insulation. Minimum R-13 insulation in 2x4 inch wood framing wall or have a U-factor of 0.102 or less, or R-20 in 2x6 inch wood framing or have a U-factor of 0.071 or less. Oppaque non-framed assemblies must have an overall assembly U-factor not exceeding 0.102. Masonry walls must meet Tables 110.8.A or B.
§ 110.8(n):	Raised-floor Insulation. Minimum R-10 insulation in raised wood framed floor or 0.027 maximum U-factor.
§ 110.8(o):	Slab Edge Insulation. Slab edge insulation must meet all of the following: have a water absorption rate, for the insulation material alone without facings, no greater than 0.3 percent; have a water vapor permeance no greater than 2.0 perm per inch; be protected from physical damage and UV light degradation; and when installed as part of a heated slab floor, meet the requirements of § 110.8(g).
§ 110.8(p):	Vapor Retarder. In climate zones 1 through 16, the earth floor or unvented crawl space must be covered with a Class I or Class II vapor retarder. This requirement also applies to controlled ventilation crawl space for buildings complying with the exception to § 110.8(p).
§ 110.8(q):	Vapor Retarder. In climate zones 14 and 16, a Class I or Class II vapor retarder must be installed on the conditioned space side of all insulation at exterior walls, vertical eaves, and unvented attics with mechanical ventilation.
§ 110.8(r):	Fenestration Products. Fenestration, including skylights, separating conditioned space from unconditioned space or outdoors must have a maximum U-factor of 0.45, or area-weighted average U-factor of fenestration must not exceed 0.45.
Fireplaces, Decorative Gas Appliances, and Gas Log:	
§ 110.9(a):	Pilot Light. Continuously burning pilot lights are not allowed for indoor and outdoor fireplaces.
§ 110.9(a)(1):	Closeted Doors. Masonry or factory-built fireplaces must have a double metal or glass door covering the entire opening of the firebox.
§ 110.9(a)(2):	Combustion Intake. Masonry or factory-built fireplaces must have a combustion outside air intake, which is at least six square inches in area and is equipped with a readily accessible, operable, and light-tight damper or combustion-air control device.
§ 110.9(a)(3):	Flue Damper. Masonry or factory-built fireplaces must have a flue damper with a readily accessible control.
Space Conditioning, Water Heating, and Plumbing Systems:	
§ 110.9(a) 110.3:	Certification. Heating, ventilation, and air conditioning (HVAC) equipment, water heaters, showerheads, faucets, and all other regulated appliances must be certified by the manufacturer to the California Energy Commission.
§ 110.9(a) 110.3:	HVAC Efficiency. Equipment must meet the applicable efficiency requirements in Table 110.2-A through Table 110.2-N.
§ 110.9(a):	Controls for Heat Pumps with Supplemental Electric Resistance Heaters. Heat pumps with supplementary electric resistance heaters must have controls that prevent supplementary heater operation when the heating load can be met by the heat pump alone; and in which the cut-on temperature for compression heating is higher than the cut-on temperature for supplementary heating, and the cut-off temperature for compression heating is higher than the cut-off temperature for supplementary heating.
§ 110.9(a):	Thermostats. All heating or cooling systems not controlled by a central energy management control system (EMCS) must have a setback thermostat.
§ 110.9(a):	Insulation. Insulation service water heater storage tanks and solar water-heating backup tanks must have adequate insulation, or tank surface heat loss rating.
§ 110.9(a):	Isolation Valves. Instantaneous water heaters with an input rating greater than 6.8 kBtu per hour (2 kW) must have isolation valves with hose valves or other fittings on both cold and hot water lines to allow for flushing the water heater when the valves are closed.

5/6/22



2022 Single-Family Residential Mandatory Requirements Summary

§ 110.5:	Pilot Lights. Continuously burning pilot lights are prohibited for natural gas, fan-type central furnaces, household cooking appliances (except appliances without an electrical supply voltage connection with pilot lights that consume less than 150 Btu per hour), and pool and spa heaters.
§ 150.0(h):	Building Cooling and Heating Loads. Heating and/or cooling loads are calculated in accordance with the ASHRAE Handbook, Equipment Volume, Applications Volume, and Fundamentals Volume; the SMACNA Residential Comfort System Installation Standards Manual; or the ACCA Manual of Air Conditioning Design conditions specified in § 150.0(h)(2).
§ 150.0(h)(3A):	Clearances. Air conditioner and heat pump outdoor condensing units must have a clearance of at least five feet from the outlet of any duct.
§ 150.0(h)(3B):	Liquid Line Drier. Air conditioners and heat pump systems must be equipped with liquid line filter driers if required, as specified by the manufacturer's instructions.
§ 150.0(i):	Water Piping, Solar Water-Heating System Piping, and Space Conditioning System Line Insulation. All domestic hot water piping must be insulated as specified in § 609.11 of the California Plumbing Code.
§ 150.0(j):	Insulation Protection. Piping insulation must be protected from damage, including that due to sunlight, moisture, equipment maintenance, and wind as required by § 120.3(b). Insulation exposed to weather must be water resistant and protected from UV light (e.g., adhesive tapes). Insulation covering chilled water piping and refrigerant suction piping located outside the conditioned space must include, or be protected by, a Class I or Class II vapor retarder. Pipe insulation buried below grade must be installed in a waterproof and non-oxidizable casing or sleeve.
§ 150.0(k):	Gas or Propane Water Heating Systems. Systems using gas or propane water heaters to serve individual dwelling units must designate a space at least 2.5' x 2.5' x 7' suitable for the future installation of a heat pump water heater, and meet electrical and plumbing requirements, based on the distance between this designated space and the water heater location, and a condensate drain no more than 2' higher than the base of the water heater.
§ 150.0(l):	Solar Water-Heating Systems. Solar water-heating systems and collectors must be certified and rated by the Solar Rating and Certification Corporation (SRCC), the International Association of Plumbing and Mechanical Officials, Research and Testing (IAPMO R&T), or by a listing agency that is approved by the executive director.
Ducts and Fans:	
§ 110.8(i):	Ducts. Insulation installed on an existing space-conditioning duct must comply with § 604.0 of the California Mechanical Code (CMC), if a contractor installs the insulation, the contractor must certify to the customer, in writing, that the insulation meets this requirement.
§ 110.8(j):	CMC Compliance. All air-distribution system ducts and plenums must meet CMC §§ 601.0-605.0 and ANSI/SMACNA-06-2008 HVAC Duct Construction Standards Metal and Flexible 3rd Edition. Portions of supply-air and return-air ducts and plenums must be insulated to R-6.0 or higher; ducts located entirely in conditioned space as confirmed through field verification and diagnostic testing (FAT 14.1.8) do not require insulation. Connections of metal ducts and inner core of flexible ducts must be mechanically fastened. Openings must be sealed with mastic, tape, or other duct-sealing system that meets the applicable requirements, or sealed sealed that meets UL 723. The combination of mastic and other meat or tape must be used to seal openings greater than 1/4". Mastic or tape is used. Building cavities, air handler support platforms, and plenums designed or constructed with materials other than sealed sheet metal, duct board or flexible duct must not be used to convey conditioned air. Building cavities and support platforms may contain ducts; ducts installed in these spaces must not be compressed.
§ 150.0(m):	Factory-Fabricated Duct Systems. Factory-fabricated duct systems must comply with applicable requirements for duct construction, connections, and closures; joints and seams of duct systems and their components must be sealed with chob back rubber adhesive tape unless such tape is used in combination with mastic and draw bands.
§ 150.0(n):	Field-Fabricated Duct Systems. Field-fabricated duct systems must comply with applicable requirements for pressure-sensitive tapes, mastic, sealants, and other recommendations specified for duct construction.
§ 150.0(o):	Backdraft Damper. Fan systems that exchange air between the conditioned space and outdoors must have backdraft or automatic dampers.
§ 150.0(p):	Grossly Ventilation Dampers. Grossly ventilating systems serving conditioned space must have either automatic or readily accessible, manually operated dampers in all openings to the outside, except combustion inlet and outlet air openings and elevator shaft vents.
§ 150.0(q):	Protection of Insulation. Insulation must be protected from damage due to sunlight, moisture, equipment maintenance, and wind. Insulation exposed to weather must be suitable for outdoor service (e.g., protected by aluminum, sheet metal, painted canvas, or plastic cover). Cellular foam insulation must be protected as above or painted with a water-resistant and solar radiation-resistant coating.
§ 150.0(r):	Porous Inner Core Flex Duct. Porous inner core of flex ducts must have a non-porous layer or air barrier between the inner core and outer vapor barrier.
§ 150.0(s):	Duct System Sealing and Leakage Test. When space conditioning systems use forced air duct systems to supply conditioned air to an occupiable space, the ducts must be sealed and duct leakage tested, as confirmed through field verification and diagnostic testing, in accordance with Reference Residential Appendix RA3.1.
§ 150.0(t):	Air Filtration. Space conditioning systems with ducts exceeding 10 feet and the supply side of ventilation systems must have MERV 13 or equivalent filters. Filters for space conditioning systems must have a two-inch depth or can be one inch if sized per Equation 150.0-A. Clean filter pressure drop and labeling must meet the requirements in § 150.0(t)(2). Filters must be accessible for regular service. Filter racks or grilles must use gaskets, sealing, or other means to close gaps around the inserted filters to prevent air from bypassing the filter.

5/6/22

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Encinitas PRADU - 1-Bedroom Plan C

Calculation Date/Time: 2023-01-14T17:20:13-08:00

(Page 13 of 13)

Calculation Description: Title 24 Analysis

Input File Name: 23Q1019-1BC-1-03.rbd22x

DOCUMENTATION AUTHOR'S DECLARATION STATEMENT

I, I certify that this Certificate of Compliance documentation is accurate and complete.

Documentation Author Name:

Documentation Author Signature:

Company:

Wayne Seward

Bear Technologies Consulting Inc.

Signature Date:

2023-01-17 12:07:59

CEA/HERS Certification Identification (if applicable):

R19-04-30011

Phone:

760-635-2327

RESPONSIBLE PERSON'S DECLARATION STATEMENT

I, I certify the following under penalty of perjury, under the laws of the State of California:

- I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design identified on this Certificate of Compliance.
- I certify that the energy features and performance specifications identified on this Certificate of Compliance conform to the requirements of Title 24, Part 1 and Part 6 of the California Code of Regulations.
- The building design features or system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations, plans and specifications submitted to the enforcement agency for approval with this Building permit application.

Responsible Designer Name:

Responsible Designer Signature:

Bar M Smith

Bart M Smith

Company:

DZN Partners

Date Signed:

2023-01-17 12:08:33

License:

C-22557

Address:

682 2nd Street

City/State/Zip:

Encinitas, CA 92024

City/State/Zip:

Encinitas, CA 92024

Digitally signed by CaCERTS. This digital signature is provided in order to secure the content of this registered document, and in no way implies

Registration Provider responsibility for the accuracy of the information.

Registration Number:

223-P010006674A-000-000-0000000000

Registration Date/Time:

2023-01-17 12:08:33

HERS Provider:

CaCERTS Inc.

CA Building Energy Efficiency Standards - 2022 Residential Compliance

Report Version: 2022.0.000

Report Generated: 2023-01-14 17:21:06

Schema Version: rev 20220901



Easy to Verify at CaCERTS.com



2022 Single-Family Residential Mandatory Requirements Summary

§ 150.0(h)(1):	Space Conditioning System Airflow Rate and Fan Efficiency. Space conditioning systems that use ducts to supply cooling must have a hole for the placement of a static pressure probe, or a permanently installed static pressure probe in the supply plenum. Airflow must be 2-350 CFM per ton of nominal cooling capacity, and an air-handling unit fan efficiency ≤ 0.45 watts per CFM for gas furnace air handlers and ≤ 0.36 watts per CFM for air handlers. Small duct high velocity systems must provide an airflow ≥ 250 CFM per ton of nominal cooling capacity, and an air-handling unit fan efficiency ≤ 0.42 watts per CFM. Field verification testing is required in accordance with Reference Residential Appendix RA3.3.
Ventilation and Indoor Air Quality:	
§ 150.0(i):	Requirements for Ventilation and Indoor Air Quality. All dwelling units must meet the requirements of ASHRAE Standard 62.2, Ventilation and Acceptable Indoor Air Quality in Residential Buildings subject to the amendments specified in § 150.0(i)(1).
§ 150.0(i)(1B):	Central Fan Integrated (CFI) Ventilation Systems. Continuous operation of CFI air handlers is not allowed to provide the whole-dwelling unit ventilation airflow required per § 150.0(i)(1C). A motorized damper(s) must be installed on the ventilation duct(s) that prevents air flow through the space conditioning duct system when the damper(s) is closed and uncontrolled per § 150.0(i)(1B)(a)(CFI) ventilation systems must have controls that track outdoor air ventilation run time, and either open or close the motorized damper(s) for compliance with § 150.0(i)(1C).
§ 150.0(i)(1C):	Whole-Dwelling Unit Mechanical Ventilation for Single-Family Detached and Townhouses. Single-family detached dwelling units, and attached dwelling units not sharing ceilings or floors with other dwelling units, occupiable spaces, public garages, or commercial spaces must have mechanical ventilation airflow specified in § 150.0(i)(1C)(i).
§ 150.0(i)(1D):	Local Mechanical Exhaust. Kitchens and bathrooms must have local mechanical exhaust; nonvented kitchens must have demand-controlled exhaust system meeting requirements of § 150.0(i)(1G); enclosed kitchens and bathrooms can use demand-controlled or continuous exhaust meeting § 150.0(i)(1G)(i). Airflow must be measured by the installer per § 150.0(i)(1G), and rated for sound per § 150.0(i)(1G)(i).
§ 150.0(i)(1H):	Airflow Measurement and Sound Ratings of Whole-Dwelling Unit Ventilation Systems. The airflow required per § 150.0(i)(1C) must be measured by using a flow hood, flow grid, or other airflow measuring device at the fan's inlet or outlet terminal(s) per Reference Residential Appendix RA3.7. Whole-dwelling unit ventilation systems must be rated for sound per ASHRAE 62.2 § 7.2 at no less than the minimum airflow rate required by § 150.0(i)(1C).
§ 150.0(i)(2):	Field Verification and Diagnostic Testing. Whole-dwelling unit ventilation airflow, vented range hood airflow and sound rating, and HVI and ERV fan efficiency must be verified in accordance with Reference Residential Appendix RA3.7. Vented range hoods must be verified per Reference Residential Appendix RA3.7.4.3 to confirm if it is rated by HVI or ASHRAE to comply with the airflow rates and sound requirements per § 150.0(i)(1G).
Pool and Spa Systems and Equipment:	
§ 110.4(a):	Certification by Manufacturers. Any pool or spa heating system or equipment must be certified to have all of the following: compliance with the Appliance Efficiency Regulations and listing in IAPCS; an on/off switch mounted outside the heater that allows shutting off the heater without adjusting the thermostat setting; a permanent weatherproof plate or card with operating instructions; and must not use electric resistance heating.
§ 110.4(b)(1):	Piping. Any pool or spa heating system or equipment must be installed with at least 36 inches of pipe between the filter and the heater, or dedicated supply and return lines, or built-in or built-up connections to allow for future solar heating.
§ 110.4(b)(2):	Covers. Outdoor pools or spas that have a heat pump or gas heater must have a cover.
§ 110.4(b)(3):	Directional Inlets and Time Switches for Pools. Pools must have directional inlets that adequately mix the pool water, and a time switch that will allow all pumps to be set or programmed to run only during off-peak electric demand periods.
§ 110.5:	Pilot Light. Natural gas pool and spa heaters must not have a continuously burning pilot light.
§ 150.0(p):	Pool Systems and Equipment Installation. Residential pool pool systems or equipment must meet the specified requirements for pump sizing, flow rate, piping, filters, and valves.
Lighting:	
§ 110.9:	Lighting Controls and Components. All lighting control devices and systems, ballasts, and luminaires must meet the applicable requirements of § 110.9.
§ 150.0(k)(1A):	Luminaire Efficacy. All installed luminaires must meet the requirements in Table 150.0-A, except lighting integral to exhaust fans, kitchen range hoods, bath vanity mirrors, and garage door openers, navigation lighting less than 5 watts, and lighting integral to drawers, cabinets, and linen closets with at least 45 lumens per watt.
§ 150.0(k)(1B):	Screw-based luminaires. Screw-based luminaires must contain lamps that comply with Reference Joint Appendix JAS.
§ 150.0(k)(1C):	Recessed Downlight Luminaires in Ceilings. Luminaires recessed into ceilings must not contain screw-based sockets, must be airtight, and must be sealed with a gasket or caulk. California Electrical Code § 410.116 must also be met.
§ 150.0(k)(1D):	Light Sources in Enclosed or Recessed Luminaires. Lamps and other replaceable light sources that are not compliant with the JAS elevated temperature requirements, including marking requirements, must not be installed in enclosed or recessed luminaires.
§ 150.0(k)(1E):	Blank Electrical Boxes. The number of electrical boxes that are more than two feet above the finished floor and do not contain a luminaire or other device shall be no more than the number of bedrooms. These boxes must be served by a dimmer, vacancy sensor control, low voltage wiring, or fan speed control.
§ 150.0(k)(1F):	Lighting Integral to Exhaust Fans. Lighting integral to exhaust fans (except when installed by the manufacturer in kitchen exhaust hoods) must meet the applicable requirements of § 150.0(k).

5/6/22



2022 Single-Family Residential Mandatory Requirements Summary

§ 150.0(k)(1G):	Screw-based luminaires. Screw-based luminaires must contain lamps that comply with Reference Joint Appendix JAS.
§ 150.0(k)(1H):	Light Sources in Enclosed or Recessed Luminaires. Lamps and other replaceable light sources that are not compliant with the JAS elevated temperature requirements, including marking requirements, must not be installed in enclosed or recessed luminaires.
§ 150.0(k)(1I):	Light Sources in Drawers, Cabinets, and Linen Closets. Light sources internal to drawers, cabinets or linen closets are not required to comply with Table 150.0-A or be controlled by vacancy sensors provided that they are not to consume no more than 5 watts of power, emit no more than 150 lumens, and are equipped with controls that automatically turn the lighting off when the drawer, cabinet or linen closet is closed.
§ 150.0(k)(2A):	Interior Switches and Controls. All forward phase cut dimmers used with LED light sources must comply with NEMA SSL 7A.
§ 150.0(k)(2B):	Accessible Controls. Lighting must have readily accessible wall-mounted controls that allow the lighting to be manually turned on and off.
§ 150.0(k)(2C):	Multiple Controls. Controls must not be a dimmer, occupancy sensor, or vacancy sensor function if the dimmer or sensor is installed to comply with § 150.0(k).
§ 150.0(k)(2D):	Mandatory Requirements. Lighting controls must comply with the applicable requirements of § 110.9.
§ 150.0(k)(2E):	Energy Management Control Systems. An energy management control system (EMCS) may be used to comply with dimming, occupancy, and control requirements if it provides the functionality of the specified control per § 110.9 and the physical controls specified in § 150.0(k)(2A).
§ 150.0(k)(2F):	Automatic Shutoff Controls. In bathrooms, garages, laundry rooms, utility rooms and walk-in closets, at least one installed luminaire must be controlled by an occupancy or vacancy sensor providing automatic off functionality. Lighting inside drawers and cabinets with opaque fronts or doors must have controls that turn the light off when the drawer or door is closed.
§ 150.0(k)(2G):	Dimmers. Lighting in habitable spaces (e.g., living rooms, dining rooms, kitchens, and bedrooms) must have readily accessible wall-mounted dimming controls that allow the lighting to be manually adjusted up and down. Forward phase cut dimmers controlling LED light sources in these spaces must comply with NEMA SSL 7A.
§ 150.0(k)(2H):	Independent Controls. Integrated lighting of exhaust fans shall be controlled independently from the fans. Lighting under cabinets or shelves, lighting in display cabinets, and switched outlets must be controlled separately from ceiling-installed lighting.
§ 150.0(k)(3A):	Residential Outdoor Lighting. For single-family residential buildings, outdoor lighting permanently mounted to a residential building, or to other buildings on the same lot, must have a manual on/off switch and either a photocell and motion sensor or automatic time switch control or an astronomical time clock. An energy management control system that provides the specified control functionality and meets all applicable requirements may be used to meet these requirements.
§ 150.0(k)(4):	Internally Illuminated Address Signs. Internally illuminated address signs must either comply with § 140.8 or consume no more than 5 watts of power.
§ 150.0(k)(5):	Residential Garages for Eight or More Vehicles. Lighting for residential parking garages for eight or more vehicles must comply with the applicable requirements for nonresidential garages in §§ 110.9, 130.0, 130.1, 130.4, 140.6, and 141.0.
Solar Readiness:	
§ 110.10(a):	Single-Family Residences. Single-family residences located in subdivisions with 10 or more single-family residences and where the application for a tentative subdivision map for the residences has been deemed complete and approved by the enforcement agency, which do not have a photovoltaic system installed, must comply with the requirements of § 110.10(a)(1).
§ 110.10(b):	Minimum Solar Zone Area. The solar zone must have a minimum table area as described below. The solar zone must comply with access, pathway, smoke ventilation, and spacing requirements as specified in Table 24, Part 4 or other parts of Title 24 or in any requirements adopted by a local jurisdiction. The solar zone total area must be comprised of areas that have no dimension less than 5 feet and are no less than 60 square feet each for buildings with roof areas less than or equal to 10,000 square feet or no less than 150 square feet each for buildings with roof areas greater than 10,000 square feet. For single-family residences, the solar zone must be located on the roof or overhang of the building and have a total area no less than 250 square feet.
§ 110.10(b)(1A):	Azimuth. All sections of the solar zone located on steep-sloped roofs must have an azimuth between 90-300° of true north.
§ 110.10(b)(2):	Shading. The solar zone must not contain any obstructions, including but not limited to: vents, chimneys, architectural features, and roof-mounted equipment.
§ 110.10(b)(3A):	Shading. Any obstruction located on the roof or any other part of the building that projects above a solar zone must be located at least twice the horizontal distance of the height of the obstruction between the highest point of the obstruction and the horizontal projection of the nearest point of the solar zone, measured in the vertical plane.
§ 110.10(b)(3B):	Structural Design Loads on Construction Documents. For areas of the roof designated as a solar zone, the structural design loads for roof dead load and roof live load must be clearly indicated on the construction documents.
§ 110.10(c):	Interconnection Pathways. The construction documents must indicate a location reserved for inverters and metering equipment and a pathway reserved for routing of conduct from the solar zone to the point of interconnection with the electrical service, and for single-family residences and central water-heating systems, a pathway reserved for routing plumbing from the solar zone to the water-heating system. Documentation. A copy of the construction documents or a comparable document indicating the information from § 110.10(b)(3) must be provided to the occupant.
§ 110.10(d):	Main Electrical Service Panel. The main electrical service panel must have a minimum busbar rating of 200 amps.
§ 110.10(e):	Main Electrical Service Panel. The main electrical service panel must have a reserved space to allow for the installation of a double pole circuit breaker for a future solar electric installation. The reserved space must be permanently marked as "For Future Solar Electric."

Electric and Energy Storage Ready:

5/6/22



2022 Single-Family Residential Mandatory Requirements Summary

§ 150.0(a):	Energy Storage System (ESS) Ready. All single-family residences must meet all of the following: Either ESS-ready interconnection equipment with backed-up capacity of 60 amps or more and four or more ESS-supplied branch circuits, or a dedicated roomway from the main service to a subpanel that supplies the branch circuits in § 150.0(a), at least four branch circuits must be identified and have their source collocated at a single panelboard suitable to be supplied by the ESS, with one circuit supplying the refrigerator; one lighting circuit near the primary exit, and one circuit supplying a sleeping room receptacle outlet; main panelboard must have a minimum busbar rating of 225 amps; sufficient space must be reserved to allow future installation of a system isolation equipment/transfer switch within 3' of the main panelboard, with receptacles installed between the panelboard and the switch location to allow the connection of backup power source.
§ 150.0(b):	Heat Pump Space Heater Ready. Systems using gas or propane furnaces to serve individual dwelling units must include: A dedicated unobstructed 240V branch circuit wiring installed within 3' of the furnace with circuit conductors rated at least 30 amps with the blank cover identified as "240V ready"; and a reserved main electrical service panel space to allow for the installation of a double pole circuit breaker permanently marked as "For Future 240V use."
§ 150.0(c):	Electric Cooktop Ready. Systems using gas or propane cooktops to serve individual dwelling units must include: A dedicated unobstructed 240V branch circuit wiring installed within 3' of the cooktop with circuit conductors rated at least 30 amps with the blank cover identified as "240V ready"; and a reserved main electrical service panel space to allow for the installation of a double pole circuit breaker permanently marked as "For Future 240V use."
§ 150.0(d):	Electric Clothes Dryer Ready. Clothes dryer locations with gas or propane plumbing to serve individual dwelling units must include: A dedicated unobstructed 240V branch circuit wiring installed within 3' of the dryer location with circuit conductors rated at least 30 amps with the blank cover identified as "240V ready"; and a reserved main electrical service panel space to allow for the installation of a double pole circuit breaker permanently marked as "For Future 240V use."

*Exceptions may apply.

General Notes



R19-04-30011
NR19-04-30020

TITLE 24, PART 6 ENERGY COMPLIANCE DOCUMENTATION

No.	Revision/Issue	Date

Firm Name and Address



BEAR TECHNOLOGIES CONSULTING, INC.
3431 DON ARTURO DRIVE,
CARLSBAD, CALIFORNIA 92010
(760) 635-2327
wayne@beartechconsulting.com
http://www.beartechconsulting.com

Project Name and Address

ENCINITAS PRADU - 1 BEDROOM PLAN C
ENCINITAS PRADU STREET
ENCINITAS, CALIFORNIA 92024

HVAC SYSTEM HEATING AND COOLING LOADS SUMMARY										
Project Name Encinitas PRADU - 1-Bedroom Plan C						Date 1/17/2023				
System Name Ductless Mini-Split						Floor Area 499				
ENGINEERING CHECKS			SYSTEM LOAD							
Number of Systems			1		COIL COOLING PEAK				COIL HTG. PEAK	
Heating System					CFM	Sensible	Latent	CFM	Sensible	
Output per System			28,000		Total Room Loads				10,884	
Total Output (Btuh)			28,000		Return Vented Lighting				0	
Output (Btuh/sqft)			56.1		Return Air Ducts				0	
Cooling System					Return Fan				0	
Output per System			24,000		Ventilation				9,414	
Total Output (Btuh)			24,000		Supply Fan				-596	
Total Output (Tons)			2.0		Supply Air Ducts				0	
Total Output (Btuh/sqft)			48.1		TOTAL SYSTEM LOAD				19,702	
Total Output (sqft/Ton)			249.5							
Air System										
CFM per System			800		HVAC EQUIPMENT SELECTION					
Airflow (cfm)			800		Ductless Mini-Split				21,922	
Airflow (cfm/sqft)			1.60							
Airflow (cfm/Ton)			400.0							
Outside Air (%)			31.2%		Total Adjusted System Output				21,922	
Outside Air (cfm/sqft)			0.50		(Adjusted for Peak Design conditions)					
Note: values above given at ARI conditions						TIME OF SYSTEM PEAK		Aug 3 PM		
HEATING SYSTEM PSYCHROMETRICS (Airstream Temperatures at Time of Heating Peak)						Jan 1 AM				
COOLING SYSTEM PSYCHROMETRICS (Airstream Temperatures at Time of Cooling Peak)										

c

HVAC SYSTEM HEATING AND COOLING LOADS SUMMARY											
Project Name Encinitas PRADU - 1-Bedroom Plan B						Date 1/17/2023					
System Name Ductless Mini-Split						Floor Area 499					
ENGINEERING CHECKS			SYSTEM LOAD								
Number of Systems			1		COIL COOLING PEAK				COIL HTG. PEAK		
Heating System					CFM	Sensible	Latent	CFM	Sensible		
Output per System			28,000		Total Room Loads		565		14,426		
Total Output (Btuh)			28,000		Return Vented Lighting		0		0		
Output (Btuh/sqft)			56.1		Return Air Ducts		0		0		
Cooling System					Return Fan		0		0		
Output per System			24,000		Ventilation		250		2,421		
Total Output (Btuh)			24,000		Supply Fan		596		-596		
Total Output (Tons)			2.0		Supply Air Ducts		0		0		
Total Output (Btuh/sqft)			48.1		TOTAL SYSTEM LOAD		17,444		5,290		
Total Output (sqft/Ton)			249.5						19,494		
Air System					HVAC EQUIPMENT SELECTION						
CFM per System			800		Ductless Mini-Split		23,445		0		
Airflow (cfm)			800						21,922		
Airflow (cfm/sqft)			1.60								
Airflow (cfm/Ton)			400.0								
Outside Air (%)			31.2%		Total Adjusted System Output		23,445		0		
Outside Air (cfm/sqft)			0.50		(Adjusted for Peak Design conditions)						
Note: values above given at ARI conditions						TIME OF SYSTEM PEAK		Aug 3 PM		Jan 1 AM	
HEATING SYSTEM PSYCHROMETRICS (Airstream Temperatures at Time of Heating Peak)											
COOLING SYSTEM PSYCHROMETRICS (Airstream Temperatures at Time of Cooling Peak)											

b

HVAC SYSTEM HEATING AND COOLING LOADS SUMMARY									
Project Name Encinitas PRADU - 1-Bedroom Plan A							Date 1/17/2023		
System Name Ductless Mini-Split							Floor Area 499		
ENGINEERING CHECKS			SYSTEM LOAD						
Number of Systems		1		COIL COOLING PEAK			COIL HTG. PEAK		
Heating System				CFM	Sensible	Latent	CFM	Sensible	
Output per System		28,000		Total Room Loads			565 14,425 1,746		
Total Output (Btuh)		28,000		Return Vented Lighting			0		
Output (Btuh/sqft)		56.1		Return Air Ducts			0		
Cooling System				Return Fan			0		
Output per System		24,000		Ventilation			250 2,421 3,543		
Total Output (Btuh)		24,000		Supply Fan			596		
Total Output (Tons)		2.0		Supply Air Ducts			0		
Total Output (Btuh/sqft)		48.1		TOTAL SYSTEM LOAD			17,442 5,290		
Total Output (sqft/Ton)		249.5							
Air System				HVAC EQUIPMENT SELECTION					
CFM per System		800		Ductless Mini-Split			23,445 0		
Airflow (cfm)		800					21,922		
Airflow (cfm/sqft)		1.60							
Airflow (cfm/Ton)		400.0							
Outside Air (%)		31.2%		Total Adjusted System Output			23,445 0		
Outside Air (cfm/sqft)		0.50		(Adjusted for Peak Design conditions)					
Note: values above given at ARI conditions				TIME OF SYSTEM PEAK			Aug 3 PM		Jan 1 AM
HEATING SYSTEM PSYCHROMETRICS (Airstream Temperatures at Time of Heating Peak)									
<div>35 °F59 °F60 °F85 °F</div> <div>Outside Air 250 cfm</div> <div>Supply Fan 800 cfm</div> <div>Heating Coil</div> <div>85 °F</div> <div>ROOM</div> <div>70 °F</div>									
COOLING SYSTEM PSYCHROMETRICS (Airstream Temperatures at Time of Cooling Peak)									
<div>83 / 67 °F77 / 62 °F77 / 62 °F50 / 49 °F</div> <div>Outside Air 250 cfm</div> <div>Supply Fan 800 cfm</div> <div>Cooling Coil</div> <div>50 / 49 °F</div> <div>ROOM</div> <div>74 / 59 °F</div> <div>41.5%</div>									

a

BY USING THESE PERMIT READY CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE THE CITY OF ENCINITAS AND THE ARCHITECT WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.



682 SECOND ST

ENCINITAS, CA

(760) 753 2464

DZNPARTNERS.COM

1 BEDROOM
PRADU

CITY: ENCINITAS

JOB: 202241R

HVAC SYSTEM
ENERGY
SUMMARIES

T-05